

**UNITED STATES OF AMERICA
BEFORE THE
FEDERAL ENERGY REGULATORY COMMISSION**

**Klamath River Renewal Corporation
PacifiCorp**

**Project Nos. 14803-001;
2082-063**

**AMENDED APPLICATION FOR SURRENDER OF LICENSE
FOR MAJOR PROJECT AND REMOVAL OF PROJECT WORKS**

**EXHIBIT P
Water Supply Management Plan
(Amended December 15, 2021)**



**Lower Klamath Project
FERC Project No. 14803**

**Water Supply
Management Plan**

**Klamath River Renewal Corporation
2001 Addison Street, Suite 317
Berkeley, CA 94704**

December 2021

This page intentionally left blank.

Table of Contents

1.0	Introduction.....	1
2.0	Regulatory Context.....	7
2.1	Organizational Structure.....	7
2.2	Specific Regulatory Interests.....	7
2.3	Results of Consultation since February 2021.....	8
2.4	Regulatory Approval.....	8
3.0	Reporting.....	8

List of Tables

Table 2-1. Lower Klamath River Management Plans	7
Table 2-2. Results of Consultation	8

List of Figures

Figure 1-1. Lower Klamath Project Location	2
Figure 1-2. J.C. Boyle Development Facility Details	3
Figure 1-3. Copco No.1 Development Facility Details.....	4
Figure 1-4. Copco No.2 Development Facility Details.....	5
Figure 1-5. Iron Gate Development Facility Details.....	6

Appendices

Appendix A	California Water Supply Management Plan
Appendix B	California Public Drinking Water Management Plan
Appendix C	Oregon Groundwater Well Management Plan
Appendix D	Fire Management Plan
Appendix E	Consultation Record

1.0 Introduction

The Lower Klamath Project (FERC No. 14803) consists of four hydroelectric developments on the Klamath River: J.C. Boyle, Copco No. 1, Copco No. 2, and Iron Gate (Figure 1-1). Specifically, the reach between J.C. Boyle dam and Iron Gate dam is known as the Hydroelectric Reach. In September of 2016, the Klamath River Renewal Corporation (Renewal Corporation) filed an *Application for Surrender of License for Major Project and Removal of Project Works*, FERC Project Nos. 2082-063 & 14803-001 (License Surrender). The Renewal Corporation filed the License Surrender Application as the dam removal entity for the purpose of implementing the Klamath River Hydroelectric Settlement (KHSA). In November of 2020, the Renewal Corporation filed its Definite Decommissioning Plan (DDP) as Exhibits A-1 and A-2 to its Amended License Surrender Application (ALSA). The DDP is the Renewal Corporation's comprehensive plan to physically remove the Lower Klamath Project and achieve a free-flowing condition and volitional fish passage, site remediation and restoration, and avoidance of adverse downstream impacts (Proposed Action). The Limits of Work is a geographic area that encompasses dam removal and restoration related activities associated with the Proposed Action. The Limits of Work may extend beyond the Federal Energy Regulatory Commission (Commission) boundary associated with the Lower Klamath Project where specifically noted.

The Proposed Action includes the deconstruction of the J.C. Boyle Dam and Powerhouse (Figure 1-2), Copco No. 1 Dam and Powerhouse (Figure 1-3), Copco No. 2 Dam and Powerhouse (Figure 1-4), and Iron Gate Dam and Powerhouse (Figure 1-5), as well as associated features. Associated features vary by development, but generally include powerhouse intake structures, embankments and sidewalls, penstocks and supports, decks, piers, gatehouses, fish ladders and holding facilities, pipes and pipe cradles, spillway gates and structures, diversion control structures, aprons, sills, tailrace channels, footbridges, powerhouse equipment, distribution lines, transmission lines, switchyards, original cofferdams, portions of the Iron Gate Fish Hatchery, residential facilities, and warehouses. Facility removal will be completed within an approximately 20-month period.

This Water Supply Management Plan identifies measures to protect water supply and beneficial uses that the Renewal Corporation will implement as part of the Proposed Action. The Renewal Corporation has prepared 16 Management Plans for the Commission's review and approval as conditions of a License Surrender Order. These Management Plans were developed in consultation with federal, state, and county governments and tribes.

In February 2021, the Renewal Corporation filed the 16 Management Plans with the Commission. Since that time, the Renewal Corporation has undertaken further consultation, resulting in material revisions. Table 2-2 herein shows the material revisions to the February 2021 version of this Water Supply Management Plan. An updated Consultation Record for the Water Supply Management Plan is included as **Error! Reference source not found.**




Figure 1-1. Lower Klamath Project Location




Figure 1-2. J.C. Boyle Development Facility Details




Figure 1-3. Copco No.1 Development Facility Details




Figure 1-4. Copco No.2 Development Facility Details




Figure 1-5. Iron Gate Development Facility Details

2.0 Regulatory Context

The Water Supply Management Plan is one of 16 Management Plans implementing the DDP.

Table 2-1. Lower Klamath River Management Plans

1. Aquatic Resources Management Plan	9. Remaining Facilities Plan
2. Construction Management Plan	10. Reservoir Area Management Plan
3. Erosion and Sediment Control Plan	11. Reservoir Drawdown and Diversion Plan
4. Hatcheries Management and Operations Plan	12. Sediment Deposit Remediation Plan
5. Health and Safety Plan	13. Terrestrial and Wildlife Management Plan
6. Historic Properties Management Plan	14. Waste Disposal and Hazardous Materials Management Plan
7. Interim Hydropower Operations Plan	15. Water Quality Monitoring and Management Plan
8. Recreation Facilities Plan	16. Water Supply Management Plan

2.1 Organizational Structure

The Water Supply Management Plan identifies measures the Renewal Corporation will implement to protect water supply. These proposed measures are part of the Proposed Action. Specifically, the Water Supply Management Plan includes an updated Consultation Record and four sub-plans, included amongst the Appendices identified below.

- Appendix A: California Water Supply Management Plan
- Appendix B: California Public Drinking Water Management Plan
- Appendix C: Oregon Groundwater Well Management Plan
- Appendix D: Fire Management Plan
- Appendix E: Consultation Record

2.2 Specific Regulatory Interests

The Renewal Corporation considered the following regulatory interests in the development of the Water Supply Management Plan:

- California Section 401 Water Quality Certification
- Oregon Section 401 Water Quality Certification
- California Department of Fish and Wildlife Memorandum of Understanding
- California Environmental Quality Act, Final Environmental Impact Report
- Siskiyou County

- Cal Fire
- Oregon Department of Forestry
- Oregon Memorandum of Understanding

2.3 Results of Consultation since February 2021

The Renewal Corporation has revised the February 2021 version of this plan, on the basis of further consultation, in the following material respects.

Table 2-2. Results of Consultation

SUB-PLAN	CHANGES TO FEBRUARY 2021 VERSION
Appendix A: California Water Supply Management Plan	<ul style="list-style-type: none">• The Renewal Corporation has proposed to monitor groundwater elevations prior to, during, and following drawdown at two existing PacifiCorp groundwater wells subject to confirmation with PacifiCorp and install two additional monitoring wells at Copco No. 1 Reservoir.
Appendix B: California Public Drinking Water Management Plan	<ul style="list-style-type: none">• No material revisions.
Appendix C: Oregon Groundwater Well Management Plan	<ul style="list-style-type: none">• No material revisions.
Appendix D: Fire Management Plan	<ul style="list-style-type: none">• Removed proposed boat ramp at the location of the Copco No. 2 Powerhouse.

2.4 Regulatory Approval

The Renewal Corporation will implement the Reservoir Drawdown and Diversion Plan as approved by the Commission in the License Surrender Order. The Renewal Corporation will obtain and report to the Commission any required approvals from other agencies.

3.0 Reporting

By April 15 of each year, the Renewal Corporation will prepare and submit to the Commission an Annual Report which will include information pertaining to implementation of the Water Supply Management Plan.

Appendix A

California Water Supply Management Plan



**Lower Klamath Project
FERC Project No. 14803**

California Water Supply Management Plan

**Klamath River Renewal Corporation
2001 Addison Street, Suite 317
Berkeley, CA 94704**

**Prepared by:
Camas LLC
680 G Street, Suite C
Jacksonville, OR 97530**

December 2021

This page intentionally left blank.

Table of Contents

1.0	Introduction.....	1
1.1	Purpose of Water Supply Management Plan	1
1.2	Relationship to Other Management Plans.....	1
2.0	Klamath River and Fall Creek Surface Water Diversion Supplies	1
2.1	Identification of Surface Water Diversion Supplies	1
2.2	Surface Water Diversions.....	6
2.3	Schedule to Address Impacts to Surface Water Diversions	6
2.3.1	Pre-drawdown	6
2.3.2	During and Post-drawdown.....	6
3.0	Groundwater	7
3.1	Background	7
3.2	Groundwater Elevation Monitoring	7
3.3	Local Impact Mitigation Fund	8
4.0	Fire Management	8
5.0	Annual Water Supply Management Report.....	8
5.1	Surface Water Diversions.....	9
5.2	Groundwater.....	9
5.3	Fire Management	9
6.0	References	9

List of Tables

Table 2.1. Klamath River - Active Surface Water Diversions	2
Table 2.2. Fall Creek - Active Surface Water Diversions	4

List of Figures

Figure 2-1. Points of Diversion on the Klamath River and Fall Creek	5
---	---

1.0 Introduction

The California Water Supply Management Plan is a subplan of the Water Supply Management Plan that will be implemented as part of the Proposed Action for the Lower Klamath Project.

1.1 Purpose of Water Supply Management Plan

The purpose of the California Water Supply Management Plan is to state the measures the Klamath River Renewal Corporation (Renewal Corporation) will implement to protect water supplies and beneficial uses of waters affected by the Proposed Action in California. Water supplies and beneficial uses subject to this plan include non-potable surface water diversions sourced from the Klamath River downstream of Iron Gate Dam and groundwater within the immediate surrounding vicinity of Copco No. 1 Reservoir.

1.2 Relationship to Other Management Plans

The California Water Supply Management Plan is supported by elements of the following management plans for effective implementation: Water Supply Management Plan (sub-plans) and the Hatcheries Management and Operations Plan. So as to not duplicate information, elements from these other management plans are not repeated herein but are, where appropriate, referred to in this California Water Supply Management Plan.

2.0 Klamath River and Fall Creek Surface Water Diversion Supplies

This section addresses the assessment and protection of surface water supplies diverted from the Klamath River. The quantity of surface water in the Klamath River downstream of the Project will not be affected as a result of the Proposed Action because the Lower Klamath Project reservoirs are not designed or operated as seasonal water storage reservoirs. Klamath River flows are established primarily from the United States Bureau of Reclamation water releases from Upper Klamath Lake at Link River Dam and from tributary inflows. Modeling results suggest the Klamath River flows will change very minimally as a result of dam removal (USBR 2012), so loss or reduction of water supply due to low river flow is not addressed by this plan.

2.1 Identification of Surface Water Diversion Supplies

According to the California State Water Resources Control Board (SWRCB) Division of Drinking Water (DDW) Electronic Water Rights Information Management System (eWRIMS), there are 22 active surface water diversions on the mainstem Klamath River and Lower Klamath Project reservoirs (Table 2.1) and two active surface water diversions on Fall Creek (Table 2.2) (eWRIMS 2020). Figure 2-1 presents the locations of the surface water diversions.

Table 2.1. Klamath River - Active Surface Water Diversions

APPLICATION NUMBER	COUNTY	DIVERSION TYPE	DIRECT DIVERSION AMOUNT	WATER RIGHT TYPE	STATUS	ENTITY TYPE	PRIMARY OWNER
A019478	Siskiyou	Diversion to Storage	0.1 cfs ²	Appropriative	Licensed	Government (State/Municipal)	Klamath River Country Estates Owners Association Inc
S016524	Siskiyou	Direct Diversion	126.8	Statement of Diversion and Use	Claimed	Corporation	R- Ranch POA
S000708	Siskiyou	Direct Diversion	0	Statement of Diversion and Use	Claimed	Government (State/Municipal)	Klamath River Country Estates Owners Association Inc
D031134R	Siskiyou	Diversion to Storage	4500 gpd ³	Registration Domestic	Registered	Individual	Richard K. Kleinkopf
S023523	Siskiyou	- ¹	2.67 cfs	Statement of Diversion and Use	Claimed	Individual	Rex Cozzalio
S027669	Siskiyou	-	10.5 cfs	Statement of Diversion and Use	Claimed	Individual	Clyde Greco Jr.
S021731	Siskiyou	-	0.11 cfs	Statement of Diversion and Use	Claimed	Individual	David L. Marsh
S027657	Siskiyou	-	-	Statement of Diversion and Use	Claimed	Individual	Michael Yager
S014586	Siskiyou	Diversion to Storage	0.11 cfs	Statement of Diversion and Use	Claimed	Individual	Frederick A. Soued
S023924	Siskiyou	-	0.4 cfs	Statement of Diversion and Use	Claimed	Individual	Shirley Fisher
S014788	Siskiyou	Diversion to Storage	1.1 cfs	Statement of Diversion and Use	Claimed	Individual	Richard L. Jennings
S021741	Siskiyou	-	0	Statement of Diversion and Use	Claimed	Individual	Chris Hodgson

APPLICATION NUMBER	COUNTY	DIVERSION TYPE	DIRECT DIVERSION AMOUNT	WATER RIGHT TYPE	STATUS	ENTITY TYPE	PRIMARY OWNER
S021740	Siskiyou	-	0	Statement of Diversion and Use	Claimed	Individual	Chris Hodgson
S016753	Siskiyou	Direct Diversion	0	Statement of Diversion and Use	Claimed	Individual	Mathew Connelly
S025997	Siskiyou	-	-	Statement of Diversion and Use	Claimed	Individual	Benjamin Solnick
S020606	Siskiyou	-	0	Statement of Diversion and Use	Claimed	Individual	David Davey
S020130	Siskiyou	-	0	Statement of Diversion and Use	Claimed	Individual	David Davey
S010021	Siskiyou	Direct Diversion	100 gpd	Statement of Diversion and Use	Claimed	Individual	Steven G. Moore
S013406	Siskiyou	Diversion to Storage	7200 gpd	Statement of Diversion and Use	Claimed	Individual	Carlos Zepeda
S025885	Siskiyou	-	14 gpm ⁴	Statement of Diversion and Use	Claimed	Individual	Joseph Munday
S014172	Siskiyou	Diversion to Storage	0.33 cfs	Statement of Diversion and Use	Claimed	Individual	Robert Rainey
A021640	Humboldt	Diversion to Storage	0.13 cfs	Appropriative	Licensed	Individual	Harry C. Mollier

Notes:

¹ This table includes information provided by the eWRIMS database. If a cell is blank, no information was available.

² cfs = cubic feet per second

³ gpd = gallons per day

⁴ gpm = gallons per minute


Table 2.2. Fall Creek - Active Surface Water Diversions

APPLICATION NUMBER	COUNTY	DIVERSION TYPE	DIRECT DIVERSION AMOUNT	WATER RIGHT TYPE	STATUS	ENTITY TYPE	PRIMARY OWNER
A022551	Siskiyou	- ¹	15 cfs ²	Appropriative	Permitted	Government (State/Municipal)	City of Yreka
A025896	Siskiyou	Direct Diversion	10 cfs	Appropriative	Licensed	Government (State/Municipal)	California Department of Fish and Wildlife

Notes:

¹ This table includes information provided by the eWRIMS database. If a cell is blank, no information was available.

² cfs = cubic feet per second



Disclaimer: This document has been prepared based on information provided by others as cited in the Notes section. McMillen Jacobs Associates has not verified the accuracy and/or completeness of this information and shall not be responsible for any errors or omissions which may be incorporated herein as a result. McMillen Jacobs Associates assumes no responsibility for data supplied in electronic format, and the recipient accepts full responsibility for verifying the accuracy and completeness of the data.

Figure 2-1. Points of Diversion on the Klamath River and Fall Creek

2.2 Surface Water Diversions

The Renewal Corporation will implement the following measures to protect surface water diversion intakes and irrigation pumps from impacts associated with release of reservoir sediments. The Renewal Corporation will assist with modifications (pre-drawdown) and/or repairs to pumps (during and post-drawdown) for diverters who agree to have their system assessed for potential effects. The schedule and procedures for addressing impacts to surface water diverters is described in Section 2.3.

2.3 Schedule to Address Impacts to Surface Water Diversions

2.3.1 Pre-drawdown

No less than six months prior to drawdown, the Renewal Corporation will contact the water right holders via mail listed in Table 2.1 and Table 2.2 to determine if the diverter is interested in having their system evaluated for potential impacts. The Renewal Corporation will send a letter to each water right holder, which will include the following information:

- A brief overview of the Proposed Action.
- A schedule for drawdown and the anticipated effects on surface water diversions from suspended sediment and turbidity.
- A proposal to provide a technical evaluation of the intake/pump system(s) currently in place.
- Contact information for the Renewal Corporation.
- A due date (three months following issuance of letter) for responses to have the participant's system evaluated.
- Instructions on how and when to initiate communication with the Renewal Corporation to be eligible to receive assistance.

If a response is received within three months of issuance of the letter, the Renewal Corporation will perform a technical evaluation of the diversion system, in cooperation with the water right holder. The evaluation will include an assessment to determine the likelihood of sediment inundation and/or interruption from Proposed Action-related activities and the appropriate measures to be implemented by the Renewal Corporation. If the impact analysis determines the diversion system will likely be compromised as a result of the Proposed Action, and per an agreement with the affected water right holder, the Renewal Corporation will implement appropriate measures or procure replacement water to provide equivalent water (e.g., amount, suitable quality, and timing) as would be used under normal circumstances.

2.3.2 During and Post-drawdown

During drawdown and up to two years following drawdown, if an impact is reported, the Renewal Corporation will investigate and implement measures to allow the water right holder to divert water in the same manner as before drawdown. Modeling efforts have shown the transport of impounded sediment will be greatly reduced within two years following drawdown, and effects

following that time are unlikely to be related to the Proposed Action. The Renewal Corporation will implement measures for water right holders who requested a technical evaluation during the pre-drawdown outreach process (Section 2.3.1).

3.0 Groundwater

3.1 Background

In 2018, the Renewal Corporation conducted a public outreach effort to identify residents for voluntary participation in a study to identify groundwater wells that may be at risk during Project implementation. The Renewal Corporation sent mailers to identify groundwater well owners willing to have their groundwater well outfitted with a continuous water level monitor (i.e., transducer). In addition, the Renewal Corporation also offered to test any groundwater well owner's water for naturally occurring minerals and metals and offered a \$500 incentive for any groundwater well owner willing to participate in the monitoring program. Only four groundwater well owners (one near Iron Gate Reservoir and three near Copco No. 1) agreed to participate in the program and have a continuous water level monitor outfitted to their well. As a result, it was difficult to obtain site-specific groundwater well monitoring data from the existing landowner groundwater wells. Of the four wells, only one participant is still currently providing information to the Renewal Corporation.

The Renewal Corporation also conducted a preliminary analysis to determine which groundwater wells within the vicinity of the reservoirs would be affected by the Proposed Action. There are no groundwater wells anticipated to be affected surrounding the Iron Gate Reservoir and up to 70 homes with 66 groundwater wells could potentially be impacted within approximately 1,000 feet of Copco No. 1 Reservoir (CDM Smith 2020). Review of existing well data in relation to the reservoir elevation indicate the following:

- Approximately 10 groundwater wells will require a new well to be installed.
- Approximately 10 groundwater wells will require deepening or similar work.
- Approximately 50 groundwater wells will require minimal work (e.g., new pump systems etc.).

3.2 Groundwater Elevation Monitoring

Reportedly, PacifiCorp has two groundwater wells located within the FERC boundary. The Renewal Corporation is currently coordinating with PacifiCorp to see if these wells can be utilized to monitor groundwater levels. In addition, the Renewal Corporation proposes to install two groundwater wells surrounding Copco No. 1 Reservoir to collect groundwater level data.

Prior to drawdown and in 2021, the Renewal Corporation will conduct a second public outreach effort to request public participation to conduct pre-drawdown groundwater monitoring. Property owners that participate in the Renewal Corporation's pre-drawdown groundwater monitoring program will be eligible to participate in the Local Impact Mitigation Fund (see Section 3.3) if

post drawdown monitoring indicates that a groundwater well has been adversely impacted by the Proposed Action.

Pre-drawdown groundwater monitoring will occur at least two months prior to drawdown for participating groundwater wells. Groundwater monitoring will occur monthly and up to two years following completion of drawdown.

3.3 Local Impact Mitigation Fund

To address potential impacts caused by reservoir drawdown, the Renewal Corporation will implement the measures stated in this plan, as required in the License Surrender Order. In order to address potential damage claims involving private properties, the Renewal Corporation will establish a Local Impact Mitigation Fund (LIMF), to be administered outside of the License Surrender Order. For property owners electing to opt into the fund, the LIMF will provide financial resources to such property owners to mitigate impacts to groundwater wells within approximately 1,000 feet of Copco No. 1 Reservoir that are determined to be caused by the Proposed Action. The fund will be backstopped by insurance. The Renewal Corporation will undertake these measures even though affected landowners, under the Water Code and other applicable state law, do not have a right to the enhanced condition of an aquifer (or enhanced well production) associated with a licensee's storage of a reservoir.

The LIMF will include procedures and standards for determining the nature and scope of any impacts, as well as stipulated payments to property owners. Developing this methodology will involve proactive participation and input from key stakeholders. The draft methodology will be made available for public comment through town halls and other meetings.

Under the LIMF, the Renewal Corporation will not accept responsibility for pre-existing conditions, such as arsenic contamination, or for any other condition not caused by the Proposed Action. The fund administrator will be supported by a technical team but will ultimately have the discretion to determine the legitimacy of covered claims. Any affected property owners who elect not to participate in the LIMF may, instead, pursue any other remedies available to such property owners under applicable state law.

4.0 Fire Management

The Fire Management Plan includes a list and map of locations where fire trucks and helicopters may access the Klamath River and its tributaries for residential fire protection efforts in the Hydroelectric Reach.

5.0 Annual Water Supply Management Report

By April 1 and 15 of each year, the Renewal Corporation will submit an annual Water Supply Management Report to the SWRCB and the Federal Energy Regulatory Commission,

respectively, beginning one year prior to and for two years following drawdown. The annual reports will include the following information.

5.1 Surface Water Diversions

The Water Supply Management Report will include the following information.

- A map presenting the location of potentially affected points of diversion.
- A description of the potential adverse effects from drawdown (e.g., intake blockage, damage to equipment etc.).
- A list of water rights holders who agreed to have a technical evaluation (Section 2.3.1) performed on their system.
- A description of the measures implemented (or to be implemented) to address the potential adverse effects from drawdown.

5.2 Groundwater

The Water Supply Management Report will include the following information.

- Documentation of groundwater well monitoring results including time series of water levels, trend analyses, and relationships of the identified trends to Proposed Action activities.
- A map of participating groundwater wells.
- Mitigation to address impacts to groundwater caused by the Proposed Action.

5.3 Fire Management

The Water Supply Management Report will include the following information.

- A list of locations where fire trucks and helicopters will be able to access water for firefighting.

6.0 References

CDM Smith. 2020. Technical Memorandum - Status of Groundwater Monitoring and Potential Effects to Supply Wells Following Reservoir Drawdown – Klamath Dam Removal.

Electronic Water Rights Information Management System (eWRIMS). 2020. California State Water Resources Control Board - Division of Drinking Water. Website: https://www.waterboards.ca.gov/waterrights/water_issues/programs/ewrims/. Accessed November 2020.

United States Bureau of Reclamation (USBR). 2012. Hydrology, Hydraulics, and Sediment Transport Studies for the Secretary's Determination on Klamath River Dam Removal and Basin Restoration, Technical Report No. SRH-2011-02. Prepared for Mid-Pacific

Region, Bureau of Reclamation, Technical Service Center, Denver, CO. Report dated April 2011, updated January 2012.

Appendix B

California Public Drinking Water Management Plan



**Lower Klamath Project
FERC Project No. 14803**

California Public Drinking Water Management Plan

**Klamath River Renewal Corporation
2001 Addison Street, Suite 317
Berkeley, CA 94704**

**Prepared By:
Camas LLC
680 G Street, Suite C
Jacksonville, OR 97530**

December 2021

This page intentionally left blank.

Table of Contents

1.0	Introduction.....	1
1.1	Purpose of Public Drinking Water Management Plan	1
1.2	Relationship to Other Management Plans.....	1
2.0	Public Drinking Water Supplies Sourced from Klamath River.....	1
2.1	Drinking Water System Assessment	4
2.1.1	Drinking Water System Description	4
2.1.2	Operations and Water Usage	5
2.1.3	Routine Monitoring and Sampling Schedule.....	6
2.2	Continuous Water Quality Monitoring.....	9
2.2.1	Drinking Water Protection Measures	9
2.2.2	Supplemental Potable Water Supply	9
3.0	City of Yreka Water Supply Line	9
3.1	Construction of Pipeline	10
3.1.1	City of Yreka Water Supply Coordination	10
3.1.2	Install Temporary Pipeline	10
3.1.3	Permanent Pipeline Replacement	10
3.1.4	Intake Structure Modification	11
3.2	Water Quality Monitoring and Protection Plan	11
4.0	References	12

List of Tables

Table 2.1. Raw Water Sampling and Performance Requirements.....	7
Table 2.2. Filtered Water Sampling and Performance Requirements.....	8

List of Figures

Figure 2-1. Collier Rest Area Location	3
--	---

Appendices

Appendix A	Figures
Appendix B	Collier Rest Area Drinking Water Protection Plan
Appendix C	100% City of Yreka Design Drawings
Appendix D	City of Yreka Pipeline Water Quality Protection Plan

1.0 Introduction

This California Public Drinking Water Management Plan is a subplan of the Water Supply Management Plan that will be implemented as part of the Proposed Action for the Lower Klamath Project.

1.1 Purpose of Public Drinking Water Management Plan

The purpose of the California Public Drinking Water Management Plan is to state the measures the Klamath River Renewal Corporation (Renewal Corporation) will implement to protect public drinking water supplies as part of the Proposed Action in California. Public drinking water supplies subject to this plan include drinking water sourced from the Klamath River below Iron Gate Dam and the California City of Yreka's water supply diverted from Fall Creek.

1.2 Relationship to Other Management Plans

The California Public Drinking Water Management Plan is supported by elements of the following management plans for effective implementation: Water Quality Monitoring and Management Plan and the Hatcheries Management and Operations Plan. So as to not duplicate information, elements from these other management plans are not repeated herein but are, where appropriate, referred to in this Public Drinking Water Management Plan.


2.0 Public Drinking Water Supplies Sourced from Klamath River

The sole public drinking water provider sourcing water supplies from the Klamath River downstream of Iron Gate Dam is the Randolph E. Collier Northbound and Southbound Roadside Rest Area (Collier Rest Area)¹. The location of this facility is presented on **Error! Reference source not found.** The California Department of Transportation (Caltrans) is the property owner and facility operator of the Collier Rest Area. The Renewal Corporation conducted the following steps to determine the appropriate management measures for the Collier Rest Area during the Proposed Action:

- Reviewed the existing Collier Rest Area drinking water system as-built drawings.
- Evaluated the Collier Rest Area drinking water system monitoring, sampling schedule and regulatory requirements as a Transient, Non-Community System.
- Consulted with Caltrans and California State Water Resources Control Board – Division of Drinking Water to determine system turbidity tolerances, prior non-compliance conditions, and preferred corrective measures.

¹ California State Water Resources Control Board Department of Drinking Water online database Drinking Water Watch and correspondence with agency representatives,

- Conducted an on-site system assessment.



Disclaimer: This document has been prepared based on information provided by others as cited in the Notes section. McMillen Jacobs Associates has not verified the accuracy and/or completeness of this information and shall not be responsible for any errors or omissions which may be incorporated herein as a result. McMillen Jacobs Associates assumes no responsibility for data supplied in electronic format, and the recipient accepts full responsibility for verifying the accuracy and completeness of the data.

Figure 2-1. Collier Rest Area Location

2.1 Drinking Water System Assessment

2.1.1 Drinking Water System Description

The Renewal Corporation has the following information about the Collier Rest Area (WaterWatch 2021).

Water System Name:	Caltrans-Collier Rest Stop
Water System No	CA4700554
Principal County Served	Siskiyou County
Primary Source	SW (surface water)
Water System No	Klamath River mile 186 where Interstate 5 intersects the Klamath River between Yreka and Hornbrook
Principal County Served	Transient, non-community, public drinking water system since 1979
Primary Water System Facilities:	<ul style="list-style-type: none"> • Raw infiltration gallery • Treated filter plant • Distribution system • Booster pump • Storage tank
Population Served:	1,400
Water Quality Monitoring Schedule:	<ul style="list-style-type: none"> • Raw infiltration gallery <ul style="list-style-type: none"> ○ Total coliform (sampled monthly) ○ Nitrate (sampled annually) ○ Nitrite (sampled every three years) ○ Other constituents sampled in 1999 at inception • Treated filter plant: <ul style="list-style-type: none"> ○ Total coliform and E. coli (sampled at least two times per month) ○ Nitrate and Nitrite (sampled only when triggered by high values in raw water)

2.1.2 Operations and Water Usage

The Renewal Corporation consulted with Caltrans to obtain as-built drawings of the drinking water system. In addition, an on-site assessment was conducted on September 30, 2020, by a Renewal Corporation representative. The following information was obtained from the as-built drawings and during the on-site assessment and is for informational purposes.

As-built drawings (Figure A-1, Appendix A) and schematics (Figure A-2, Appendix A) of the Collier Rest Area drinking water system (dated 1968) indicate the system consists of the following primary components:

- Raw Infiltration Gallery
 - Water Intake Gallery
 - Water Gallery Extension
- Raw Water Turbidimeter
- Polymer Injection
- Water Treatment Building (3-part filtration system)
- Chlorine Injection
- Filtered Water Turbidimeter
- Residual Chlorine Analyzer
- Booster Pumps
- 1,500-gallon Pressure Tank
- 32,000-gallon Treated Water Storage Tank

The raw infiltration gallery consists of two components: a below-ground water intake gallery and a raw water intake gallery extension. The below-ground water intake gallery is located approximately 27 ft below the ground surface and consists of three 250 ft long 24-inch perforated metal pipes. The raw water intake gallery extension extends from the water intake gallery into the Klamath River and is overlain by cobble. The extension consists of two 100 ft long 12-inch perforated metal pipes. These galleries deliver water to both the irrigation pump and the drinking water pump, which operate separate systems.

An above-ground water treatment building which contains a three-part filtration unit is centrally located above the water intake gallery. A 60-inch diameter sump extends from the water treatment building to the floor of the gallery, and the intake pump is situated at the bottom of the sump. Water destined for the potable water system is pumped to the treatment building and sampled by an automated turbidimeter and then injected with a polymer coagulant prior to passing through three separate pressure vessels for filtration. The first (roughing) filter consists of sand, the second (fining) filter is comprised of garnet media, and the third is comprised of activated carbon. After passing through the filters, the potable water is injected with chlorine before being sampled by an automated turbidimeter and residual chlorine analyzer and pumped to a 32,000-gallon bolted-steel tank for storage. The water is then distributed to the restrooms and potable water faucets located throughout the Collier Rest Area.

The average volume of water passing through the potable water system is approximately 5,000 gallons per day. During peak usage periods in the late-summer, potable water demand can approach approximately 9,000 gallons per day to operate toilets, sinks, drinking fountains, and faucets located throughout the Collier Rest Area.

2.1.3 Routine Monitoring and Sampling Schedule

Per the April 16, 2019, California Regulations Related to Drinking Water, the Collier Rest Area is required to routinely collect bacteriological water quality samples and conduct performance monitoring. Table 2.1 presents the raw water bacteriological and inorganic chemical water quality sample and treatment technique requirements.

Turbidity monitoring is conducted daily via the turbidimeters discussed in Section 2.1.2, and is recorded on-site with a circular chart recorder. This data is transmitted to a Supervisory Controls and Data Acquisition system at Caltrans headquarters in Sacramento. The system is equipped with alarm functionality to alert operators when these parameters are outside bounds set by the operator.

Table 2.2 presents the filtered bacteriological water quality sample and treatment technique requirements.

Table 2.1. Raw Water Sampling and Performance Requirements

ANALYTE	FREQUENCY	ANALYSIS	REGULATION
Bacteriological Water Quality samples			
Total Coliform and <i>E. coli</i>	Monthly	If total coliform-positive, the water supplier shall collect a repeat sample from the same location within 48 hours of being notified of the positive result. If the repeat sample is also total coliform-positive, the sample shall also be analyzed for the presence of fecal coliforms or <i>Escherichia coli</i> (<i>E. coli</i>). The water supplier shall notify the local health officer within 48 hours from the time the results are received and shall take corrective actions as directed by the local health officer to eliminate the cause of the positive samples.	Title 22 Code of Regulations, Division 4. Environmental Health - Chapter 15. Domestic Water Quality and Monitoring Regulations - Article 3. Primary Standards – Bacteriological Quality §64421 General Requirements
Inorganic Water Quality samples			
Nitrite	Every three years	If any sample exceeds 50% of the Maximum Contaminant Level (MCL) (5 milligrams/liter [mg/L] for nitrate, 0.5 mg/L for nitrite), the monitoring frequency for that analyte will be quarterly. After four consecutive quarters of samples containing less than 50% of the MCL, the monitoring frequency may return to annual sampling.	Title 22 Code of Regulations, Division 4. Environmental Health - Chapter 15. Domestic Water Quality and Monitoring Regulations - Article 4. Primary Standards – Inorganic Chemicals §64432.1. Monitoring and Compliance – Nitrate and Nitrite
Nitrate	Annually		
Treatment Technique Requirements			
Turbidity	At least once per day	Not applicable.	Title 22 Code of Regulations, Division 4. Environmental Health - Chapter 15. Domestic Water Quality and Monitoring Regulations - Article 3. Monitoring Requirements §64654.8. Source, Raw, Settled, and Recycled Filter Backwash Monitoring

Table 2.2. Filtered Water Sampling and Performance Requirements

ANALYTE	FREQUENCY	ANALYSIS	REGULATION
Bacteriological Water Quality samples			
Total Coliform	2 times per month	If total coliform-positive, the water supplier shall collect a repeat sample from the same location within 48 hours of being notified of the positive result. If the repeat sample is also total coliform-positive, the sample shall also be analyzed for the presence of fecal coliforms or <i>E. coli</i> . The water supplier shall notify the local health officer within 48 hours from the time the results are received and shall take corrective actions as directed by the local health officer to eliminate the cause of the positive samples.	Title 22 CCR, Division 4. Environmental Health - Chapter 15. Domestic Water Quality and Monitoring Regulations - Article 3. Primary Standards – Bacteriological Quality §64421 General Requirements
Inorganic Water Quality samples			
Nitrite	If raw water quality sample is positive	If any sample exceeds 50% of the MCL (5 mg/L for nitrate, 0.5 mg/L for nitrite), the monitoring frequency for that analyte will be quarterly. After four consecutive quarters of samples containing less than 50% of the MCL, the monitoring frequency may return to annual sampling.	Title 22 CCR, Division 4. Environmental Health - Chapter 15. Domestic Water Quality and Monitoring Regulations - Article 4. Primary Standards – Inorganic Chemicals §64432.1. Monitoring and Compliance – Nitrate and Nitrite
Nitrate			
Treatment Technique Requirements			
Turbidity	At least once every 15 minutes	Shall not exceed 1 NTU for more than one continuous hour.	Title 22 CCR, Division 4. Environmental Health - Chapter 15. Domestic Water Quality and Monitoring Regulations - Article 3. Monitoring Requirements §64655. Filtration Monitoring

2.2 Continuous Water Quality Monitoring

The Water Quality Monitoring and Management Plan identifies measures the Renewal Corporation will implement to assess potential water quality impacts relating to implementation of the Proposed Action from the site of J.C. Boyle Dam to the estuary. As part of the Water Quality Monitoring and Management Plan, the Renewal Corporation will continuously monitor water quality stations along the Klamath River prior to, during, and following drawdown. One of these water quality stations includes the United States Geological Station (USGS) stream gage no. 11516530, which is located approximately 11 river miles upstream of the Collier Rest Area (Figure A-3, Appendix A). Continuous real-time water quality parameters (dissolved oxygen, water temperature, turbidity, conductivity, and pH) will be monitored by the Renewal Corporation at this location at 15-minute intervals.

In addition, the Renewal Corporation will collect monthly water quality grab samples from this location. Water quality grab samples will include but are not limited to analyzing for nitrate, nitrite, and turbidity. The schedule and full list of parameters can be found in the Water Quality Monitoring and Management Plan.

2.2.1 Drinking Water Protection Measures

The Renewal Corporation will implement a Drinking Water Protection Plan to protect the Collier Rest Area drinking water supplies following initial drawdown and up to two years following initial drawdown. Modeling efforts have shown the transport of impounded sediment will be greatly reduced within two years following drawdown, and any effects after that time are unlikely to be related to the Proposed Action. The Drinking Water Protection Plan is being developed through consultation with the DWR and Caltrans. The Drinking Water Protection Plan is included as Appendix B.

2.2.2 Supplemental Potable Water Supply

The Renewal Corporation will supplement the Collier Rest Area with drinking water per the Drinking Water Protection Plan.

3.0 City of Yreka Water Supply Line

The Renewal Corporation will replace the City of Yreka's existing water supply pipeline that traverses beneath the north end of the Iron Gate Reservoir to avoid damage following reservoir drawdown.

The existing City of Yreka water supply pipeline intake structure originates in Fall Creek, near the Fall Creek Fish Hatchery. The pipeline then traverses south along Copco Road until it joins the north end of the Iron Gate Reservoir, where it crosses beneath the reservoir (Figure A-4, Appendix A) and connects to the city's water distribution system.

Prior to drawdown of Iron Gate Reservoir, the Renewal Corporation will temporarily reroute the pipeline across the Daggett Road bridge until the new pipeline is replaced. The Renewal Corporation will also construct a velocity barrier downstream of Dam A and the City of Yreka's intake structure to serve as a barrier for adults and juveniles and follows the design guidance from the National Marine Fisheries Service (NMFS 2011).

3.1 Construction of Pipeline

The Renewal Corporation will replace the City of Yreka water supply pipeline in accordance with the 100% design drawings (see Appendix C).

3.1.1 City of Yreka Water Supply Coordination

The Renewal Corporation will coordinate with the City of Yreka to provide uninterrupted water supply during replacement of the pipeline prior to drawdown. The estimated water delivery outage timeframe will be provided and agreed upon between the City of Yreka and the Renewal Corporation prior to construction.

3.1.2 Install Temporary Pipeline

Prior to drawdown, the Renewal Corporation will construct a temporary pipeline to provide water service during the drawdown period. The temporary pipeline will connect to the existing pipeline on Daggett Road, will then cross the Daggett Road Bridge, and lead to a connection point to the existing pipeline on the south side of the reservoir (Figure A-4, Appendix A). A portion of the temporary pipeline will require a pipe crossing over Fall Creek. The pipeline will be mounted on the upstream side of Daggett Bridge. The portion of the pipeline from Daggett Road to the existing pipeline connection point will be buried. Isolation valves will be installed to control the diversion of water during drawdown.

When the connections to the existing pipeline are constructed, there will be a disruption of water service. The Renewal Corporation will coordinate this activity with the City of Yreka as described in Section 3.1.1.

3.1.3 Permanent Pipeline Replacement

The Renewal Corporation will conduct pipeline construction in two stages to allow the river to be routed around the work zone (Figure A-5, Appendix A). In the first stage, a cofferdam will be constructed on the north side of the river channel, diverting flow to the south. A turbidity curtain will be placed downstream to reduce the impact of construction activities on turbidity levels in the newly established Klamath River. Water from within the cofferdam will be pumped to a Baker tank on the shoreline where suspended sediment will settle prior to the water being pumped back into the Klamath River. Behind the cofferdam, a trench will be excavated into the riverbed and the new pipeline will be buried at a depth that will prevent scour from 500-year flood events. Upon completion of the first stage, the cofferdam diversion will be removed from the north side and reinstalled on the opposite bank of the Klamath River. The cofferdam areas will overlap slightly to allow access to the section of pipeline completed in the first stage. The

second stage of the pipeline replacement will be conducted in the same manner as the first stage on the south side of the Klamath River. The pipeline will then extend to the existing pipeline on the south side of the Klamath River.

3.1.4 Intake Structure Modification

The Renewal Corporation will modify the dam just below the intake pool on Fall Creek (Dam A) to include a concrete high-velocity apron, also known as a velocity barrier, to prevent fish from entering the pool where the intakes for the City of Yreka water supply pipeline and the Fall Creek Fish Hatchery are located (Figure A-6, Appendix A). The Renewal Corporation will install another velocity apron fish barrier downstream of Dam B. The fish barrier designs follow the guidance of NMFS (2011). These modifications will not impact the intakes themselves and will not cause any interruptions to the water supply for the City of Yreka. These velocity apron fish barriers are described in detail in the Hatcheries Management and Operations Plan, which also includes a Water Quality Monitoring and Protection Plan for the in-water work.

The Renewal Corporation will install water intakes for the Fall Creek Fish Hatchery in the same pool as the intake structure for the City of Yreka water supply pipeline. During construction of the hatchery intakes, the Renewal Corporation will protect the City of Yreka intakes to maintain continuous flow. The Hatcheries Management and Operations Plan describes how hatchery operators will protect flows to the City of Yreka pipeline during hatchery operations after construction.

3.2 Water Quality Monitoring and Protection Plan

In-water work will be required to replace the City of Yreka water supply pipeline and intake modifications. The Renewal Corporation's City of Yreka Waterline Modification Construction Water Quality Monitoring and Protection Plan (Appendix D) includes management measures to control erosion, stream sedimentation, dust, and soil mass movement. This plan is included as Appendix D. This plan includes the following elements:

1. Description of site conditions and the proposed activity;
2. Detailed descriptions, design drawings, and specific topographic locations of all management measures in relation to the proposed activity, which may include:
 - a. Measures to divert runoff away from disturbed land surfaces;
 - b. Measures to collect and filter runoff from disturbed land surfaces, including sediment ponds at the sites; and
 - c. Measures to dissipate energy and prevent erosion;
3. Revegetation of disturbed areas using native plants and locally sourced plants and seeds; and
4. A monitoring, maintenance, and reporting schedule.

4.0 References

California Code of Regulations (CCR). Title 22, Division 4, Chapter 15. Domestic Water Quality and Monitoring Regulations. *Accessed online November 5, 2020.*

California State Water Resources Control Board - Division of Drinking Water 2020. Drinking Water Watch) Website: <https://sdwis.waterboards.ca.gov/PDWW/>. Accessed January 2021.

National Marine Fisheries Service (NMFS). 2011. Anadromous Salmonid Passage Facility Design. National Oceanic and Atmospheric Administration, NMFS, Northwest Region: Portland, OR.

Appendix A

Figures




Figure A-1. As-built - Drinking Water System

CalTrans Collier Rest Area Public Water System #4700554






Figure A-2. Schematic Drawing - Drinking Water System

Document Path: C:\Users\slm\OneDrive\GIS\Project_Based\Klamath_River_Renewal_MU\AGIS_Request_Tracking\GIS_Requests_Management_Plans\Camas_MP\MP2\CA_P\MP2_2_3_1_9_gauge.mxd





Lower Klamath Project

December 2020

PRELIMINARY DESIGN (NOT FOR CONSTRUCTION)

Legend

- ★ Collier Rest Area
- USGS Gauge
- Klamath River

N

0 1 2 4 Miles

Notes

1. Coordinate System: WGS 1984 Web Mercator Auxiliary Sphere

2. Background: Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

USGS The National Map, National Boundaries Dataset, 3DEP Elevation Program, Geographic Names Information System, National Hydrography Dataset, National Land Cover Database, National Structures Dataset, and National Transportation Dataset; USGS Global Ecosystems; U.S. Census Bureau TIGER/Line data; USFS Road Data; Natural Earth Data; U.S. Department of State Humanitarian Information Unit; and NOAA National Centers for Environmental Information, U.S. Coastal Relief Model. Data refreshed May, 2020.

Disclaimer: This document has been prepared based on information provided by others as cited in the Notes section. McMillen Jacobs Associates has not verified the accuracy and/or completeness of this information and shall not be responsible for any errors or omissions which may be incorporated herein as a result. McMillen Jacobs Associates assumes no responsibility for data supplied in electronic format, and the recipient accepts full responsibility for verifying the accuracy and completeness of the data.

Figure A-3. USGS Iron Gate Water Quality Monitoring




Figure A-4. City of Yreka Water Supply Pipeline




Figure A-6. City of Yreka Water Supply Pipeline Intake

Appendix B

Collier Rest Area Drinking Water Protection Plan



Lower Klamath River Project

Drinking Water Protection Plan

Collier Rest Area

December 2021



This page intentionally left blank.

Prepared for:

Caltrans – California Department of Transportation
California State Water Board – Division of Drinking Water

Prepared by:

KRRC Technical Representatives:

Camas, LLC
680 G Street, Suite C
Jacksonville, OR 97530

Table of Contents

1	Introduction	2
1.1	Lower Klamath Project.....	2
1.2	Collier Rest Area	5
2	Drinking Water Protection.....	7
2.1	Phase I - Pre-Drawdown	7
2.2	Phase 2 - Drawdown and Phase 3A/B - Post-Drawdown.....	7
3	Contact Information	8
Exhibit 1: Contacts:.....		10

List of Figures

Figure 1.	Lower Klamath Project Location	4
Figure 2.	Collier Rest Area Location	5
Figure 3.	DWPP Decision Tree	9

A large, stylized blue wavy shape that spans across the middle of the slide. It has a lighter blue upper section and a darker blue lower section, separated by a white wavy line.

Chapter 1: Introduction

1 Introduction

1.1 Lower Klamath Project

The Lower Klamath River Project (Lower Klamath Project) (FERC No. 14803) consists of four hydroelectric developments on the Klamath River: J.C. Boyle, Copco No. 1, Copco No. 2, and Iron Gate (Figure 1). In September of 2016, the Renewal Corporation filed an *Application for Surrender of License for Major Project and Removal of Project Works*, FERC Project Nos. 2082-063 & 14803-001 (License Surrender). The Renewal Corporation filed the License Surrender Application as the dam removal entity for the purpose of implementing the Klamath River Hydroelectric Settlement (KHSA). In November of 2020, the Renewal Corporation filed its Definite Decommissioning Plan (DDP) as Exhibits A-1 and A-2 to its Amended License Surrender Application. The DDP is the Renewal Corporation's comprehensive plan to physically remove the Lower Klamath Project and achieve a free-flowing condition and volitional fish passage, site remediation and restoration, and avoidance of adverse downstream impacts (Proposed Action). The Limits of Work is a geographic area that encompasses dam removal- related activities in the Proposed Action, within the FERC boundary associated with the Lower Klamath Project except where specifically noted.

The License Surrender identifies the preparation of a Water Supply Management Plan (WSMP) which will include the protection of drinking water at the Collier Rest Area. FERC will issue the Surrender Order approving and requiring the Renewal Corporation's implementation of the WSMP. In addition, the State Water Resources Control Board (SWRCB) issued a Water Quality Certification (CA 401 WQC) for the Lower Klamath Project on April 7, 2020. The CA 401 WQC includes Condition 8 - Public Drinking Water Supplies, identifying the development of the WSMP.

The Proposed Action includes the deconstruction of the J.C. Boyle Dam and Powerhouse, Copco No. 1 Dam and Powerhouse, Copco No. 2 Dam and Powerhouse, and Iron Gate Dam and Powerhouse, as well as associated features. Associated features vary by development, but generally include powerhouse intake structures, embankments, and sidewalls, penstocks and supports, decks, piers, gatehouses, fish ladders and holding facilities, pipes and pipe cradles, spillway gates and structures, diversion control structures, aprons, sills, tailrace channels, footbridges, powerhouse equipment, distribution lines, transmission lines, switchyards, original cofferdam, portions of the Iron Gate Fish Hatchery, residential facilities, and warehouses. Facility removal will be completed within an approximately 20-month period.

Removal of Lower Klamath Project facilities will consist of three primary phases.

Phase 1 Pre-Drawdown - Pre-Drawdown includes construction-related activities up to the initiation of drawdown.

Phase 2 Drawdown - Drawdown includes initial drawdown which will occur approximately from January 1 to March 15 and the final reservoir drawdown which will occur when the water surface elevation is at the Klamath River historic channel elevation. The duration of drawdown is expected to last approximately four to six months depending on water year type.

Phase 3A Post - Drawdown - Post-Drawdown facility removal includes construction-related activities associated with removing the physical facilities associated with the Project.

Phase 3B Post - Drawdown - Post-Drawdown Site Restoration and Ancillary Site Improvements includes construction-related and restoration activities occurring post-facility removal.

The Renewal Corporation will also continuously monitor turbidity, flow, temperature, conductivity, dissolved oxygen, and pH in the Klamath River downstream of the Iron Gate Dam at United States Geological Survey [USGS] gage station no. 11516530 located approximately 11 miles upstream of the Collier Rest Area prior to and during the dam removal project. Data from this station will be used to indicate Proposed Action-related effects on water quality at the Collier Rest Area. Based on recent modeling efforts, water quality impacts will likely occur following initial reservoir drawdown from January until drawdown is complete.




Figure 1. Lower Klamath Project Location

1.2 Collier Rest Area

The Randolph E. Collier Northbound and Southbound Roadside Rest Area (Collier Rest Area, Figure 2) is located approximately 11 miles downstream of Iron Gate Dam and uses a surface water diversion from the Klamath River to supply drinking water to the public. The water is treated and tested before being distributed to restrooms, drinking fountains, and water faucets. During drawdown, increased turbidity and suspended sediment in the Klamath River could result in increased system maintenance or exceedances of drinking water quality standards as set forth by the California State Water Board Division of Drinking Water (DDW).




Figure 2. Collier Rest Area Location



Chapter 2: Drinking Water Protection

2 Drinking Water Protection

The Renewal Corporation has established the following measures in consultation with Caltrans and the California DDW to protect drinking water supplies at the Collier Rest Area during the Lower Klamath Project, FERC 14803. Please refer to Figure 3, which outlines the items below.

The Renewal Corporation will implement the DWPP to protect the Collier Rest Area drinking water supplies following initial drawdown and up to two years following initial drawdown.

2.1 Phase I - Pre-Drawdown

- The Renewal Corporation will notify Caltrans and the DDW no less than six months prior to the start of reservoir drawdown.
- The Renewal Corporation will prepare, with support from the DDW, the following Draft Unsafe Water Notifications (Public Notices):
 - **Tier 1 Public Notice (for violation of *E. coli* Maximum Contaminant Level [MCL], and**
 - **Tier 2 Public Notice (for violation of Treatment Technique Requirements).**

The Public Notices will be prepared in accordance with the April 16, 2019, California Regulations Related to Drinking Water Title 22 Code of Regulations, Division 4. Environmental Health - Chapter 15. Domestic Water Quality and Monitoring Regulations - Article 18. Notification of Water Consumers and the State Board §64463 General Public Notification Requirements, §64463.1 Tier 1 Public Notice, and §64463.4 Tier 2 Public Notice, respectively.

2.2 Phase 2 - Drawdown and Phase 3A/B - Post-Drawdown

Caltrans facility operator(s) will conduct Treatment Technique Requirements (i.e., turbidity monitoring) and collect monthly bacteriological water quality samples (Total Coliform, *E. coli*) in accordance with their DDW permit. As shown in Figure 3, if there is a violation of Treatment Technique Requirements or *E. coli*, Caltrans facility operator(s) and the Renewal Corporation will perform the following steps:

1. Shut down the drinking water system intake pump and notify the Renewal Corporation within 24 hours.
2. Once the intake pump is shut down, the 32,000-gallon water supply storage tank will continue to provide drinking water to the Collier Rest Area facility for 1-3 days depending on usage by the public.
3. Following the shutdown notification, the Renewal Corporation will finalize the appropriate public notice template to be approved by DDW. For a Tier 1 violation, Caltrans will issue the approved public notice within 24 hours of the violation, and for a Tier 2 violation, Caltrans will issue the approved public notice within 7 days of the violation. Caltrans personnel will ensure the notice is properly posted throughout the facility in accordance with the April 16, 2019, California Regulations Related to Drinking Water.
4. The Renewal Corporation will provide a California Department of Public Health licensed drinking water delivery truck to the Collier Rest Area within 1-3 days of the system being shut down and prior to

depletion of the 32,000-gallon water supply storage tank. Below are the options for drinking water deliveries for each violation type.

a. *E. coli* MCL Violation

- i. Supplement the existing 32,000-gallon water supply storage tank with drinking water to be used throughout the rest area.
- ii. Caltrans will collect a repeat sample(s) in accordance with Title 22 Code of Regulations, Division 4. Environmental Health - Chapter 15. Domestic Water Quality and Monitoring Regulations - Article 3. Primary Standards - Bacteriological Quality §64424. Repeat Sampling.
- iii. If analytical results of the repeat sample(s) are negative, the Unsafe Water Notice is canceled in accordance with the April 2020 SWB Unsafe Water Notification Guidance, and the DDW approves, Caltrans will resume utilizing the drinking water system.

b. Treatment Technique Requirements

- i. The Renewal Corporation will coordinate with DDW to determine which of the following two options is applicable:
 - a. Supplement the existing 32,000-gallon water supply storage tank with drinking water to be used throughout the rest area, or
 - b. Caltrans will continue operation of the drinking water system for handwashing and toilets, but not drinking water. Drinking water will be provided by the Renewal Corporation via mobile drinking water station(s).
- ii. Caltrans will continue to monitor turbidity (raw and filtered) as required per their permit. Once Treatment Technique Requirements are achieved, and the DDW approves, Caltrans will resume operation of the drinking water system.

3 Contact Information

Contact information for the Renewal Corporation, DDW, and Caltrans is included in Exhibit 1.




Figure 3. DWPP Decision Tree

Exhibit 1: Contacts:

Caltrans

Thomas March
Landscape Specialist,
1657 Riverside Drive
Redding, California 96001
Email: Thomas.March@dot.ca.gov
Mobile: 530-604-1819
Office: 530-225-2460

Kevin Boudro
System Operator
Mobile: 530-598-9040

California Division of Drinking Water

Barry Sutter
District Engineer
364 Knollcrest Drive, Suite 101
Redding, California 96002
Email: Barry.Sutter@waterboards.ca.gov
Office: 530-224-4875

Craig Bunas
Associate Engineer
364 Knollcrest Drive, Suite 101
Redding, California 96002
Email: Craig.Bunas@waterboards.ca.gov
Office: 530-224-4887

Klamath River Renewal Corporation

Laura Hazlett
Chief Operations Officer
2001 Addison Street, Suite 317
Berkeley, California 94704
Email: lhazlett@klamathrenewal.org
Office: 415-820-4441

Lisa DeRose (Camas LLC)
Project Scientist III
680 G Street, Suite C
Jacksonville, Oregon 97530
Email: Lisa@camasllc.com
Mobile: 908-229-6488

End of Drinking Water Protection Plan

Appendix C

100% City of Yreka Design Drawings



KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE




VOLUME 2 - CONSTRUCTION DRAWINGS
FEBRUARY, 2021

100% DESIGN SUBMITTAL

KLAMATH RIVER RENEWAL CORPORATION

CITY OF YREKA WATERLINE MODIFICATION PROJECT

100% DESIGN SUBMITTAL



SURVEY CONTROL POINT SCHEDULE						
CONTROL POINT	MONUMENT_ID	NORTHING	EASTING	ELEVATION	GROUP	TYPE
CP1	WCP-101	2602481.28	6461785.59	2362.79	WOOLPERT	REBAR WITH CAP
CP2	GMA-203	2599140.91	6444628.30	2479.26	GMA	REBAR WITH CAP
CP3	GMA-205	2587906.56	6443500.04	2463.69	GMA	REBAR WITH CAP
CP4	KLAM_RTK_01	2587307.60	6441471.45	2193.84	QSI	REBAR WITH CAP

- SURVEY CONTROL NOTES:**
- HORIZONTAL DATUM: HPGN NAD 1983 CALIFORNIA STATE PLANE ZONE I (FEET)
 - VERTICAL DATUM: NAVD 88 GEOID 12B.

REV	DATE	BY	DESCRIPTION
B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.



KLAMATH RIVER RENEWAL CORPORATION	
CITY OF YREKA WATER LINE	
LOCATION MAP, VICINITY MAP AND SURVEY CONTROL POINTS	


DESIGNED	J. BURNS
DRAWN	R. WOOD
CHECKED	M. MCMILLEN
PROJECT DATE	02/05/21

DRAWING
G001

DRAWING INDEX		
DWG NO	SHEET NO.	DESCRIPTION
GENERAL		
		COVER SHEET
1	G001	LOCATION MAP, VICINITY MAP AND SURVEY CONTROL POINTS
2	G002	DRAWING INDEX
3	G003	STANDARD ABBREVIATIONS
4	G004	STANDARD SYMBOLS
5	G005	OVERALL PLAN AND PROJECT CONTROL
6	G006	CONTRACTOR STAGING AREA
7	G007	PIPING AND VALVE SCHEDULE
EROSION AND SEDIMENT CONTROL		
8	EC001	EROSION AND SEDIMENT CONTROL STANDARD DETAILS 1
9	EC002	EROSION AND SEDIMENT CONTROL STANDARD DETAILS 2
10	EC100	EROSION AND SEDIMENT CONTROL PLAN
11	EC101	EROSION AND SEDIMENT CONTROL SITE COORDINATES
DEMOLITION		
12	D101	DEMOLITION WATERLINE PLAN AND PROFILE
CIVIL		
13	GC001	CIVIL GENERAL NOTES
14	GC002	CIVIL STANDARD DETAILS 1
15	GC003	CIVIL STANDARD DETAILS 2
16	GC004	CIVIL STANDARD DETAILS 3
17	C001	OVERALL SITE PLAN
18	C100	TEMPORARY WATERLINE PLAN AND PROFILE 1
19	C101	TEMPORARY WATERLINE PLAN AND PROFILE 2
20	C102	TEMPORARY WATERLINE PLAN AND PROFILE 3
21	C103	TEMPORARY WATERLINE PLAN AND PROFILE 4
22	C104	TEMPORARY WATERLINE PLAN AND PROFILE 5
23	C105	TEMPORARY WATERLINE PLAN AND PROFILE 6
24	C106	TEMPORARY WATERLINE PLAN AND PROFILE 7
25	C107	TEMPORARY WATERLINE PLAN AND PROFILE 8
26	C200	PERMANENT WATERLINE PLAN AND PROFILE
27	C201	CIVIL SECTIONS AND DETAILS 1
28	C202	CIVIL SECTIONS AND DETAILS 2

B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL
REV	DATE	BY	DESCRIPTION

PRELIMINARY
NOT FOR CONSTRUCTION




KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
DRAWING INDEX

DESIGNED <u>J. BURNS</u>
DRAWN <u>R. WOOD</u>
CHECKED <u>M. MCMILLEN</u>
PROJECT DATE <u>02/05/21</u>

DRAWING
G002


A/C	AIR CONDITIONING	CMH	COMMUNICATION MANHOLE	F TO F	FACE TO FACE	I	INSTRUMENTATION (DWG DISCIPLINE)	N	NORTH, NEUTRAL	RET	RETAINING, RETURN	V	VENT, VELOCITY, VOLT
A/E	ARCHITECT/ENGINEER	CMU	CONCRETE MASONRY UNIT	FAB	FABRICATE	ID	INSIDE DIAMETER, INTERIOR DIMENSION	NA	NOT APPLICABLE	REV	REVISION, REVERSE	VA	VOLT AMPERE
A	ARCHITECTURAL (DWG DISCIPLINE), AMP	CO	CLEAN OUT, CONCRETE OPENING	FBO	FURNISHED BY OWNER	IE	INVERT ELEVATION	NAT	NATURAL	RFL	REFLECTED, REFLECTOR	VAC	VACUUM
AB	ANCHOR BOLT	COL	COLUMN	FC	FLUSHING CONNECTION	IF	INSIDE FACE	NC	NORMALLY CLOSED	RGS	RIGID GALVANIZED STEEL	VAR	VARNISH, VARIABLE, VOLT AMPERES REACTIVE
ABC	AGGREGATE BASE COURSE	COM	COMMON	FCA	FLANGED COUPLING ADAPTER	IFC	ISSUED FOR CONSTRUCTION	NEG	NEGATIVE	RH	RELIEF HOOD, RIGHT HAND, RELATIVE HUMIDITY	VB	VAPOR BARRIER, VINYL BASE, VALVE BOX
ABAN	ABANDON	COMB	COMBINATION	FCV	FIXED CONE VALVE	IH	INTAKE HOOD	NF	NEAR FACE, NON-FUSED			VC	VERTICAL CURVE
AC	ALTERNATING CURRENT	COMM	COMMUNICATION	FD	FLOOR DRAIN	IMP	IMPACT	NG	NATURAL GAS	RL	REQUIRED LAP	VCT	VINYL COMPOSITION TILE, VERTICAL CENTERLINE
ACST	ACOUSTIC	COMP	COMPOSITION, COMPRESSIBLE, COMPOSITE	FDC	FLEXIBLE DUCT CONNECTION	IN	INCH	NIC	NOT IN CONTRACT	RND	ROUND		
AD	ADDENDUM, AREA DRAIN	CONC	CONCENTRIC, CONCRETE	FDR	FEEDER	INC	INCLUDE, INCANDESCENT	NO	NORMALLY OPEN, NUMBER	RNG	RENEWABLE NATURAL GAS	VEL	VELOCITY
ADDL	ADDITIONAL	CONN	CONNECTION	FE	FLANGED END	INF	INFLUENT	NOM	NOMINAL	RO	ROUGH OPENING	VENT	VENTILATION
ADH	ADHESIVE	CONST	CONSTRUCTION	FEC	FIRE EXTINGUISHER CABINET	INSTR	INSTRUMENTATION	NPS	NOMINAL PIPE SIZE	ROW	RIGHT-OF-WAY	VERT	VERTICAL
ADJ	ADJUSTABLE, ADJACENT	CONT	CONTINUOUS, CONTINUED	FEXT	FIRE EXTINGUISHER	INSUL	INSULATION	NPT	NATIONAL PIPE THREAD	RPM	REVOLUTIONS PER MINUTE	VS	VERSES, VAPOR SEAL
AF	AMP FRAME, AMP FUSE	COORD	COORDINATE	FF	FAR FACE, FACTORY FINISH, FLAT FACE	INT	INTERIOR, INTERSECTION	NS	NEAR SIDE	RR	RAILROAD	VOL	VOLUME
AFF	ABOVE FINISH FLOOR	CORR	CORROSIVE, CORRUGATED	FG	FINISHED GRADE	INTR	INTERMEDIATE, INTERIOR	NTS	NOT TO SCALE	RT	RIGHT	VPC	VERTICAL POINT OF CURVATURE
AFG	ABOVE FINISH GRADE	CP	CHECKER PLATE, CONTROL POINT	FIG	FIGURE	INV	INVERT	NWL	NORMAL WATER LEVEL			VPI	VERTICAL POINT OF INTERSECTION
AGGR	AGGREGATE	CPLG	COUPLING	FH	FIRE HYDRANT	IPS	IRON PIPE SIZE			S	SOUTH, SINK, STRUCTURAL (DWG DISCIPLINE)	VPT	VERTICAL POINT OF TANGENCY
AIC	AMPS INTERRUPTING CAPACITY	CSK	COUNTERSINK	FIN	FINISH	IPT	INTERNAL PIPE THREAD			SA	SUPPLY AIR	VTR	VENT THROUGH ROOF
ALIG	ALIGNMENT	CTR	CENTER	FL	FLOW, FLOW LINE	IRR	IRRIGATION			SAN	SANITARY	VWC	VINYL WALL COVERING
ALUM	ALUMINUM	CTRL	CONTROL	FLEX	FLEXIBLE	ISO	ISOMETRIC			SC	SOLID CORE		
ALT	ALTERNATE, ALTITUDE	CU	COPPER, CUBIC	FLG	FLANGE					OC	ON CENTER		
AMB	AMBIENT	CW	CLOCKWISE	FLOR	FLUORESCENT					OC	OVER CURRENT PROTECTION DEVICE		
ANC	ANCHOR	CY	CUBIC YARD	FLR	FLOOR					OD	OUTSIDE DIAMETER		
AP	ACCESS PANEL			FLR	FLOOR					OH	OVERHEAD		
APRX	APPROXIMATE	d	PENNY (NAIL MEASURE)	FLS	FLASHING, FLUSH					OPNG	OPENING		
APVD	APPROVED ARCH ARCHITECTURAL	D	DEEP, DIFFUSER	FND	FOUNDATION					OPP	OPPOSITE		
ASSY	ASSEMBLY	DB	DUCT BANK, DECIBEL, DRY BULB	FNC	FENCE					OPT	OPTIONAL		
AT	AMP TRIP	DBA	DEFORMED BAR ANCHOR	FO	FINISHED OPENING					ORD	OVERFLOW ROOF DRAIN		
ATM	ATMOSPHERE	DBL	DOUBLE	FOB	FLAT ON BOTTOM					ORIG	ORIGINAL		
AUTO	AUTOMATIC	DC	DIRECT CURRENT	FOC	FACE OF CONCRETE, FACE OF CURB, FIBER					OVFL	OVERFLOW		
AUX	AUXILIARY	DEG	DEGREE							OVHG	OVERHANG		
AVE	AVENUE	DEG C	DEGREE CENTIGRADE	FOF	FACE OF FINISH					OZ	OUNCE		
AVG	AVERAGE	DEG F	DEGREE FAHRENHEIT	FOM	FACE OF MASONRY								
AWG	AMERICAN WIRE GAGE	DEMO	DEMOLITION	FOS	FACE OF STUDS								
		DEP	DEPRESSED	FOT	FLAT ON TOP								
		DEPT	DEPARTMENT	FPT	FEMALE PIPE THREAD								
		DET	DETAIL	FR	FRAME								
		DI	DROP INLET, DUCTILE IRON	FRP	FIBERGLASS REINFORCED PLASTIC								
		DIA	DIAMETER	FS	FLOOR SINK, FAR SIDE								
		DIAG	DIAGONAL, DIAGRAM	FT	FEET, FOOT								
		DIFF	DIFFERENTIAL, DIFFERENCE	FTG	FOOTING, FITTING FUR FURRED, FURRING								
		DIM	DIMENSION	FURN	FURNITURE, FURNISH								
		DISCH	DISCHARGE	FUT	FUTURE								
		DIST	DISTANCE, DISTRIBUTION	FV	FACE VELOCITY								
		DIV	DIVISION	FW	FIELD WELD, FIRE WALL								
		DL	DEAD LOAD	FWD	FORWARD								
		DN	DOWN	FWE	FURNISHED WITH EQUIPMENT								
		DP	DEPTH	FXTR	FIXTURE								
		DS	DOWN SPOUT			G	GRILLE, GROUND, GENERAL (DWG DISCIPLINE)						
		DT	DOUBLE TEE, DRIP TRAP ASSEMBLY			GA	GAGE (METAL THICKNESS)						
		DUP	DUPLICATE			GAL	GALLON						
		DWG	DRAWING			GALV	GALVANIZED						
		DWL	DOWEL			GB	GRADE BREAK						
						GD	GUARD						
		E	EAST, ELECTRICAL (DWG DISCIPLINE)			GEN	GENERAL						
		EA	EACH, EXHAUST AIR			GFCI	GROUND FAULT CIRCUIT INTERRUPTER						
		EC	ELECTRICAL CONTRACTOR			GL	GLASS						
		ECC	ECCENTRIC			GP	GUY POLE						
		EDB	ELECTRICAL DUCT BANK			GR	GRADE						
		EE	EACH END			GRND	GROUND						
		EF	EACH FACE			GRTG	GRATING						
		EG	EXISTING GRADE			GT	GREASE TRAP						
		EGL	ENERGY GRADE LINE			GWB	GYPSUM WALLBOARD						
		EFF	EFFLUENT, EFFICIENCY			GYP	GYPSUM HARDBOARD						
		EHH	ELECTRICAL HANDHOLE										
		EIFS	EXTERIOR INSULATION & FINISH SYSTEM			H	HIGH						
		EJ	EXPANSION JOINT			HB	HOSE BIB						
		EL	ELBOW, ELEVATION			HBD	HARDBOARD						
		ELEC	ELECTRICAL			HC	HANDICAPPED, HOLLOW CORE, HORIZONTAL CURVE						
		EMBD	EMBEDDED			HC	HORIZONTAL CENTERLINE						
		EMER	EMERGENCY			HDR	HEADER						
		EMH	ELECTRICAL MANHOLE			HDW	HARDWARE						
		ENCL	ENCLOSURE			HEX	HEXAGONAL						
		ENGR	ENGINEER			HH	HANDHOLE						
		ENTR	ENTRANCE			HM	HOLLOW METAL						
		EOP	EDGE OF PAVEMENT			HORIZ	HORIZONTAL						
		EOW	EDGE OF WATER			HP	HIGH POINT, HORSEPOWER						
		EQ	EQUAL			HPC	HORIZONTAL POINT OF CURVATURE						
		EQUIP	EQUIPMENT			HPS	HIGH PRESSURE SODIUM						
		EQUIV	EQUIVALENT			HPT	HORIZONTAL POINT OF TANGENCY						
		ES	EACH SIDE, EQUAL SPACE, EMERGENCY SHOWER			HR	HOOR						
		ESEW	EMERGENCY SHOWER AND EYE WASH			HS	HEADED STUD, HIGH STRENGTH						
		EST	ESTIMATE			HSS	HOLLOW STRUCTURAL SHAPE						
		EW	EACH WAY, EMERGENCY EYE/FACE WASH			HT	HEIGHT						
		EWG	ELECTRIC WATER COOLER			HV	HIGH VOLTAGE						
		EWEF	EACH WAY, EACH FACE			HVAC	HEATING, VENTILATION & AIR CONDITIONING						
		EWTB	EACH WAY, TOP AND BOTTOM			HWD	HARDWOOD						
		EXC	EXCAVATION			HWL	HIGH WATER LEVEL						
		EXH	EXHAUST			HYD	HYDRAULIC HZ HERTZ, CYCLES PER SECOND						
		EXIST	EXISTING										
		EXP	EXPANSION, EXPOSED										
		EXT	EXTERIOR, EXTERNAL, EXTENSION										
				</									

[illegible]



OVERALL SITE PLAN

SCALE: 1"= 100'



SHEET NOTES:

1. LIDAR SURVEY PROVIDED BY KRRC ON NOVEMBER 2020, CONTRACTOR SHALL CONFIRM AND VERIFY ELEVATIONS PRIOR TO CONSTRUCTION.
2. THE HORIZONTAL DATUM FOR THE PROJECT IS BASED UPON THE CALIFORNIA COORDINATE SYSTEM OF 1983, ZONE 1 NORTH AMERICAN DATUM OF 1983 (NAD83) IN FEET.
3. THE VERTICAL DATUM FOR THE PROJECT IS BASED UPON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88, GEOID 12B).

MAJOR CONSTRUCTION ITEMS:

- A CONSTRUCT NEW TEMPORARY PIPELINE.
- B SUPPORT THE TEMPORARY PIPELINE AT THE FALL CREEK CULVERT DURING CONSTRUCTION AND REMOVAL.
- C SUPPORT THE TEMPORARY PIPELINE ALONG THE DAGGETT ROAD BRIDGE DURING CONSTRUCTION AND REMOVAL.
- D DEMOLISH & DISPOSE OF EXISTING 24" DIAMETER WATERLINE. DISPOSE OF MATERIALS OFFSITE AT APPROVED LOCATION.
- E CONSTRUCT NEW 24" DIAMETER WATERLINE.
- F RETAIN AND PROTECT EXIST CATHODIC PROTECTION SYSTEM.

B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL
REV	DATE	BY	DESCRIPTION

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING
0 1/2 1
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.




KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE

OVERALL PLAN AND PROJECT CONTROL

DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. MCMILLEN
PROJECT DATE 02/05/21

DRAWING

G005



CONTRACTOR STAGING AREA PLAN
SCALE: 1"= 100'

- SHEET NOTES:**
1. CONTRACTOR SHALL COORDINATE LAYDOWN AND STAGING AREAS WITH OWNER.
 2. CONTRACTOR SHALL DEVELOP A DETAILED ACCESS PLAN IN ACCORDANCE WITH SPECIFICATIONS AND SUBMIT FOR REVIEW AND APPROVAL BY OWNER PRIOR TO INITIATING CONSTRUCTION ACTIVITIES.
 3. CONTRACTOR STAGING AREA IS SUGGESTED ONLY, AND WILL BE AT THE DISCRETION OF THE CONTRACTOR, SUBJECT TO APPROVAL BY THE OWNER AND ENGINEER.
 4. THE CONTRACTOR SHALL MAKE ITS OWN ARRANGEMENTS FOR ANY NECESSARY OFF-SITE STORAGE OR SHOP AREAS AS NECESSARY FOR THE PROPER EXECUTION OF THE WORK.
 5. THE CONTRACTOR SHALL DEVELOP AND SUBMIT TO THE ENGINEER A PLAN FOR STORING AND DISPOSING OF HAZARDOUS MATERIALS.
 6. THE CONTRACTOR SHALL RESTORE THE STAGING AREAS AT PROJECT COMPLETION TO PRE CONSTRUCTION CONDITIONS.

B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL
REV	DATE	BY	DESCRIPTION

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING
0 1/2 1
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.




KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
CONTRACTOR STAGING AREA

DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. McMILLEN
PROJECT DATE 02/05/21

DRAWING
G006

FLUID ABBREVIATION	FUNCTION	ALLOWABLE PIPING MATERIAL GROUP NO. (SEE NOTE 1 AND 4)				FIELD TEST REQUIREMENTS (SEE NOTE 3 AND NOTE 4)			PIPING MATERIAL SCHEDULE (SEE NOTE 1)				TYPICAL PIPE DESIGNATION:	
	THIS LIST MAY INCLUDE FLUIDS NOT USED IN THIS PROJECT	EXPOSED PIPING (SEE NOTE 14)		BURIED PIPING (SEE NOTE 13)		MINIMUM TEST PRESSURE PSI	TEST MEDIUM	LEAKAGE ALLOWANCE (SEE NOTE 2)	GROUP NO.	PIPE MATERIAL	FITTINGS / JOINTS	LININGS AND COATINGS (SEE NOTE 13)	NOTES:	
		3" DIA AND SMALLER	4" DIA AND LARGER	3" DIA AND SMALLER	4" DIA AND LARGER								NOTE 1 ALTHOUGH SEVERAL PIPE MATERIAL GROUPS MAY BE LISTED ON THIS SHEET FOR A GIVEN FLUID SERVICE, CONTRACTOR SHALL PROVIDE ONLY THE PIPE MATERIAL GROUP SHOWN ON THE DRAWINGS AND SPECIFIED FOR THAT FLUID SERVICE.	
													NOTE 2 LEAKAGE ALLOWANCE IS AS FOLLOWS A. PIPES SO DESIGNATED SHALL SHOW ZERO LEAKAGE. B. PIPES SO DESIGNATED SHALL SHOW ZERO LEAKAGE FOR UNBURIED PIPE AND NOT MORE THAN 0.02 GALLON PER HOUR PER INCH DIAMETER PER 100 FEET OF BURIED PIPE. C. PIPES SO DESIGNATED SHALL NOT SHOW A LEAKAGE OF MORE THAN 0.15 GALLON PER HOUR PER INCH OF DIAMETER PER 100 FEET OF PIPE. D. PIPES SO DESIGNATED SHALL NOT SHOW A LOSS OF PRESSURE OF MORE THAN 5 PERCENT. E. PIPE SO DESIGNATED SHALL NOT SHOW A LOSS OF VACUUM OF MORE THAN 4 INCHES MERCURY COLUMN.	
COMMONLY USED FUNCTIONS													NOTE 3 FOR FIELD TEST PROCEDURES AND ADDITIONAL TEST REQUIREMENTS, SEE PIPING SECTION OF SPECIFICATIONS.	
RW	RAW WATER	--	6,8	--	6,8	175	WATER	(A)	8	WELDED STEEL PIPE, CEMENT MORTAR LINING, ¾" WALL THICKNESS (AWWA C200 & MODIFIED PER SECTION 331111) (ALL PIPE CALLOUT DIAMETERS ARE 'ID' OF CML)	WELDED STEEL, AWWA C208 MODIFIED PER SECTION 33 11 11, FABRICATED.	SEE SECTION 33 11 11	NOTE 4 NO SUBSTITUTIONS U.N.O. IN THE SPECIFICATIONS.	
VT	VENT AIR	2	2	2	2	15 IN Hg	VACUUM	(A) (D)					NOTE 5 PIPING GROUP FUNCTION SHOWN THUS * SHALL BE INSULATED PER SPECIFICATIONS.	
													NOTE 6 STATIC WATER TEST WITH SURFACE 5 FEET ABOVE HIGH POINT OF PIPE.	
													NOTE 7 INSPECTION AND TESTING SHALL BE IN ACCORDANCE WITH APPLICABLE PLUMBING CODE.	
													NOTE 8 NO APPARENT LEAKS UNDER NORMAL OPERATING CONDITIONS.	
													NOTE 9 INSPECTION AND TESTING SHALL BE IN ACCORDANCE WITH APPLICABLE NATIONAL FIRE PROTECTION ASSOCIATION STANDARDS.	
													NOTE 10 PIPING MATERIALS SHALL BE IN ACCORDANCE WITH NATIONAL FIRE PROTECTION ASSOCIATION STANDARDS.	
													NOTE 11 FOR VALVES 4" AND LARGER SEE VALVE SCHEDULE FOR SPECIAL VALVES SEE SPECIFICATIONS.	
													NOTE 12 CHANGE IN PIPING MATERIAL GROUP NUMBER IS INDICATED THUS: ———→	
													NOTE 13 FOR FULL PIPE LINING AND COATING REQUIREMENTS, SEE SPECIFICATIONS.	
													NOTE 14 EXPOSED OUTDOOR PIPING SHALL BE PAINTED IN ACCORDANCE WITH SPECIFICATIONS. COLORS TO BE SELECTED BY OWNER.	
													NOTE 15 NOT USED	
													NOTE 16 NOT USED	
													NOTE 17 FOR HDPE PIPING THE SIZE OF PIPE SHOWN ON DRAWING CALL-OUTS SHALL BE THE MINIMUM INSIDE DIAMETER. PIPE WALL THICKNESS SHALL BE PER DR RATING REQUIREMENT.	

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--



SILT FENCE DETAIL
SCALE: NTS


TABLE 1
FENCE SPACING FOR GENERAL APPLICATION
INSTALL PARALLEL ALONG CONTOURS AS FOLLOWS

GRADE	MAXIMUM SPACING ON GRADE
GRADE ≤ 0%	300'
10% ≤ GRADE < 15%	150'
15% ≤ GRADE < 20%	100'
20% ≤ GRADE < 30%	50'
30% ≤ GRADE	25'

TABLE 2
POST SPACING

POST SPACING	POST SPACING
4'	SUPPORTED SEDIMENT FENCE
6'	UNSUPPORTED SEDIMENT FENCE WITH GEOTEXTILE ELONGATION * LESS THAN 50%
4'	UNSUPPORTED SEDIMENT FENCE WITH GEOTEXTILE ELONGATION * MORE THAN 50%


* GEOTEXTILE GRAB ELONGATION VALUE AS DOCUMENTED BY "LEVEL B" MANUFACTURER'S DOCUMENTATION (SEE STANDARD SPECIFICATIONS).




BARRIER SPACING FOR GENERAL APPLICATION
INSTALL PARALLEL ALONG CONTOURS AS FOLLOWS

% SLOPE	% SLOPE	MAXIMUM SPACING ON SLOPE
10% FLATTER	1:10 OR FLATTER	300'
10 > % ≥ 15	10 > X ≥ 7.5	150'
15 > % ≥ 20	7.5 > X ≥ 5	100'
20 > % ≥ 30	5 > X ≥ 3	50'
STEEPER THAN 30%	STEEPER THAN 1:3	25'

- NOTES
1. INSTALL WATTLES ALONG CONTOURS.
 2. WATTLES SHALL BE INSPECTED REGULARLY, AND IMMEDIATELY AFTER A RUNOFF PRODUCING RAINFALL, TO ENSURE THEY REMAIN THOROUGHLY ENTRENCHED AND IN CONTACT WITH THE SOIL.
 3. INSTALL WATTLES SNUGLY INTO THE TRENCH. ABUT ADJACENT WATTLES TIGHTLY, END TO END, WITHOUT OVERLAPPING THE ENDS.
 4. PILOT HOLES MAY BE DRIVEN THROUGH THE WATTLE AND INTO THE SOIL, WHEN SOIL CONDITIONS REQUIRE.




TEMPORARY ENTRANCE
SCALE: NTS



- NOTE:
1. TURBIDITY BLANKET TO BE CSI GEOSYNTHETICS OR EQUAL.

TURBIDITY CURTAIN
SCALE: NTS




- NOTES
1. INSTALL WATTLES ALONG CONTOURS. SEE TABLE FOR SPACING.
 2. WATTLES SHALL BE INSPECTED REGULARLY, AND IMMEDIATELY AFTER A RUNOFF PRODUCING RAINFALL, TO ENSURE THEY REMAIN THOROUGHLY ENTRENCHED AND IN CONTACT WITH THE SOIL.
 3. LIVE STAKES MAY BE USED FOR PERMANENT INSTALLATIONS.
 4. INSTALL WATTLES SNUGLY INTO THE TRENCH. ABUT ADJACENT WATTLES TIGHTLY, END TO END, WITHOUT OVERLAPPING THE ENDS.
 5. PILOT HOLES MAY BE DRIVEN THROUGH THE WATTLE AND INTO THE SOIL, WHEN SOIL CONDITIONS REQUIRE.
 6. INSTALL AT TOE OF SLOPES. SLOPES GREATER THAN 15' IN LENGTH SHALL HAVE A WATTLE INSTALLED MID SLOPE.

WATTLE
SCALE: NTS

WATTLE SPACING TABLE

SLOPE	MAXIMUM SPACING
1:1	10 FEET
2:1	20 FEET
3:1	30 FEET
4:1	40 FEET
>4:1	80 FEET



REV	DATE	BY	DESCRIPTION
B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.


McMILLEN
JACOBS
ASSOCIATES

KLAMATH
RIVER RENEWAL
CORPORATION

KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
EROSION AND SEDIMENT CONTROL STANDARD
DETAILS 1

DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. McMILLEN
PROJECT DATE 02/05/21

DRAWING
EC001



- NOTES:
- 1. SEE SPECIFICATIONS FOR FENCE MATERIAL, COATINGS, AND INSTALLATION REQUIREMENTS.
 - 2. EXTENSION ARM MAY BE TURNED IN AT OPTION OF OWNER.

CONSTRUCTION FENCING DETAIL

SCALE: NTS



B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL
REV	DATE	BY	DESCRIPTION

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.




KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
EROSION AND SEDIMENT CONTROL STANDARD DETAILS 2


DESIGNED	J. BURNS
DRAWN	R. WOOD
CHECKED	M. MCMILLEN
PROJECT DATE	02/05/21

DRAWING

EC002



EROSION AND SEDIMENT CONTROL PLAN
SCALE: 1"= 100'



SHEET NOTES:

1. THE EXPOSED AND DISTURBED AREAS SHALL BE REGRADED TO MATCH EXISTING AND RESEED WITH NATIVE GRASS PER OWNER REQUIREMENTS
2. ALL FILL MATERIALS AND COMPACTION REQUIREMENTS ARE DEFINED IN SPECIFICATION SECTION 31 00 00.
3. MATCH EXISTING GRADE AND PROVIDE SMOOTH TRANSITION BETWEEN ALL NEW SURFACING AND EXISTING GRADE.
4. COFFERDAM SHALL BE DESIGNED AND CONSTRUCTED BY CONTRACTOR, REFER TO SPECIFICATION 01 12 00 FOR DETAILS OF THE SITE HYDROLOGY.

EROSION AND SEDIMENT CONTROL NOTES:

GENERAL NOTES:

1. THE CONTRACTOR SHALL SUBMIT AN EROSION AND SEDIMENT CONTROL PLAN FOR WORK DURING CONSTRUCTION THAT MEETS ALL FEDERAL, STATE, AND LOCAL REQUIREMENTS.
 - A. THE CONTRACTOR IS RESPONSIBLE FOR IMPLEMENTATION AND MAINTENANCE OF EROSION AND SEDIMENT CONTROL MEASURES (MULCHING OF STRAW, SAND DIVERSION DITCHES, ETC.) DICTATED BY FIELD CONDITIONS TO PREVENT EROSION OR THE INTRODUCTION OF DIRT, MUD, OR DEBRIS TO EXIST PUBLIC OR PRIVATE ROADWAY, ONTO ADJACENT PROPERTIES, INTO FALL CREEK, OR INTO KLAMATH RIVER DURING ANY PHASE OF CONSTRUCTION OPERATIONS. SPECIAL ATTENTION SHALL BE GIVEN TO ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES NOTED BELOW.
 - B. THE GENERAL EROSION AND SEDIMENT CONTROL PLAN ON THE EC DRAWINGS ARE PROVIDED TO AID THE CONTRACTOR IN DEVELOPING THE EROSION AND SEDIMENT CONTROL PLAN ACCORDING TO CONTRACTOR SCHEDULE AND PHASING OF THE PROJECT.
 - C. EROSION CONTROL DETAILS ARE FOR INFORMATION ONLY TO AID THE CONTRACTOR. THE FINAL LOCATIONS AND DETAIL SHALL BE SHOWN ON THE CONTRACTOR'S PREPARED STORMWATER POLLUTION PREVENTION PLAN (SWPPP) DOCUMENT.
 - D. CONTRACTOR IS RESPONSIBLE TO PROVIDE ALL NECESSARY EROSION CONTROL MEASURES FOR THE DURATION OF THE PROJECT. MAINTENANCE OF BOTH TEMPORARY AND PERMANENT EROSION CONTROL MEASURES SHALL BE CONSIDERED INCIDENTAL.
 - E. ALL BMP REQUIRED MATERIALS SHALL MEET OR EXCEED STATE OF CALIFORNIA STORMWATER QUALITY ASSOCIATION (CASQA) REQUIREMENTS.
 - F. CONTRACTOR SHALL DEVELOP A SPILL PREVENTION, CONTAINMENT, AND RESPONSE PLAN THAT WILL BE ATTACHED TO THE SWPPP.

GRADING AND FINAL STABILIZATION:

1. CLEARING, GRUBBING, AND GROUND DISTURBING ACTIVITIES SHALL BE CONFINED TO WITHIN CLEARING LIMITS AND SHALL MEET THE REQUIREMENTS OF SPECIFICATION 31 11 00. NO GRADING OR CONSTRUCTION ACTIVITIES SHALL OCCUR OUTSIDE OF THE PROPOSED IMPROVEMENTS SHOWN ON THE CONSTRUCTION PLANS FOR THIS PROJECT. PRESERVE EXIST VEGETATION BEYOND DISTURBED AREA - UTILIZE AS NATURAL BUFFER STRIPS.
2. DURING CONSTRUCTION, PROVIDE POSITIVE DRAINAGE AWAY FROM FACILITIES.
3. CONTRACTOR SHALL REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL FACILITIES, FENCING, AND STAGING AREA MATERIALS WHEN CONSTRUCTION IS COMPLETE. NO CONSTRUCTION DEBRIS, DEMOLITION MATERIALS, OR EXCESS EQUIPMENT SHALL BE LEFT ON SITE.
4. CONTRACTOR SHALL REGRADE DISTURBED SLOPED TO NEAR EXIST CONDITION AS APPROVED BY THE OWNER.
5. ESTABLISH A TEMPORARY VEGETATIVE COVER ON ALL DISTURBED AREAS AS SOON AS PRACTICAL AFTER THE LAST GROUND DISTURBING ACTIVITIES IN THE AREA. CONTRACTOR SHALL RESEED ALL DISTURBED AREAS WITH NATIVE VEGETATION, PER SPECIFICATION 31 35 30, AND IN ACCORDANCE WITH SHEET EC100.

BMP MEASURES:

1. ALL RUNOFF FROM SITE CONSTRUCTION ACTIVITIES AND FROM RAINFALL EVENTS SHALL BE DETAINED ON SITE AND FILTERED PRIOR TO DISCHARGE. STORMWATER RUNOFF SHALL NOT BE ALLOWED TO LEAVE THE SITE UNTREATED (LADEN W/ SUSPENDED SEDIMENT). IF THIS OCCURS, THE CONTRACTOR WILL BE HELD SOLELY RESPONSIBLE FOR ANY PERMIT VIOLATIONS AND FINES.
2. CONTRACTOR SHALL TAKE APPROPRIATE MEASURES TO PREVENT ACCUMULATION OF CONSTRUCTION WASTE AND LITTER ON-SITE.
3. CONTRACTOR SHALL INSTALL SILT FENCE AND/OR STRAW WATTLES AS INDICATED AND IN ANY ADDITIONAL LOCATIONS WHERE MATERIAL COULD LEAVE THE CONSTRUCTION SITE, AT CONTRACTOR'S EXPENSE.
4. THE SILT FENCE AND/OR STRAW WATTLES SHALL BE INSTALLED PRIOR TO ANY CONSTRUCTION ACTIVITIES.
5. CONTRACTOR SHALL HAVE AVAILABLE AT ALL TIMES ADEQUATE SPRINKLER EQUIPMENT TO FACILITATE DUST ABATEMENT AND CONTROL. CONTRACTOR SHALL PROVIDE ALL WATER NECESSARY FOR SPRINKLER OPERATIONS.
6. STOCKPILED EXCAVATION MATERIALS SHALL BE PROTECTED FROM WATER AND WIND EROSION BY COVERING AS APPROPRIATE. WHEN EXPOSED FOR MORE THAN 14 DAYS, COVER STOCKPILES WITH IMPERMEABLE TARPES TO PROTECT DISTURBED SOILS AND SLOPES.
7. ALL TOP SOIL SHALL BE STRIPPED AND PLACED IN SEPARATE STOCKPILE. AFTER BANK RESTORATION TO EXIST GRADE, TOP SOIL SHALL BE PLACED AND RESEED.
8. CONTRACTOR SHALL HAVE ON-SITE AT ALL TIMES SPILL PREVENTION AND CONTROL MEASURES.
9. ENSURE ALL EQUIPMENT IS CLEAN AND FREE OF OIL/FUEL LEAKS, DIRT, PLANTS, AND ANIMALS OR FRAGMENTS OF PLANTS, AQUATIC INVASIVE SPECIES, AND OTHER VEGETATIVE MATTER.

B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL
REV	DATE	BY	DESCRIPTION

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING
0 1/2 1
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.



KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
EROSION AND SEDIMENT CONTROL PLAN

DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. MCMILLEN
PROJECT DATE 02/05/21


DRAWING
EC100

CLEARING AND GRUBBING CONTROL POINTS			
POINT NO	NORTHING	EASTING	DESCRIPTION
◊200◊	2601591.04	6461314.59	CLEARING AND GRUBBING LIMITS
◊201◊	2601559.03	6461315.82	CLEARING AND GRUBBING LIMITS
◊202◊	2601456.61	6461281.40	CLEARING AND GRUBBING LIMITS
◊203◊	2601328.69	6461197.31	CLEARING AND GRUBBING LIMITS
◊204◊	2601270.74	6461292.00	CLEARING AND GRUBBING LIMITS
◊205◊	2601273.82	6461559.72	CLEARING AND GRUBBING LIMITS
◊206◊	2601276.90	6461827.45	CLEARING AND GRUBBING LIMITS
◊207◊	2601652.33	6461964.53	CLEARING AND GRUBBING LIMITS
◊208◊	2601863.50	6462316.97	CLEARING AND GRUBBING LIMITS
◊209◊	2602074.68	6462669.41	CLEARING AND GRUBBING LIMITS
◊210◊	2602168.50	6462651.74	CLEARING AND GRUBBING LIMITS
◊211◊	2602203.04	6462644.91	CLEARING AND GRUBBING LIMITS
◊212◊	2602163.99	6462707.60	CLEARING AND GRUBBING LIMITS
◊213◊	2602049.59	6462724.69	CLEARING AND GRUBBING LIMITS
◊214◊	2601833.38	6462365.36	CLEARING AND GRUBBING LIMITS
◊215◊	2601617.18	6462006.03	CLEARING AND GRUBBING LIMITS
◊216◊	2601226.80	6461862.75	CLEARING AND GRUBBING LIMITS
◊217◊	2601225.07	6461568.41	CLEARING AND GRUBBING LIMITS
◊218◊	2601222.90	6461274.38	CLEARING AND GRUBBING LIMITS
◊219◊	2601333.65	6461093.42	CLEARING AND GRUBBING LIMITS
◊220◊	2601268.67	6461041.93	CLEARING AND GRUBBING LIMITS
◊221◊	2601258.02	6460966.22	CLEARING AND GRUBBING LIMITS
◊222◊	2601356.68	6460838.26	CLEARING AND GRUBBING LIMITS
◊223◊	2601447.10	6460973.34	CLEARING AND GRUBBING LIMITS
◊224◊	2601523.20	6461163.01	CLEARING AND GRUBBING LIMITS
◊225◊	2601573.73	6461181.16	CLEARING AND GRUBBING LIMITS
◊226◊	2601600.89	6461234.49	CLEARING AND GRUBBING LIMITS
◊227◊	2602056.30	6461384.92	CLEARING AND GRUBBING LIMITS
◊228◊	2602020.94	6461427.94	CLEARING AND GRUBBING LIMITS
◊229◊	2602011.59	6461422.01	CLEARING AND GRUBBING LIMITS

CLEARING AND GRUBBING CONTROL POINTS			
POINT NO	NORTHING	EASTING	DESCRIPTION
◊230◊	2601963.28	6461428.54	CLEARING AND GRUBBING LIMITS
◊231◊	2601950.26	6461389.07	CLEARING AND GRUBBING LIMITS
◊232◊	2601980.79	6461392.94	CLEARING AND GRUBBING LIMITS
◊233◊	2601987.28	6461340.64	CLEARING AND GRUBBING LIMITS
◊234◊	2601976.38	6461289.67	CLEARING AND GRUBBING LIMITS
◊235◊	2601958.76	6461251.41	CLEARING AND GRUBBING LIMITS
◊236◊	2601957.34	6461215.84	CLEARING AND GRUBBING LIMITS
◊237◊	2601986.41	6461225.11	CLEARING AND GRUBBING LIMITS
◊238◊	2602008.87	6461195.30	CLEARING AND GRUBBING LIMITS
◊239◊	2602025.64	6461198.77	CLEARING AND GRUBBING LIMITS
◊240◊	2602018.73	6461281.84	CLEARING AND GRUBBING LIMITS
◊241◊	2602024.95	6461338.98	CLEARING AND GRUBBING LIMITS
◊242◊	2602364.18	6461841.28	CLEARING AND GRUBBING LIMITS
◊243◊	2602357.88	6461901.54	CLEARING AND GRUBBING LIMITS
◊244◊	2602346.71	6461901.23	CLEARING AND GRUBBING LIMITS
◊245◊	2602261.96	6461705.51	CLEARING AND GRUBBING LIMITS
◊246◊	2602273.13	6461680.79	CLEARING AND GRUBBING LIMITS
◊247◊	2602312.41	6461716.81	CLEARING AND GRUBBING LIMITS
◊248◊	2602337.27	6461764.82	CLEARING AND GRUBBING LIMITS
◊249◊	2602430.95	6461763.76	CLEARING AND GRUBBING LIMITS
◊250◊	2602426.37	6461773.84	CLEARING AND GRUBBING LIMITS
◊251◊	2602425.11	6462173.73	CLEARING AND GRUBBING LIMITS
◊252◊	2602415.89	6462242.90	CLEARING AND GRUBBING LIMITS
◊253◊	2602363.52	6462427.33	CLEARING AND GRUBBING LIMITS
◊254◊	2602342.31	6462475.11	CLEARING AND GRUBBING LIMITS
◊255◊	2602316.31	6462455.37	CLEARING AND GRUBBING LIMITS
◊256◊	2602335.38	6462416.64	CLEARING AND GRUBBING LIMITS
◊257◊	2602386.44	6462236.79	CLEARING AND GRUBBING LIMITS
◊258◊	2602395.11	6462171.69	CLEARING AND GRUBBING LIMITS
◊259◊	2602396.37	6461772.86	CLEARING AND GRUBBING LIMITS
◊260◊	2602403.01	6461746.40	CLEARING AND GRUBBING LIMITS

B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL
REV	DATE	BY	DESCRIPTION

PRELIMINARY
NOT FOR CONSTRUCTION



KLAMATH RIVER RENEWAL CORPORATION

CITY OF YREKA WATER LINE

EROSION AND SEDIMENT CONTROL SITE
COORDINATES

DESIGNED J. BURNS


DRAWN R. WOOD

CHECKED M. MCMILLEN

PROJECT DATE 02/05/21

DRAWING

EC101





- SHEET NOTES:**
1. CONTRACTOR SHALL DEMOLISH AND DISPOSE OF EXISTING 24-INCH DIAMETER PIPELINE AFTER THE TEMPORARY PIPELINE IS IN SERVICE AND OPERATIONAL AS APPROVED BY OWNER. DISPOSE OF MATERIALS OFFSITE AT APPROVED DISPOSAL LOCATION.
 2. THE EXISTING ROCK LINE IS BASED SOLELY UPON EXISTING BORINGS COMPLETED FOR THE PROJECT. SEE SPECIFICATIONS FOR DETAILED BORING INFORMATION. CONTRACTOR SHALL VERIFY THE LOCATION OF ROCK LINE PRIOR TO CONSTRUCTION OF THE NEW 24-INCH DIAMETER PERMANENT PIPELINE.

PLAN

SCALE: 1"= 20'

0" 20' 40'




PROFILE

SCALE: HORIZ 1"= 20'

VERT 1"= 10'

0" 20' 40'



EXISTING UNDER WATER RIPRAP DETAIL

SCALE: NTS

1

REV	DATE	BY	DESCRIPTION
B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.

**McMILLEN
JACOBS
ASSOCIATES**

**KLAMATH
RIVER RENEWAL
CORPORATION**

KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
DEMOLITION WATERLINE PLAN AND PROFILE

DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. McMILLEN
PROJECT DATE 02/05/21

DRAWING
D101

Path: C:\Vault20\Klamath River Renewal Corp\City of Yreka Water Line\D101.dwg Plot date: Feb 05, 2021 04:57pm, CAD User: rooney

JOB NO: 000000

GENERAL PROJECT NOTES:

- 1. EXISTING TOPOGRAPHY, STRUCTURES, AND SITE FEATURES ARE SHOWN SCREENED AND/OR LIGHT-LINED. NEW FINISH GRADE, STRUCTURES, AND SITE FEATURES ARE SHOWN UNSCREENED AND HEAVY-LINED.
- 2. MAINTAIN, RELOCATE, OR REPLACE EXISTING SURVEY MONUMENTS, CONTROL POINTS, AND STAKES WHICH ARE DISTURBED OR DESTROYED. PERFORM THE WORK TO PRODUCE THE SAME LEVEL OF ACCURACY AS THE ORIGINAL MONUMENT(S) IN A TIMELY MANNER, AND AT THE CONTRACTOR'S EXPENSE.
- 3. VERTICAL DATUM BASED UPON NAVD 88 DATUM, GEOID 12B.
- 4. HORIZONTAL DATUM BASED UPON THE CALIFORNIA COORDINATE SYSTEM OF 1983, ZONE 1 NORTH AMERICAN DATUM OF 1983 (NAD83) IN FEET.
- 5. STAGING AREA SHALL BE FOR CONTRACTOR'S EMPLOYEE PARKING, CONTRACTOR'S TRAILERS AND ON-SITE STORAGE OF MATERIALS, SEE SHEET G006. COORDINATE SPECIFIC AREA LIMITS WITH OWNER.
- 6. ELEVATIONS GIVEN ARE TO FINISH GRADE UNLESS OTHERWISE SHOWN.
- 7. SLOPE UNIFORMLY BETWEEN CONTOURS AND SPOT ELEVATIONS SHOWN.
- 8. A GEOTECHNICAL EVALUATION WAS PREFORMED FOR THIS PROJECT. A 2019 GEOTECHNICAL ENGINEERING EVALUATION REPORT WAS PREPARED BY AECOM TECHNICAL SERVICES AND CDM SMITH. A GEOTECHNICAL MEMO WAS PREPARED BY CDM SMITH BASED ON THE REVIEW OF THE LARGER REPORT FOR THIS PROJECT AND IS ATTACHED TO THE PROJECT SPECIFICATIONS.
- 9. CONTRACTOR SHALL CONTACT KRRC A MINIMUM OF 48 HOURS PRIOR TO COMMENCING CONSTRUCTION ACTIVITIES TO REQUEST VERIFICATION OF UNDERGROUND UTILITY LOCATIONS.
- 10. PROVIDE MINIMUM 3-FT COVER OVER WATER MAIN PIPES UNLESS OTHERWISE INDICATED ON THE DRAWINGS.
- 11. CONTRACTOR SHALL KEEP CONSTRUCTION ACTIVITIES WITHIN THE SITE BOUNDARIES FOR THIS PROJECT AS SHOWN. THIS INCLUDES, BUT IS NOT LIMITED TO, VEHICLES AND EQUIPMENT. LIMITS OF TRENCH EXCAVATION, STOCKPILED EXCAVATED MATERIALS, BACKFILL MATERIAL, AND PIPE MATERIAL.

GENERAL CONSTRUCTION NOTES:

- 1. CONTRACTOR SHALL ATTEND A PRE-CONSTRUCTION CONFERENCE (OR AN ON-SITE MEETING) WITH THE PROJECT REPRESENTATIVE PRIOR TO THE START OF WORK.
- 2. CONTRACTOR SHALL NOTIFY THE PROJECT REPRESENTATIVE WHEN MATERIALS ARE ON SITE OR INSPECTION OF THE WORK IS REQUIRED. NO WORK MAY BEGIN ON ANY PROJECT WITHOUT TWENTY FOUR (24) HOUR PRIOR NOTICE.
- 3. ALL MATERIAL FURNISHED ON, OR FOR THE PROJECT MUST MEET THE MINIMUM REQUIREMENTS OF THE APPROVING AGENCIES. AT THE REQUEST OF THE APPROVING AGENCY OR THE DESIGN ENGINEER, CONTRACTOR SHALL FURNISH PROOF THAT ALL MATERIALS INSTALLED ON THIS PROJECT MEET THE SPECIFICATION REQUIREMENTS SET FORTH IN THE PROJECT SPECIFICATIONS.
- 4. WORK SUBJECT TO APPROVAL BY ENGINEER MUST BE APPROVED PRIOR TO (A) BACKFILL TRENCHES FOR PIPE; (B) PLACING OF AGGREGATE BASE; (C) PLACING OF CONCRETE; (D) PLACING OF ASPHALT PAVING; (E) OR AS OTHERWISE SPECIFIED.
- 5. ANY DEVIATION FROM THE APPROVED PLANS AND SPECIFICATIONS MUST HAVE DESIGN ENGINEER AND OWNER APPROVAL IN WRITING PRIOR TO CONSTRUCTION.
- 6. ALL DISTURBED SURFACES SHALL BE RETURNED TO ORIGINAL OR BETTER CONDITIONS.


GENERAL YARD PIPING AND UTILITIES NOTES:

- 1. EXISTING UNDERGROUND UTILITIES OBTAINED FROM AS-BUILTS AND FROM TOPOGRAPHIC FIELD SURVEY PROVIDED BY KRRP. CONTRACTOR SHALL FIELD VERIFY DEPTH AND LOCATION PRIOR TO EXCAVATION. CONTRACTOR SHALL PROTECT ALL EXISTING UTILITIES DURING CONSTRUCTION. IF EXISTING UTILITIES (GAS, ELECTRIC, POTABLE WATER, ETC.) ARE IN CONFLICT WITH THE PIPELINE REALIGNMENT OR TRENCH ALIGNMENT, CONTRACTOR SHALL CONTACT ENGINEER.
- 2. EXISTING PIPING AND EQUIPMENT ARE SHOWN SCREENED AND/OR LIGHT-LINED. NEW PIPING AND EQUIPMENT ARE SHOWN UNSCREENED AND HEAVY-LINED.
- 3. ALL PIPES SHALL HAVE CONSTANT UNIFORM SLOPE.
- 4. THE HORIZONTAL SEPARATION OF POTABLE WATER MAINS AND NON-POTABLE WATER MAINS (SANITARY SEWER, STORM DRAIN, AND IRRIGATION) SHALL BE A MINIMUM OF TEN (10) FEET OUTSIDE OF PIPE TO OUTSIDE OF PIPE. WHERE IT IS NECESSARY FOR A POTABLE WATER MAIN AND NON-POTABLE WATER MAIN TO CROSS WITH LESS THAN EIGHTEEN (18) INCHES OF VERTICAL SEPARATION. THE CROSSING SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION 64572, TITLE 22, CALIFORNIA ADMINISTRATION CODE.
- 5. CONTRACTOR SHALL REPAIR ALL EXISTING SURFACES, UTILITIES, BUILDINGS AND FOUNDATIONS IMPACTED BY CONSTRUCTION.
- 6. ALL VALVES SET FLUSH WITH GRADE SHALL HAVE BOXES AND COLLARS.

DESIGN CRITERIA			
CRITERIA	UNITS	VALUE	COMMENTS
MAXIMUM DESIGN FLOW	CFS	15	MAXIMUM DESIGN FLOW WITH THREE PUMPS RUNNING
AVERAGE SUMMER PEAK FLOW RATE	CFS	11	PEAK FLOW RATE DURING SUMMER MONTHS WITH TWO PUMPS RUNNING
AVERAGE WINTER PEAK FLOW RATE	CFS	6	PEAK FLOW RATE DURING WINTER MONTHS WITH ONE PUMP RUNNING
DESIGN HYDROSTATIC PRESSURE	PSIG	308	
DESIGN MAXIMUM SURGE PRESSURE	PSIG	375	
PIPE DIAMETER	IN	24	STEEL PIPE WITH WALL THICKNESS = ¾" WITH CEMENT MORTAR LINING. COAL TAR ENAMEL WITH ADDITIONAL 3-INCH CEMENT MORTAR EXTERIOR COATING

B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL
REV	DATE	BY	DESCRIPTION

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING

IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.




KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE

GENERAL CIVIL NOTES

DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. MCMILLEN
PROJECT DATE 02/05/21

DRAWING


GC001




ASPHALT REPAIR
SCALE: NTS

DRAIN BLIND FLANGE TO GRADE
SCALE: NTS


- A. FLEXIBLE PIPE REFERS TO ALL STEEL, AND HDPE PLASTIC PIPES.
B. TYPICAL TRENCH SECTION TO BE USED ONLY WHERE STABLE, COMPACT SOIL CONDITIONS EXIST. IF BOULDERS OR LARGE OBSTRUCTIONS ARE ENCOUNTERED, TRENCH SECTIONS MAY BE DEEPER OR WIDER THAN SHOWN. THE ENGINEER SHALL BE ADVISED SHOULD THIS OCCUR.
C. THE NEED FOR PROTECTIVE SYSTEMS AND EXCAVATION SLOPES SHALL BE DETERMINED CONSIDERING APPLICABLE LOCAL, STATE AND FEDERAL (OSHA) SAFETY STANDARDS AND REGULATIONS, AND GEOTECHNICAL CONSULTANTS' RECOMMENDATIONS.
D. PROTECTIVE SYSTEMS SHALL BE DESIGNED AND BUILT IN ACCORDANCE WITH THE APPLICABLE LOCAL, STATE AND FEDERAL (OSHA) SAFETY STANDARDS AND REGULATIONS.
E. SUPPORTING DOCUMENTATION SHALL BE SUBMITTED TO THE ENGINEER REGARDING PIPE DESIGN AND COMPLIANCE WITH APPLICABLE LOCAL, STATE AND FEDERAL (OSHA) SAFETY STANDARDS.
F. UNSUPPORTED VERTICAL AND/OR SLOPING TRENCH WALL SLOPES SHALL NOT BE STEEPER THAN ALLOWED BY APPLICABLE LOCAL, STATE AND FEDERAL (OSHA) SAFETY STANDARDS AND REGULATIONS, UNLESS SUPPORTING DOCUMENTATION IS SUBMITTED, ACCORDING TO AFOREMENTIONED SAFETY STANDARDS.
G. TRENCH SECTIONS OTHER THAN THE TYPICAL SECTION SHOWN MAY BE UTILIZED PROVIDED THEY COMPLY WITH APPLICABLE LOCAL, STATE AND FEDERAL (OSHA) SAFETY STANDARDS AND REGULATIONS. DOCUMENTATION SUPPORTING THIS COMPLIANCE AND PIPE DESIGN CALCULATIONS SHALL BE SUBMITTED TO THE ENGINEER.
H. IF OVER-EXCAVATION DUE TO POOR FOUNDATION MATERIAL IS ORDERED BY THE ENGINEER, THE BACKFILL MATERIAL SHALL BE ACCORDING TO THE EARTHWORK SECTION OF THE SPECIFICATIONS ARTICLE ENTITLED, "FILL AND BACKFILL MATERIAL REQUIREMENTS."
I. IF DURING CONSTRUCTION, THE WATER TABLE IS DISCOVERED TO BE ABOVE THE TRENCH BOTTOM, THE ENGINEER SHALL BE NOTIFIED, AND APPROPRIATE DEWATERING SHALL BE IMPLEMENTED TO LOWER THE WATER LEVEL BELOW THE TRENCH BOTTOM. THE BACKFILL MATERIAL SHALL BE ACCORDING TO THE EARTHWORK SECTIONS OF THE SPECIFICATIONS, OR AS ORDERED BY THE ENGINEER.
J. IF CONTRACTOR SELECTS CLSM PIPE ZONE BACKFILL, THEN ELIMINATE THE SAND BEDDING MATERIAL AND USE CLSM FOR BEDDING ALSO.



TRENCH SECTION FLEXIBLE PIPE (FOR TEMP PIPELINE ONLY)
SCALE: NTS



BURIED VALVE INSTALLATION
SCALE: NTS



VALVE BOX COLLAR
SCALE: NTS

REV	DATE	BY	DESCRIPTION
B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING
0 1/2 1
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.


McMILLEN
JACOBS
ASSOCIATES

KLAMATH
RIVER RENEWAL
CORPORATION

KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
CIVIL STANDARD DETAILS 1

DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. McMILLEN
PROJECT DATE 02/05/21


DRAWING
GC002



PIPELINE MARKER
SCALE: NTS

STEEL PIPE BELL AND SPIGOT LAP JOINT WELD
SCALE: NTS

STEEL PIPE - BUTT WELD JOINT (SINGLE OUTSIDE BEVEL)
SCALE: NTS




BUTT STRAP JOINT (WSP - FLEXIBLE/DIELECTRIC COATING SYSTEM)
SCALE: NTS

CONCRETE ENCASED TRENCH PIPE
SCALE: NTS



DRAIN LINE
SCALE: 1/2"=1'-0"

Path: C:\Vault20\Klamath River Renewal Corp\City of Yreka Water Line\GC003.dwg Plot date: Feb 05, 2021 04:57pm, CAD User: rooney


JOB NO: 000000



- NOTES:
1. IF POSSIBLE, MAKE WIRE CONNECTION TO STEEL PIPE AT FIELD JOINT AT HOLDBACK OF PIPELINE COATING.
 2. MAINTAIN SEPARATION BETWEEN MULTIPLE TEST WIRE CONNECTIONS OF ONE PIPE DIA OR 12", WHICHEVER IS LESS.
 3. COPPER SLEEVE REQUIRED FOR #2 AWG JOINT BONDS OR FOR #12 AWG OR SMALLER TEST WIRES.
 4. WELDER AND CARTRIDGE SIZE VARIES ACCORDING TO PIPE SIZE AND PIPE MATERIAL, CONSULT WELDER MANUFACTURER FOR RECOMMENDED WELDER AND CARTRIDGE.
 5. COAT COMPLETED CONNECTIONS WITH DIELECTRIC COATING AS SPECIFIED.
 6. PIPELINE JOINT COATING NOT SHOWN FOR CLARITY.



- NOTE:
1. FOR PIPING SYSTEM WITH SERVICE PRESSURE CLASS GREATER THAN 150 PSI. ALL COMPONENTS FURNISHED SHALL BE SUITABLE FOR THE HIGHER PRESSURE.



PIPE WIRE CONNECTION DETAIL


SCALE: NTS

BANK RIPRAP DETAIL

SCALE: NTS

AIR-VACUUM AND AIR-RELEASE VALVE ASSEMBLY - 3" AND SMALLER

SCALE: NTS



- NOTES:
1. PRECAST MANHOLE SHALL BE TYPE 1 MANHOLE OR APPROVED EQUAL. INSTALLATION SHALL BE PER MANUFACTURER'S RECOMMENDATIONS. ACCESS TO MANHOLE SHALL BE EQUIPPED WITH LOCKING DEVICES AND FRP STEPS CAST INTO WALLS.
 2. PROVIDE VAULTS AT ALL MANHOLES AND AT ALL AIR VALVE LOCATIONS.
 3. ISOLATION VALVE SHALL BE 3"Ø BRASS BALL VALVE 2-PART W/ NPT ENDS AND MIN 600 PSI RATED COLD WORKING PRESS.




TABLE FOR BURIED THRUST BLOCKS, DETAIL C-406																
PIPE BEND (DEG):	35.0				45.0				70.0				90.0			
	< 100	< 300	< 400	< 500	< 100	< 300	< 400	< 500	< 100	< 300	< 400	< 500	< 100	< 300	< 400	< 500
MAX HYDROSTATIC: PRESSURE (PSI)																
NOM PIPE DIAMETER (OD) [inches]	Bearing Capacity 3,500 PSF*															
24	6	23	31	36	10	30	40	43	15	41	59	74	18	55	73	91

*NOTE THAT THIS BEARING CAPACITY DOES NOT APPLY TO ANY OTHER PORTIONS OF PROJECT & SHALL BE USED ONLY FOR THE WATERLINE THRUST BLOCK CALC.

BURIED AIR/VAC ASSEMBLY - PLAN/SECTION

SCALE: NTS

THRUST BLOCK DETAIL

SCALE: NTS

REV	DATE	BY	DESCRIPTION
B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING
0 1/2 1
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.

McMILLEN
JACOBS
ASSOCIATES

KLAMATH
RIVER RENEWAL
CORPORATION

KLAMATH RIVER RENEWAL CORPORATION


CITY OF YREKA WATER LINE

CIVIL STANDARD DETAILS 3


DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. McMILLEN
PROJECT DATE 02/05/21

DRAWING

GC004



OVERALL SITE PLAN
SCALE: 1"= 100'



B	02/05/21	MDM	100% DESIGN SUBMITTAL	
A	12/18/20	MDM	50% DESIGN SUBMITTAL	
REV	DATE	BY	DESCRIPTION	

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING
0 1/2 1
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.





KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE

OVERALL SITE PLAN

DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. McMILLEN
PROJECT DATE 02/05/21

DRAWING

C001



REV	DATE	BY	DESCRIPTION
B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL

PRELIMINARY
NOT FOR CONSTRUCTION


WARNING
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.




KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
TEMPORARY WATERLINE PLAN AND PROFILE 1

DESIGNED	J. BURNS
DRAWN	R. WOOD
CHECKED	M. McMILLEN
PROJECT DATE	02/05/21

DRAWING
C100



- SHEET NOTES:**
1. SEE EC DWGS FOR EROSION AND SEDIMENT CONTROL MEASURES.
 2. ELEVATIONS SHOWN IN PIPELINE PROFILE ARE TO INVERT (FLOWLINE) OF PIPELINE UNLESS OTHERWISE NOTED.
 3. CONTRACTOR TO PROVIDE A MINIMUM OF 1.5FT OF COVER OVER TEMPORARY PIPELINE.



B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL
REV	DATE	BY	DESCRIPTION

PRELIMINARY
NOT FOR CONSTRUCTION


WARNING
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.



KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
TEMPORARY WATERLINE PLAN AND PROFILE 2


DESIGNED	J. BURNS
DRAWN	R. WOOD
CHECKED	M. MCMILLEN
PROJECT DATE	02/05/21

DRAWING
C101



SHEET NOTES:

1. SEE EC DWGS FOR EROSION AND SEDIMENT CONTROL MEASURES.
2. ELEVATIONS SHOWN IN PIPELINE PROFILE ARE TO INVERT (FLOWLINE) OF PIPELINE UNLESS OTHERWISE NOTED.
3. CONTRACTOR TO PROVIDE A MINIMUM OF 1.5FT OF COVER OVER TEMPORARY PIPELINE.



REV	DATE	BY	DESCRIPTION
B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL

PRELIMINARY
NOT FOR CONSTRUCTION


WARNING
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.




KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
TEMPORARY WATERLINE PLAN AND PROFILE 3

DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. McMILLEN
PROJECT DATE 02/05/21

DRAWING
C102



- SHEET NOTES:**
1. SEE EC DWGS FOR EROSION AND SEDIMENT CONTROL MEASURES.
 2. ELEVATIONS SHOWN IN PIPELINE PROFILE ARE TO INVERT (FLOWLINE) OF PIPELINE UNLESS OTHERWISE NOTED.
 3. CONTRACTOR TO PROVIDE A MINIMUM OF 1.5FT OF COVER OVER TEMPORARY PIPELINE.



REV	DATE	BY	DESCRIPTION
B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL

PRELIMINARY
NOT FOR CONSTRUCTION


WARNING
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.



KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
TEMPORARY WATERLINE PLAN AND PROFILE 4


DESIGNED	J. BURNS
DRAWN	R. WOOD
CHECKED	M. MCMILLEN
PROJECT DATE	02/05/21

DRAWING
C103



SHEET NOTES:

1. SEE EC DWGS FOR EROSION AND SEDIMENT CONTROL MEASURES.
2. ELEVATIONS SHOWN IN PIPELINE PROFILE ARE TO INVERT (FLOWLINE) OF PIPELINE UNLESS OTHERWISE NOTED.
3. CONTRACTOR TO PROVIDE A MINIMUM OF 1.5FT OF COVER OVER TEMPORARY PIPELINE.



REV	DATE	BY	DESCRIPTION
B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING

0 1/2 1

IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.

McMILLEN
JACOBS
ASSOCIATES

KLAMATH
RIVER RENEWAL
CORPORATION



KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
TEMPORARY WATERLINE PLAN AND PROFILE 5

DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. McMILLEN
PROJECT DATE 02/05/21

DRAWING

C104

- SHEET NOTES:
- SEE EC DWGS FOR EROSION AND SEDIMENT CONTROL MEASURES.
 - ELEVATIONS SHOWN IN PIPELINE PROFILE ARE TO INVERT (FLOWLINE) OF PIPELINE UNLESS OTHERWISE NOTED.
 - CONTRACTOR TO PROVIDE A MINIMUM OF 1.5FT OF COVER OVER TEMPORARY PIPELINE.



B	02/05/21	MDM	100% DESIGN SUBMITTAL	
A	12/18/20	MDM	50% DESIGN SUBMITTAL	
REV	DATE	BY	DESCRIPTION	

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING

0 1/2 1

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE.



KLAMATH RIVER RENEWAL CORPORATION

CITY OF YREKA WATER LINE

TEMPORARY WATERLINE PLAN AND PROFILE 6

DESIGNED J. BURNS


DRAWN R. WOOD

CHECKED M. McMILLEN



PROJECT DATE 02/05/21

DRAWING


C105



PLAN
SCALE: 1"= 20'



PROFILE
SCALE: HORIZ 1"= 20'
VERT 1"= 5'



SHEET NOTES:

1. SEE EC DWGS FOR EROSION AND SEDIMENT CONTROL MEASURES.
2. ELEVATIONS SHOWN IN PIPELINE PROFILE ARE TO INVERT (FLOWLINE) OF PIPELINE UNLESS OTHERWISE NOTED.
3. CONTRACTOR TO PROVIDE A MINIMUM OF 1.5FT OF COVER OVER TEMPORARY PIPELINE.

B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL
REV	DATE	BY	DESCRIPTION

PRELIMINARY
NOT FOR CONSTRUCTION


WARNING
0 1/2 1
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.



KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
TEMPORARY WATERLINE PLAN AND PROFILE 7


DESIGNED <u>J. BURNS</u>
DRAWN <u>R. WOOD</u>
CHECKED <u>M. MCMILLEN</u>
PROJECT DATE <u>02/05/21</u>

DRAWING
C106




PLAN

SCALE: 1"= 20'




1
C001



PROFILE

SCALE: HORIZ 1"= 20'

VERT 1"= 5'



SHEET NOTES:

1. SEE EC DWGS FOR EROSION AND SEDIMENT CONTROL MEASURES.
2. ELEVATIONS SHOWN IN PIPELINE PROFILE ARE TO INVERT (FLOWLINE) OF PIPELINE UNLESS OTHERWISE NOTED.
3. CONTRACTOR TO PROVIDE A MINIMUM OF 1.5FT OF COVER OVER TEMPORARY PIPELINE.

REV	DATE	BY	DESCRIPTION
B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.




KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
TEMPORARY WATERLINE PLAN AND PROFILE 8

DESIGNED	J. BURNS
DRAWN	R. WOOD
CHECKED	M. McMILLEN
PROJECT DATE	02/05/21


DRAWING
C107

- SHEET NOTES:
1. SEE ESC DWGS FOR EROSION AND SEDIMENT CONTROL MEASURES.
 2. PROVIDE A MINIMUM OF 3-FT COVER.
 3. ELEVATIONS SHOWN IN PIPELINE PROFILE ARE TO INVERT (FLOWLINE) OF PIPELINE UNLESS OTHERWISE NOTED.
 4. STRAIGHT SLOPES SHALL BE MAINTAINED BETWEEN PIPE INVERTS SHOWN OR SPECIFIED.
 5. THE EXISTING ROCKLINE IS BASED SOLELY UPON EXISTING BORINGS COMPLETED FOR THE PROJECT. SEE SPECIFICATIONS FOR DETAILED BORING INFORMATION. CONTRACTOR SHALL VERIFY THE LOCATION OF ROCK LINE PRIOR TO CONSTRUCTION OF THE NEW 24-INCH DIAMETER PERMANENT PIPELINE.



PLAN

SCALE: 1"= 20'



PROFILE

SCALE: HORIZ 1"= 20'
VERT 1"= 10'

REV	DATE	BY	DESCRIPTION
B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.




KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
PERMANENT WATERLINE PLAN AND PROFILE


DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. MCMILLEN
PROJECT DATE 02/05/21

DRAWING


C200




DETAIL
SCALE: 3/4" = 1'-0"



SECTION
SCALE: 3/4" = 1'-0"



DETAIL
SCALE: 1/2" = 1'-0"



DETAIL
SCALE: 1/2" = 1'-0"

- SHEET NOTES:**
- ALL EXISTING BOLTS SHALL BE REPLACED WITH NEW 3/4-INCH GALV BOLTS. PROVIDE 1/4"x4" MIN PLATE WASHERS AT LOCATIONS ADJACENT TO WOOD.

REV	DATE	BY	DESCRIPTION
B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.

**McMILLEN
JACOBS
ASSOCIATES**

**KLAMATH
RIVER RENEWAL
CORPORATION**


KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE

CIVIL SECTIONS AND DETAILS 1

DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. McMILLEN
PROJECT DATE 02/05/21



DRAWING
C201

Path: C:\Vault20\Klamath River Renewal Corp\City of Yreka Water Line\C201.dwg Plot date: Feb 08, 2021 02:13pm, CAD User: wood




DOWNSTREAM TEMPORARY PIPELINE CONNECTION

SCALE: 3/4"= 1'-0"



UPSTREAM TEMPORARY PIPELINE CONNECTION

SCALE: 3/4"= 1'-0"



REV	DATE	BY	DESCRIPTION
B	02/05/21	MDM	100% DESIGN SUBMITTAL
A	12/18/20	MDM	50% DESIGN SUBMITTAL

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.

McMILLEN
JACOBS
ASSOCIATES

KLAMATH
RIVER RENEWAL
CORPORATION

KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE

CIVIL SECTIONS AND DETAILS 2

DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. McMILLEN
PROJECT DATE 02/05/21

DRAWING

C202

Appendix D

City of Yreka Pipeline Modification Construction Water Quality Protection Plan

City of Yreka Waterline Modification Construction

Water Quality Monitoring and Protection Plan

1. Description of Site Conditions and the Proposed Activity

The Klamath River Restoration Project includes removal of four dams along the Klamath River. Within the Iron Gate Reservoir, near Daggett Road Bridge, the City of Yreka (City) has a 24-inch-diameter waterline minimally buried in the reservoir bed. According to the as-built record drawings prepared by Piemme, Neill, and Bryan and Clair A. Hill Associates in 1968, the existing pipeline was constructed by directly laying the pipe on the Iron Gate Reservoir bed within a riprap berm. A replacement pipe crossing is required before dam removal and reservoir drawdown to ensure an uninterrupted water supply for the City of Yreka. The general site layout is depicted in Appendix A and shows the major components of the proposed City waterline improvements. The new improvements include construction of a new 24-inch diameter steel pipe across the Klamath River. The modification will require two basic phases to construct. Phase 1 would consist of installation of a temporary pipe to provide water service during the reservoir drawdown period. The temporary pipe would extend from a connection point near the intersection of Copco Road and Daggett Road, across the existing Daggett Road Bridge, and then to a connection point on the south abutment of the reservoir. Phase 2 would consist of installing a permanent pipe buried across the river at the same location as the existing pipeline. The basic steps and design features of each work phase are presented in the following paragraphs.

1.1. Phase 1 – Install Temporary Pipe

The basic steps to construct the temporary pipeline include:

- 1) Construct a connection to the existing pipeline near the intersection of Copco Road and Daggett Road. Provide a butterfly valves for isolation to allow flow diversion from the existing pipeline to the temporary pipeline when the reservoir drawdown begins.*
- 2) Install a 30-inch diameter HDPE pipe or 24-inch diameter steel pipe from the existing pipe connection to the existing Daggett Bridge. This section will require a pipe crossing over the new Fall Creek culvert. The exposed sections of pipe will be protected to prevent damage from vandalism while it is in operation.*
- 3) The temporary pipe will be mounted on the guard rail on the existing Daggett Bridge. The pipe will be shielded to prevent damage during construction. Thrust restraint will be required at each end. Section 6.0 documents the structural supports and thrust restraint for the Daggett Bridge pipe crossing.*

- 4) *Construct a buried pipe from Daggett Bridge to the connection point with the existing pipeline on the south abutment. Similarly, the connection point will include butterfly valves to allow flow diversion to the temporary pipe and isolation of the existing pipe.*
- 5) *When the reservoir drawdown is initiate, flow will be diverted to the temporary pipe which will remain in service until the permanent pipe river crossing is completed.*

1.2. Phase 2 – Permanent Pipe River Crossing

The basic steps to construct the new 24-inch diameter steel pipeline include:

- 1) *With the reservoir drawdown, construct a cofferdam across the north half of the Klamath River.*
- 2) *Install the pipe crossing in the river and extend up to the connection point.*
- 3) *Relocate the cofferdam to the south side of the river. Construct the second section of the new 24-inch diameter pipe connecting to the north section.*
- 4) *When the cofferdams are in place, remove the existing pipe crossing.*
- 5) *The new pipe crossing will be concrete encased up to the 500-year Klamath River water surface elevation and buried in the rock layer (volcanic breccia) to prevent exposure from scouring action of the river.*
- 6) *Restore the riverbank planting and place riprap to protect the riverbed from scouring when the new pipe crossing is complete.*

2. Detailed descriptions, design drawings, and specific topographic locations of all control measures in relation to the proposed activity, which may include:

- Measures to divert runoff away from disturbed land surfaces;
- Measures to collect and filter runoff from disturbed land surfaces, including sediment ponds at the sites; and
- Measures to dissipate energy and prevent erosion;

Attached to the WQMPP includes erosion and sediment control drawings for the construction of the City of Yreka Waterline Modification Project. As shown on the construction drawings, silt fences, straw wattles, and cofferdams will be installed throughout the site as best management practices (BMPs) to prevent runoff from site construction activities and from rainfall events to leave the site laden with sediment. Drawings EC001 and EC002 include erosion control details

provided to the contractor for information only. The final locations and details of BMPs shall be shown on the contractor's prepared Stormwater Pollution Prevention Plan (SWPPP) Document.

Drawing EC100 includes a general erosion and sediment control drawing and are provided to aid the contractor in developing the erosion and sediment control plan according to the contractor's schedule and phasing of the Project. The cofferdams will be designed and constructed by the contractor to meet the site hydrology for the post reservoir drawdown conditions for the Klamath River and according to the contractor's schedule and phasing of the Project. The contractor will be required to detain and filter all runoff from site construction activities and from rainfall events. Stormwater will not be allowed to leave the site untreated (laden with suspended sediment). The contractor will establish a temporary vegetative cover on all disturbed areas as soon as practical after the last ground disturbing activities.

The contractor will prevent its operation from producing dust in amounts damaging to property, cultivated vegetation, or domestic animals, or causing a nuisance to persons living in or occupying buildings in the vicinity of the Site.

3. Revegetation of Disturbed Areas Using Native Plants and Locally-Sourced Plants and Seeds.


The contractor will reseed all disturbed areas with native grasses as a permanent BMP measure.

4. Monitoring, Maintenance, and Reporting Schedule


The contractor will be responsible for implementation and maintenance of erosion and sediment control measures (mulching of straw, sand diversion ditches, etc.) as dictated by field conditions to prevent erosion or the introduction of dirt, mud or debris to existing public or private roadways, onto adjacent properties, into the Klamath River or Fall Creek during any phase of construction operations. The contractor will be responsible to provide all necessary erosion control measures for the duration of the Project. Maintenance of both temporary and permanent erosion control measures shall be considered incidental. The contractor will be required to repair and reinstall temporary soil erosion control measures as necessary to ensure proper function for the duration of ground disturbing activities and through the warranty period.

List of Appendices


Appendix A City of Yreka Waterline Modification Project Erosion and Sediment Control Drawings




SILT FENCE DETAIL
SCALE: NTS



TEMPORARY ENTRANCE
SCALE: NTS



TURBIDITY CURTAIN
SCALE: NTS



WATTLE
SCALE: NTS

REV	DATE	BY	DESCRIPTION
A	12/18/20	MDM	50% DESIGN SUBMITTAL

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING
0 1/2 1
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.


McMILLEN
JACOBS
ASSOCIATES

KLAMATH
RIVER RENEWAL
CORPORATION

KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
EROSION AND SEDIMENT CONTROL STANDARD
DETAILS 1

DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. McMILLEN
PROJECT DATE 12/18/20

DRAWING
EC001



- NOTES:
- 1. SEE SPECIFICATIONS FOR FENCE MATERIAL, COATINGS, AND INSTALLATION REQUIREMENTS.
 - 2. EXTENSION ARM MAY BE TURNED IN AT OPTION OF OWNER.

CONSTRUCTION FENCING DETAIL
SCALE: NTS



A	12/18/20	MDM	50% DESIGN SUBMITTAL
REV	DATE	BY	DESCRIPTION

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING

IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.




KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
EROSION AND SEDIMENT CONTROL STANDARD DETAILS 2

DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. MCMILLEN
PROJECT DATE 12/18/20

DRAWING

EC002



EROSION AND SEDIMENT CONTROL PLAN

SCALE: 1"= 100'



SHEET NOTES:

1. THE EXPOSED AND DISTURBED AREAS SHALL BE REGRADED TO MATCH EXISTING AND RESEED WITH NATIVE GRASS PER OWNER REQUIREMENTS
2. ALL FILL MATERIALS AND COMPACTION REQUIREMENTS ARE DEFINED IN SPECIFICATION SECTION 31 00 00.
3. MATCH EXISTING GRADE AND PROVIDE SMOOTH TRANSITION BETWEEN ALL NEW SURFACING AND EXISTING GRADE.
4. COFFERDAM SHALL BE DESIGNED AND CONSTRUCTED BY CONTRACTOR, REFER TO SPECIFICATION 01 12 00 FOR DETAILS OF THE SITE HYDROLOGY.

EROSION AND SEDIMENT CONTROL NOTES:

GENERAL NOTES:

1. THE CONTRACTOR SHALL SUBMIT AN EROSION AND SEDIMENT CONTROL PLAN FOR WORK DURING CONSTRUCTION THAT MEETS ALL FEDERAL, STATE, AND LOCAL REQUIREMENTS.
 - A. THE CONTRACTOR IS RESPONSIBLE FOR IMPLEMENTATION AND MAINTENANCE OF EROSION AND SEDIMENT CONTROL MEASURES (MULCHING OF STRAW, SAND DIVERSION DITCHES, ETC.) DICTATED BY FIELD CONDITIONS TO PREVENT EROSION OR THE INTRODUCTION OF DIRT, MUD, OR DEBRIS TO EXIST PUBLIC OR PRIVATE ROADWAY, ONTO ADJACENT PROPERTIES, INTO FALL CREEK, OR INTO KLAMATH RIVER DURING ANY PHASE OF CONSTRUCTION OPERATIONS. SPECIAL ATTENTION SHALL BE GIVEN TO ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES NOTED BELOW.
 - B. THE GENERAL EROSION AND SEDIMENT CONTROL PLAN ON THE EC DRAWINGS ARE PROVIDED TO AID THE CONTRACTOR IN DEVELOPING THE EROSION AND SEDIMENT CONTROL PLAN ACCORDING TO CONTRACTOR SCHEDULE AND PHASING OF THE PROJECT.
 - C. EROSION CONTROL DETAILS ARE FOR INFORMATION ONLY TO AID THE CONTRACTOR. THE FINAL LOCATIONS AND DETAIL SHALL BE SHOWN ON THE CONTRACTOR'S PREPARED STORMWATER POLLUTION PREVENTION PLAN (SWPPP) DOCUMENT.
 - D. CONTRACTOR IS RESPONSIBLE TO PROVIDE ALL NECESSARY EROSION CONTROL MEASURES FOR THE DURATION OF THE PROJECT. MAINTENANCE OF BOTH TEMPORARY AND PERMANENT EROSION CONTROL MEASURES SHALL BE CONSIDERED INCIDENTAL.
 - E. ALL BMP REQUIRED MATERIALS SHALL MEET OR EXCEED STATE OF CALIFORNIA STORMWATER QUALITY ASSOCIATION (CASQA) REQUIREMENTS.
 - F. CONTRACTOR SHALL DEVELOP A SPILL PREVENTION, CONTAINMENT, AND RESPONSE PLAN THAT WILL BE ATTACHED TO THE SWPPP.

GRADING AND FINAL STABILIZATION:

1. CLEARING, GRUBBING, AND GROUND DISTURBING ACTIVITIES SHALL BE CONFINED TO WITHIN CLEARING LIMITS AND SHALL MEET THE REQUIREMENTS OF SPECIFICATION 31 11 00. NO GRADING OR CONSTRUCTION ACTIVITIES SHALL OCCUR OUTSIDE OF THE PROPOSED IMPROVEMENTS SHOWN ON THE CONSTRUCTION PLANS FOR THIS PROJECT. PRESERVE EXIST VEGETATION BEYOND DISTURBED AREA - UTILIZE AS NATURAL BUFFER STRIPS.
2. DURING CONSTRUCTION, PROVIDE POSITIVE DRAINAGE AWAY FROM FACILITIES.
3. CONTRACTOR SHALL REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL FACILITIES, FENCING, AND STAGING AREA MATERIALS WHEN CONSTRUCTION IS COMPLETE. NO CONSTRUCTION DEBRIS, DEMOLITION MATERIALS, OR EXCESS EQUIPMENT SHALL BE LEFT ON SITE.
4. CONTRACTOR SHALL REGRADE DISTURBED SLOPED TO NEAR EXIST CONDITION AS APPROVED BY THE OWNER.
5. ESTABLISH A TEMPORARY VEGETATIVE COVER ON ALL DISTURBED AREAS AS SOON AS PRACTICAL AFTER THE LAST GROUND DISTURBING ACTIVITIES IN THE AREA. CONTRACTOR SHALL RESEED ALL DISTURBED AREAS WITH NATIVE VEGETATION, PER SPECIFICATION 31 35 30, AND IN ACCORDANCE WITH SHEET EC100.

BMP MEASURES:

1. ALL RUNOFF FROM SITE CONSTRUCTION ACTIVITIES AND FROM RAINFALL EVENTS SHALL BE DETAINED ON SITE AND FILTERED PRIOR TO DISCHARGE. STORMWATER RUNOFF SHALL NOT BE ALLOWED TO LEAVE THE SITE UNTREATED (LADEN W/ SUSPENDED SEDIMENT). IF THIS OCCURS, THE CONTRACTOR WILL BE HELD SOLELY RESPONSIBLE FOR ANY PERMIT VIOLATIONS AND FINES.
2. CONTRACTOR SHALL TAKE APPROPRIATE MEASURES TO PREVENT ACCUMULATION OF CONSTRUCTION WASTE AND LITTER ON-SITE.
3. CONTRACTOR SHALL INSTALL SILT FENCE AND/OR STRAW WATTLES AS INDICATED AND IN ANY ADDITIONAL LOCATIONS WHERE MATERIAL COULD LEAVE THE CONSTRUCTION SITE, AT CONTRACTOR'S EXPENSE.
4. THE SILT FENCE AND/OR STRAW WATTLES SHALL BE INSTALLED PRIOR TO ANY CONSTRUCTION ACTIVITIES.
5. CONTRACTOR SHALL HAVE AVAILABLE AT ALL TIMES ADEQUATE SPRINKLER EQUIPMENT TO FACILITATE DUST ABATEMENT AND CONTROL. CONTRACTOR SHALL PROVIDE ALL WATER NECESSARY FOR SPRINKLER OPERATIONS.
6. STOCKPILED EXCAVATION MATERIALS SHALL BE PROTECTED FROM WATER AND WIND EROSION BY COVERING AS APPROPRIATE. WHEN EXPOSED FOR MORE THAN 14 DAYS, COVER STOCKPILES WITH IMPERMEABLE TARPES TO PROTECT DISTURBED SOILS AND SLOPES.
7. ALL TOP SOIL SHALL BE STRIPPED AND PLACED IN SEPARATE STOCKPILE. AFTER BANK RESTORATION TO EXIST GRADE, TOP SOIL SHALL BE PLACED AND RESEED.
8. CONTRACTOR SHALL HAVE ON-SITE AT ALL TIMES SPILL PREVENTION AND CONTROL MEASURES.
9. ENSURE ALL EQUIPMENT IS CLEAN AND FREE OF OIL/FUEL LEAKS, DIRT, PLANTS, AND ANIMALS OR FRAGMENTS OF PLANTS, AQUATIC INVASIVE SPECIES, AND OTHER VEGETATIVE MATTER. EQUIPMENT FOR WORK INSIDE OF THE ORDINARY HIGH WATER MARK SHALL UTILIZE FOOD-GRADE HYDRAULIC FLUID.

A	12/18/20	MDM	50% DESIGN SUBMITTAL	
REV	DATE	BY	DESCRIPTION	

PRELIMINARY
NOT FOR CONSTRUCTION

WARNING
0 1/2 1
IF THIS BAR DOES NOT
MEASURE 1" THEN
DRAWING IS NOT TO SCALE.



KLAMATH RIVER RENEWAL CORPORATION
CITY OF YREKA WATER LINE
EROSION AND SEDIMENT CONTROL PLAN

DESIGNED J. BURNS
DRAWN R. WOOD
CHECKED M. MCMILLEN
PROJECT DATE 12/18/20

DRAWING
EC100

Appendix C

Oregon Groundwater Well Management Plan



**Lower Klamath Project
FERC Project No. 14803**

Oregon Groundwater Well Management Plan

**Klamath River Renewal Corporation
2001 Addison Street, Suite 317
Berkeley, CA 94704**

**Prepared by:
Camas LLC
680 G Street, Suite C
Jacksonville, OR 97530**

December 2021

This page intentionally left blank.

Table of Contents

1.0	Introduction.....	1
1.1	Purpose of the Groundwater Well Management Plan	1
2.0	Groundwater Well Management.....	1
2.1	Identification of Groundwater Wells.....	1
2.2	Local Impact Mitigation Fund	1
2.3	Klamath County Outreach	2
2.4	Pre-Drawdown Monitoring	2
3.0	Annual Compliance Report.....	3
4.0	References	3

1.0 Introduction

This Oregon Groundwater Well Management Plan is a subplan of the Water Supply Management Plan that will be implemented as part of the Proposed Action for the Lower Klamath Project.

1.1 Purpose of the Groundwater Well Management Plan

The purpose of the Oregon Groundwater Well Management Plan is to state measures the Renewal Corporation will implement to protect groundwater supplies potentially affected by the Proposed Action in Oregon.

2.0 Groundwater Well Management

2.1 Identification of Groundwater Wells

The Renewal Corporation conducted a preliminary analysis to determine which groundwater wells within the vicinity of the J.C. Boyle reservoir would potentially be affected by the Proposed Action. According to the Oregon Water Resources Department (OWRD) online groundwater well database (Find a Well Report) (OWRD 2021), there are approximately 54 groundwater wells located within 2.5 miles of the J.C. Boyle Reservoir (CDM Smith, 2020). Of the 54 wells, five groundwater well reports included a specific location and are reported as active. Of the five wells, one active groundwater well is located within 1,000 feet of the J.C. Boyle Reservoir. This groundwater well is located at Sportsman's Park. Sportsman's Park is owned by Klamath County and under a lease agreement, by the Klamath Sportsman's Park Association. The Sportsman's Park groundwater well supplies water to the Bureau of Land Management (BLM) Topsy Campground via a tank. Review of existing well log data (e.g., screen elevation [248-294 feet below the ground surface]), the shallowness of the J.C. Boyle Reservoir (approximately 20-30 feet deep), and the site topography and location of the well upgradient from the J.C. Boyle Reservoir, the groundwater well is not likely hydraulically connected to the Reservoir, therefore no impact to this well is anticipated.

2.2 Local Impact Mitigation Fund

Based on the analysis, the Renewal Corporation concludes the production of groundwater wells surrounding the J.C. Boyle Reservoir will likely not be affected.

Nonetheless, to address potential impacts caused by reservoir drawdown, the Renewal Corporation will implement the measures stated in this plan, as required by the License Surrender Order. In order to address potential damage claims involving private properties, the Renewal Corporation will establish a Local Impact Mitigation Fund (LIMF), to be administered outside of the License Surrender Order. For property owners electing to opt into the fund, the LIMF will provide financial resources to such property owners to mitigate impacts to groundwater wells that are determined to be caused by the Proposed Action. The fund will be

backstopped by insurance. The Renewal Corporation will undertake these measures even though affected landowners, under the Oregon Water Code and other applicable state law, do not have a right to the enhanced condition of an aquifer (or enhanced well production) associated with a licensee's storage of a reservoir.

The LIMF will include procedures and standards for determining the nature and scope of any impacts, as well as stipulated payments to property owners. Developing this methodology will involve proactive participation and input from key stakeholders. The draft methodology will be made available for public comment through town halls and other meetings.

Under the LIMF, the Renewal Corporation will not accept responsibility for pre-existing conditions, such as arsenic contamination, or for any other condition not caused by the Proposed Action. The fund administrator will be supported by a technical team but will ultimately have the discretion to determine the legitimacy of covered claims. Any affected property owners who elect not to participate in the LIMF may, instead, pursue any other remedies available to such property owners under applicable state law.

2.3 Klamath County Outreach

Prior to drawdown, as part of the Proposed Action, the Renewal Corporation will request participation to conduct pre-drawdown and drawdown groundwater monitoring at Sportsman's Park. If Klamath County allows the Renewal Corporation to monitor their well, the well will be evaluated in accordance with Section 2.4. If Klamath County participates in the Renewal Corporation's pre-drawdown groundwater monitoring program, Klamath County will be eligible to participate in the LIMF if post drawdown monitoring indicates that a groundwater well has been adversely impacted by the Proposed Action.

2.4 Pre-Drawdown Monitoring

The Renewal Corporation will conduct the following pre-drawdown and drawdown monitoring activities following coordination with Klamath County:

Pre-Drawdown

- At least two months prior to commencing drawdown activities, the Renewal Corporation will monitor groundwater levels at the Sportsman's Park well.
- Monthly water quality samples will be collected at the Sportsman's Park well for the following parameters: pH, conductivity, major anions and cations (these will be specified following conversations with Klamath County).

Drawdown

- Groundwater level monitoring will occur monthly and up to two years following completion of drawdown at the Sportsman's Park well.
- Monthly water quality samples will be collected at the Sportsman's Park well up to two years following completion of drawdown for the following parameters: pH, conductivity, major anions and cations (these will be specified following conversations with Klamath County).

3.0 Annual Compliance Report

By April 1 of each year, the Renewal Corporation will submit to the Oregon Department of Environmental Quality an Annual Compliance Report describing field activities, outreach efforts, and monitoring results under this plan for the preceding year in which activities are performed.

4.0 References

CDM Smith. 2020. Technical Memorandum - Status of Groundwater Monitoring and Potential Effects to Supply Wells Following Reservoir Drawdown – Klamath Dam Removal.

Oregon Water Resources Department (OWRD) – Find A Well Report.

https://apps.wrd.state.or.us/apps/gw/well_log/Default.aspx Accessed online January 1, 2021.

Appendix D

Fire Management Plan



Lower Klamath Project FERC No. 14803

Fire Management Plan

December 2021



Prepared for:

Klamath River Renewal Corporation

Prepared by:

Renewal Corporation Technical Representative:

AECOM Technical Services
300 Lakeside Drive, Suite 400
Oakland, California 94612
Seth Gentzler
Shannon Leonard

River Design Group
311 SW Jefferson Avenue
Corvallis, Oregon 97333
Jack Zunka
Scott Wright

CEA Consulting
235 Montgomery Street, Suite 950
San Francisco, California 94104
Kirk Marckwald

Table of Contents

Executive Summary	8
1. Introduction	10
2. Background and Overview of Fire in the Region.....	13
2.1 Environmental Conditions and Fire History	13
2.2 Government and Agency Fire Mitigation Planning	14
2.3 Fire Risks Associated with Power Generation and Transmission	15
3. Fire Suppression Agencies, Resources, and Considerations	17
3.1 Fire Support and Services.....	17
3.2 Existing Management Resources and Strategies	20
3.2.1 Fire Detection	21
3.2.2 Prevention and Preparedness.....	24
3.2.3 Water Sources and Access.....	25
4. Regulations and Requirements.....	27
4.1 Federal	27
4.2 Oregon Department of Forestry Klamath-Lake District	28
4.3 CalFire Siskiyou Unit.....	31
5. Near-term Measures: Construction-Related Activities.....	35
5.1 Roles and Responsibilities	35
5.1.1 During Dam Decommissioning and Removal - Kiewit	35
5.1.2 During Restoration and Monitoring - RES	36
5.1.3 Safety Officer.....	38
5.2 Agency Contacts	40
5.3 Fire Prevention and Suppression Measures and Equipment.....	40
5.3.1 Regulations and Requirements	40
5.3.2 Standards and Best Practices.....	41
5.3.3 Fire Management Preparation Checklist.....	44
6. Long-Term Fire Management Measures	45
6.1 Term	45
6.2 Objectives and Overview.....	46
6.3 Conditions after Dam Removal	46
6.4 Post-Removal Management Measures.....	47

6.4.1	Monitored Detection System (MDS)	48
6.4.2	Chipper	50
6.4.3	Copco Lake Hydrant System	50
6.4.4	Dry Hydrants	51
6.4.5	Boat Launches	52
6.4.6	Aerial River Access Points (ARAPs)	52
6.4.7	Dip Tanks	56
6.5	Evaluation of Post-Removal Fire Risk	57
6.5.1	Burn Probability and Risk of Ignition	58
6.5.2	Firefighting Capabilities	60
7.	Renewal Corporation Commitments.....	65
8.	Agency Consultation	66
9.	References	69

List of Tables

Table 3-1.	Fire protection agencies in the ASE area, updated table from BOR & CDFG (2012).....	17
Table 3-2.	Fire services in the analysis area.	20
Table 3-3.	Comparison of common firefighting helicopters.	26
Table 4-1.	2019 ODF fire season minimum requirements (ODF, 2019).	28
Table 4-2.	Fire precautionary measures required by California Public Resources Code (PRC) and applicable during any times of the year when burning permits are required unless otherwise stated.....	31
Table 5-1.	Kiewit primary leads for fire protection and control.	36
Table 5-2.	RES leads for fire protection and control.	37
Table 5-3.	Fire management preparation checklist for the Contractors.	44
Table 6-1.	Miles of transmission and distribution lines removed by the Proposed Action (Renewal Corporation Technical Representatives, 2018, <i>updated 2021</i>).....	47
Table 6-2.	Post-removal ground access points as shown in Figure 9.	52
Table 6-3.	Change in modeled burn probability within ASE area from pre-restoration to post-restoration fuels.	58
Table 6-4.	Percentage of ASE area (568.9 mi ²) covered from Reax viewshed analysis	61
Table 6-5.	Results for mean burn probability from Reax's wildfire spread modeling	62
Table 8-1.	Agency personnel consulted during development of the Fire Management Plan.	66

List of Figures

Figure 1.	Aerial Suppression Extent (ASE) in the Klamath Basin.....	12
Figure 2.	Map of fire hazard in the Klamath River basin generated using MODIS by the USFS. Figure from BOR & CDFG (2012).....	14

Figure 3. Fire threat map of the Klamath Basin showing California Public Utilities Commission fire threat tier data.	16
Figure 4. Land ownership around the analysis area. Figure from BOR & CDFG (2012).....	18
Figure 5. Map of hospitals, fire stations, and major fire routes near the Klamath Dams. From BOR & CDFG (2012). Note, Klamath Falls Interagency Fire Center is now an air tanker base.....	19
Figure 6. Overview map of the existing fire management resources in the Klamath River Basin near the Project.....	22
Figure 7. Cell coverage in the ASE area where white indicates “no coverage.” Coverage maps generated from their respective carrier websites on May 12, 2020.	23
Figure 8. Viewshed analysis at 500 Ft above ground surface for existing detection resources with green and yellow indicating visibility by one and two observers, respectively. From Reax report (Appendix A).....	24
Figure 9. Proposed post-removal long-term fire management measures.	48
Figure 10. Viewshed analysis at 500 Ft above ground surface for contemplated MDS camera locations with green, yellow, and orange indicating visibility by one, two, and three observers, respectively. From Reax report (Appendix A).	49
Figure 11. Conceptual cross-section illustrating the performance criteria/minimum requirements for aerial river access points.....	53
Figure 12. Potential post-removal resources in footprint of Iron Gate Reservoir.....	54
Figure 13. Potential post-removal resources in footprint of Copco Lake.....	55
Figure 14. Potential post-removal resources in footprint of J.C. Boyle Reservoir.....	56
Figure 15. Difference between modeled pre- and post-restoration burn probabilities. Red/orange and blue/green indicate increases and decreases in burn probability, respectively. From Reax report (Appendix A).	59
Figure 16. Comparison of pre- (white) and post-Proposed Action viewsheds at 500 Ft above ground level with additional coverage (pink) by one observer (left) and multiple observers (right). From Reax report (Appendix A).....	60
Figure 17. Modeled mean burn probability in ASE area vs. time of initial attack after fire ignition. From Reax report (Appendix A).....	63

List of Appendices

Appendix A - Reax Engineering, Inc., Qualitative Wildfire Risk Analysis of the Klamath River Renewal Project

Appendix B - Spatial Informatics Group, Review of Reax Analysis

Appendix C - Agency Approval Letters

Acronyms and Abbreviations

ARAP	Aerial River Access Point
ASE	Aerial Suppression Extent
BLM	Bureau of Land Management
BOR	United States Bureau of Reclamation

CalFire	California Department of Forestry and Fire Protection
CCR	California Code of Regulations
CDFG	California Department of Fish and Game
CFR	Code of Federal Regulations
CFSU	CalFire Siskiyou Unit
CPUC	California Public Utilities Commission
CSBFFP	California State Board of Forestry and Fire Protection
DDP	Definite Decommissioning Plan
EO	Executive Order
EVS	EnviroVision Solutions
FDL	Fire Danger Level
FERC	Federal Energy Regulatory Commission
FMP	Fire Management Plan
FSCSC	Fire Safe Council of Siskiyou County
IFPL	Industrial Fire Precautionary Level
LIFC	Lakeview Interagency Fire Center
LSO	License Surrender Order
LTC	Liability Transfer Corporation
MDS	Monitored Detection System
OAR	Oregon Administrative Rules
OAS	U.S. Office of Aviation Services
ODF	Oregon Department of Forestry
ODF KLD	Oregon Department of Forestry Klamath Lake District
ODF SWO	Oregon Department of Forestry Southwest Oregon District
ORS	Oregon Revised Statutes
OSHA	Occupational Safety and Health Administration
NPS	National Park Service
PAL	Predicted Activity Level
PDM	Power Driven Machinery
PRC	California Public Resources Code
Renewal Corporation	Klamath River Renewal Corporation
RES	Resource Environmental Solutions, LLC
SB	Senate Bill
SCOFMP	South Central Oregon Fire Management Partnership
SRA	CalFire State Responsibility Area
USC	United States Code
USFS	U.S. Forest Service
WFT	Wildland Fire Technologies, Inc
WMP	Wildfire Mitigation Plan

WUI

Wildland Urban Interface

Definitions

Analysis area	Area defined by an approximately 50-mile buffer surrounding the four dams of the Lower Klamath Project
ASE area	Area defined by the approximate boundary within which the reservoirs are used for aerial fire suppression
Project	Lower Klamath Project (FERC No. 14803)
Proposed Action	Dam removal and habitat restoration as described in the Definite Decommissioning Plan
Proposed Action area	Lands on which construction activities associated with the Proposed Action may occur. Includes the reservoir footprints and PacifiCorp Parcel B lands

EXECUTIVE SUMMARY

The Klamath River Renewal Corporation (Renewal Corporation) will implement this Fire Management Plan (FMP) to address fire risks associated with the physical removal of four dams (Iron Gate, Copco No. 1, and Copco No. 2 in California, and J.C. Boyle in Oregon) of the Lower Klamath Project (FERC Project No. 14803). PacifiCorp (as the licensee and owner of the Project), the states of California and Oregon (the States), tribes, and other stakeholders entered into the Klamath Hydropower Settlement Agreement (KSHA, 2016). The Renewal Corporation is implementing this settlement, which establishes a process leading to dam removal. The Renewal Corporation has applied to the Federal Energy Regulatory Commission (FERC) to surrender the license for the Project. The FMP is part of the Definite Decommissioning Plan. When FERC issues a License Surrender Order, the Renewal Corporation will be legally responsible to implement all commitments in that plan, including the FMP. A Memorandum of Agreement, signed by the Renewal Corporation, the States, PacifiCorp, and the Yurok and Karuk tribes in November 2020, adds the States as co-licensees for the purpose of License Surrender.

The Renewal Corporation developed the FMP in consultation with CalFire Siskiyou Unit, Oregon Department of Forestry (ODF) Klamath Lake and Southwest Oregon Districts, and local fire departments. Letters of support for a prior (2020) version of the FMP from CalFire and ODF are in Appendix C. This December 2021 version of the Plan is substantively the same as the prior version that CalFire and ODF reviewed and supported. Based on conversations with CalFire, there was a change in approach at one California site, and that change is reflected in the December 2021 version of the Plan.

From a near-term perspective, the FMP requires the Renewal Corporation to use best management measures and comply with regulations to prevent and control fire risk associated with deconstruction activities. The Renewal Corporation has engaged Kiewit for this work. Across decades of experience in western states, Kiewit has never caused a damaging fire at a complex construction project like this. The Renewal Corporation's contractor for habitat restoration, Resource Environmental Solutions, will also follow best management practices and regulations.

From a long-term perspective, dam removal will result in the loss of three Project reservoirs, which have been used as water supply for firefighting. It will result in regrowth of vegetation in the reservoir footprints. Under the FMP, the Renewal Corporation will implement measures to assure that these changes do not result in an increase in wildfire risk in the area. In cooperation with fire agencies, the Renewal Corporation will install Monitored Detection System cameras in a 570 square-mile area around the Project. It will construct ramps for fire trucks to access the river as well as install dry hydrants for ground crews. It will purchase dip tanks and maintain aerial river access sites for helicopter crews. It will purchase equipment to assist the local communities with defensible space and reducing risk of structure fires. These measures will assure that dam removal does not increase wildfire risk in the area on a long-term basis. Indeed, the expansion of the camera monitoring system will increase the area where early detection and triangulation are currently possible by more than 40%.

The Renewal Corporation engaged REAX Engineering to evaluate the effectiveness of the FMP using advanced wildfire risk computer modeling that public utility commissions use with respect to utility operations. REAX consults to utilities and public utility commissions on management of wildfire risk. Its

report is attached to the FMP as Appendix A, along with a peer review by an independent expert in wildfire risk modeling (Spatial Informatics Group) as Appendix B. The report confirms that dam removal will not increase wildfire risk in the area.

1. INTRODUCTION

The Klamath River Renewal Corporation (Renewal Corporation) will implement this Fire Management Plan (FMP) to address fire prevention and suppression that may be associated with the physical removal of four dam developments (Iron Gate, Copco No. 1, Copco No. 2, and J.C. Boyle) of the Lower Klamath Project (FERC Project No. 14803), hereafter the Project. The FMP was included as an Appendix of the Definite Decommissioning Plan (DDP; Renewal Corporation, 2020), which was submitted to the Federal Energy Regulatory Commission (FERC) in November 2020 by the Renewal Corporation. The Proposed Action is defined as dam removal and habitat restoration as described in the DDP. The FMP includes the Renewal Corporation commitments for fire management that will be effective when FERC issues the License Surrender Order (LSO), which will approve the DDP and require implementation of the individual management plans, including this FMP.

The FMP includes fire agency regulations and fire prevention and suppression management strategies to combat short-term increases to risk of fire specifically associated with dam removal construction activities. The FMP addresses, in addition, long-term fire management in the Klamath River Basin and incorporates strategies to counter the loss of the three Klamath River reservoirs, which have served as fire suppression resources in the past, and also to provide in the long-term new local and regional fire suppression resources that do not currently exist in the Basin. The FMP was developed in accordance with standards and goals of and in consultation with local, state, and federal fire suppression agencies. The FMP, fire history and ignition risk in the Basin, and the effectiveness of the measures and strategies proposed in the FMP were reviewed in the “Quantitative Wildfire Risk Analysis of the Klamath River Renewal Project,” which was completed by Reax Engineering Inc. (Reax) and included herein as Appendix A. The Reax analysis was peer-reviewed by Spatial Informatics Group, and the review is included herein as Appendix B. Letters of support for a prior (2020) version of the FMP from CalFire and ODF are in Appendix C. This December 2021 version of the Plan is substantively the same as the prior version that CalFire and ODF reviewed and supported. Based on conversations with CalFire, there was a change in approach at one California site, and that change is reflected in the December 2021 version of the Plan.

The objectives of the FMP are 1) to prevent or control any fire caused by construction or habitat restoration activities under the DDP, and 2) to avoid a net diminution in firefighting resources or an increase in the fire ignition risk as a result of the loss of the Project reservoirs. The Renewal Corporation will implement (and oversee through License Surrender) effective and feasible measures to enhance both short- and long-term fire prevention, detection, and suppression in the Basin. The Renewal Corporation will cooperate with local and regional fire agencies through agreements, as appropriate, to implement measures that counter the loss of any current fire suppression resources. The FMP will terminate when FERC issues notice that License Surrender is effective.

The sections below provide: 1) background information relating to fire, 2) relevant agencies and their jurisdictions and regulatory requirements, 3) plan for complying with regulations and best management practices to reduce fire risk in the short-term during Proposed Action construction, and 4) descriptions of the FMP components and analysis demonstrating that the execution of the removal of the Klamath Dams does not increase fire risk in the long-term.

For the FMP and the Reax report (Appendix A), fire-related analysis is conducted and discussed over several areal extents. General basin characteristics, environmental conditions, fire history, and fire agency resources are analyzed over an “analysis area” defined by an approximately 50-mile buffer surrounding the four dams. This size of the area was selected to characterize regional conditions without analyzing an unnecessarily large area in physiographically and climatically diverse states of Oregon and California. Fire suppression techniques and effectiveness are discussed within a 570 mi² area known as the Aerial Suppression Extent (ASE), which is the approximate boundary within which the reservoirs are used for aerial fire suppression (Figure 1). The boundary of this area was delineated by California Department of Forestry and Fire Protection (CalFire) during an in-person meeting (CalFire Siskiyou Unit, *pers. comm.*, 2019.03.04). The ASE area is bounded by I-5 to the west, the Siskiyou Crest to the North, and high topography to the east and south. This area is most relevant for investigating the broader impacts of the Proposed Action. The ASE area is significantly smaller than the analysis area. A smaller area, the “Proposed Action area,” corresponds to lands on which construction activities associated with the Proposed Action may occur. This area, which includes the reservoir footprints and PacifiCorp Parcel B lands, is significantly smaller than the ASE area. We analyze some local-scale effects and construction-related activities over this area.




Figure 1. Aerial Suppression Extent (ASE) in the Klamath Basin.

2. BACKGROUND AND OVERVIEW OF FIRE IN THE REGION

The Proposed Action area is located in Northern California and Southern Oregon. Iron Gate, Copco No. 1, and Copco No. 2 dams are located in Siskiyou County, California, and J.C. Boyle Dam is located in Klamath County, Oregon. The Klamath Basin in the analysis area also includes the southern portion of Jackson County, Oregon.

2.1 Environmental Conditions and Fire History

The analysis area surrounding the four Klamath River dams is at risk of wildfires. CalFire categorizes the fire threat in the analysis area as high to very high (CalFire, 2007). Fire hazard mapping using the Moderate-resolution Imaging Spectroradiometers (MODIS; USFS, 2010) shows the moderate to very high fire threat in the analysis area (Figure 2). Klamath County has identified Wildland Urban Interfaces (WUI), scored the fire hazards for each WUI community, and categorized the fire damage hazard scores as low, moderate, and high (WFT, 2016). J.C. Boyle Dam is located in the Keno WUI Community, which has the highest fire hazard score in the county and a “high” ranking (WFT, 2016).

The physiographic, climatic, and ecological characteristics of the analysis area create a high fire hazard. Much of the terrain is steep, rugged, and remote, resulting in sparse access to fires and long response times. The area supports a range of fuel types, including timber, timber with grass understory, grass, brush, oak woodland, desert sage, western juniper, and Ponderosa pine (CalFire, 2016). A spatial analysis of fuel types in the analysis area is presented in Appendix A. The Proposed Action activities are primarily in the Shasta Valley planning area, which is 60% grass and shrub vegetation, a light and flashy fuel type (Siskiyou County, 2019). Grass and shrub fuel types burn quickly, which, along with high winds and steep terrain, encourages rapid spread of wildfires (Estes et al., 2017), and rates up to 1.25 miles per hour (mph) have been measured in the area (Siskiyou County, 2019; Stephens et al., 2008). Fire risk is elevated in Northern California from June 1 to October 1, based on ignition data (PacifiCorp, 2019); summer temperatures often exceed 100° F and are accompanied by low precipitation and drought conditions (CalFire, 2016). In the summer, mountain ranges and local weather patterns support electrical storms often accompanied by strong winds and little to no precipitation (CalFire, 2016).

A detailed analysis of fire history in the analysis area conducted with aggregated available datasets of past events is presented in Appendix A, wherein fire occurrences are parsed into human-caused and lightning-caused categories. Human-caused fires tend to cluster along roads (e.g., I-5) and around population centers (e.g., Keno, Klamath Falls, campgrounds), and these events tend to be smaller and more successfully suppressed during initial attack. Lightning is the leading cause of wildfire in the analysis area. Lightning strikes tend to be more randomly distributed than human-caused ignitions but do favor higher elevations. The density of lightning-caused ignitions is very low around Iron Gate Reservoir and low-to-moderate around Copco Lake (Appendix A). In Northern California, lightning was the cause of ignition in 54% of the 1200 records CalFire documented from 2007 to 2017. In Klamath County, Oregon, 46% of the fires (and 79% of the burned acreage) on Oregon Department of Forestry (ODF)-protected lands from 2006 to 2015 were caused by lightning, and 20% were caused by debris burning (WFT, 2016). On federal lands in Klamath County from 2006 to 2015, 81% of the fires were caused by lightning, which accounted for 89% of the

federal acreage burned. Most larger fires are categorized as wind-driven fires (CalFire, 2016). The combination of high drought index (i.e., dryness) values and high wind velocities promote wildfire ignition and growth (PacifiCorp, 2019).




Figure 2. Map of fire hazard in the Klamath River basin generated using MODIS by the USFS. Figure from BOR & CDFG (2012).

2.2 Government and Agency Fire Mitigation Planning

Prevention and mitigation of large, destructive fires has become a recent top priority for California, and electrical utilities are an important consideration in the management of fires. 15 of the 20 most destructive wildfires in California history have occurred since 2000, and 10 of these have occurred since 2015 (Strike Force, 2019). In the past 20 years, a number of these destructive fires in California have been ignited by elements of overhead utilities systems. In response to these events, the California Public Utilities Commission (CPUC) initiated a multi-phase statewide effort to reduce the risk of wildfire caused by overhead utility systems. This effort included the development of strict regulations for such systems and the creation of fire threat maps (e.g., Figure 3), which incorporate environmental variables, human and infrastructure risk, and the type and density of power generating and transmitting infrastructure. CPUC designates three threat levels: Tier 1 no threat, Tier 2 elevated, and Tier 3 extreme. The area around and upstream of Copco

Lake is delineated as a Tier 2 elevated fire threat, as are most of the Klamath Basin areas west of Interstate-5 (Figure 3).

In September 2018, the Governor of California signed Senate Bill (SB) 901 into law. SB 901 provides a comprehensive approach to mitigating and improving resilience against wildfire risk and requires, through CPUC initiative, electrical utilities to develop and annually update wildfire mitigation plans (WMPs) (e.g., PacifiCorp, 2019, 2020) with review and approval from CPUC (Strike Force, 2019). In addition to SB 901, the Governor of California created a strike force, who drafted a report to coordinate the state's efforts and provide a plan for dealing with wildfire, climate change, and the energy sector and for reducing the incidence and severity of wildfires (Strike Force, 2019). The proposed wildfire mitigation and resiliency steps are 1) expand fire prevention activity, 2) make communities more resilient, 3) invest in fire suppression and response (e.g., detection cameras), and 4) call on the federal government to better manage federal forest land (Strike Force, 2019).

On January 8, 2019, the California Governor issued Executive Order (EO) N-05-19, which directed CalFire to recommend immediate and medium- and long-term actions to help prevent destructive wildfires with special attention to methods to quickly deploy personnel and resources. EO N-05-19 also described the Governor's proposed 2019-2020 budget, which will include investments in greater use of technology and equipment for the purpose of preventing and fighting wildfire. The CalFire response report to EO N-05-19 (CalFire, 2019) recommended, among other actions, a number of strategies to reduce fuels on private lands and improve defensible space regulations and enforcement.

2.3 Fire Risks Associated with Power Generation and Transmission

As licensee, PacifiCorp is responsible for fire risks associated with power generation and transmission from the Lower Klamath Project. PacifiCorp's service area includes all of Siskiyou County, California, and portions of the analysis area in Klamath and Jackson counties in Oregon.

The generation and transmission of power is a potential cause of fires, and utility-caused fires tend to spread rapidly and be among the most destructive (Strike Force, 2019). These potential ignition sources include equipment deterioration/failure, the interaction of power infrastructure with weather and environmental conditions, animals, vegetation, and external factors, operational or mis-operation, and lightning (PacifiCorp, 2019).

PacifiCorp released their first CPUC-required WMP (PacifiCorp, 2019), which describes their utility-related wildfire risk and its steps to mitigate that risk. The area analyzed in their WMP includes the Proposed Action and ASE areas. PacifiCorp queried their outage database in the Northern California service area from 2014 to 2018 for outages related to fire. They found that equipment failure (299 incidents), wind (74), animals (45), and trees (39) are the most numerous causes of fire-related outage per year and have the highest potential for ignition (PacifiCorp, 2019). In the period from 2007 to 2017, PacifiCorp infrastructure has not been an ignition source for any large fires (defined as grass fires >100 acres, timber fires > 5 acres) within their California service area. Several power outages in the analysis area were attributed to PacifiCorp power pole fires or animals interacting with power infrastructure (PacifiCorp, 2019).




Figure 3. Fire threat map of the Klamath Basin showing California Public Utilities Commission fire threat tier data.

3. FIRE SUPPRESSION AGENCIES, RESOURCES, AND CONSIDERATIONS

3.1 Fire Support and Services

Fire support and services in the ASE area are provided by multiple city, county, state, and federal fire suppression agencies, including United States Forest Service (USFS), Bureau of Land Management (BLM), the ODF Klamath-Lake District (KLD) and Southwest Oregon District (SWO), CalFire - Siskiyou Unit (CFSU), local districts of Klamath and Jackson Counties in Oregon and Siskiyou County, California, and local city and volunteer fire stations (Table 3-1). Fire safety and suppression resources are available from the various agencies in the event of a fire.

Table 3-1. Fire protection agencies in the ASE area, updated table from BOR & CDFG (2012).

Agency	Federal/State/Local	Jurisdiction
United States Forest Service	Federal	National Forests, federally managed land
United States Bureau of Land Management	Federal	BLM lands, federally managed land
CalFire	State of California	State Resource Lands, California
Oregon Department of Forestry	State of Oregon	State Resource Lands, Oregon
Klamath County Fire District	Local, County of Klamath	Unincorporated County Lands and the City of Klamath Falls
Colestin Rural Fire District	Local, County of Jackson	County Fire District in Jackson County, Oregon
Siskiyou County Fire Protection Districts: Copco Lake, Hornbrook, Montague, South Yreka, Tulelake, Etna, Ft. Jones, Weed	Local, County	Unincorporated County Lands throughout Siskiyou County, California
Mount Shasta Fire Department	Local, City of Mount Shasta	Mt. Shasta Municipal Boundaries
Yreka Fire Department	Local, City of Yreka	City of Yreka Municipal Boundaries

The USFS and BLM are the two federal agencies responsible for fire support and suppression in the ASE area. Both agencies provide wildfire protection primarily on land under their direct ownership and management but will provide support and assistance to other agencies when requested. Federal land near the ASE area is primarily limited to BLM parcels along the Klamath River downstream of J.C. Boyle Dam and along Iron Gate Reservoir and Copco Lake and secondarily to USFS lands south of Copco Lake (Figure 4). The BLM lands in the Proposed Action area are part of the Lakeview District and overseen by the Klamath Falls field office (T. Wilkie, Assistant Fire Management Officer, BLM Lakeview District, *pers. comm.*, 2020.06.10).




Figure 4. Land ownership around the analysis area. Figure from BOR & CDFG (2012).

The Oregon and California State forestry and fire prevention agencies (ODF and CalFire) are the primary fire protection providers in the unincorporated areas in the ASE area. ODF and CalFire enforce their respective state laws and regulations, and they coordinate fire support with the local agencies. CalFire operates and works with local city, county, and volunteer fire departments. The non-Federal land in Siskiyou County is in the CalFire State Responsibility Area (SRA), except lands directly managed by a local entity (e.g., in incorporated areas such as Yreka and Montague). Fire management in Siskiyou County is operated as CalFire Siskiyou Unit (CFSU). The Iron Gate and Copco Project sites are located within the CFSU Shasta Valley Battalion 2 area, and the river flows through Battalion 3. CalFire stations in the analysis area include the City of Yreka and Hornbrook, which is located 10 miles west of Iron Gate dam. The J.C. Boyle Project site in Oregon is under the jurisdiction of ODF KLD. The ODF KLD is a member of the South Central Oregon Fire Management Partnership (SCOFMP), which is a cooperative group of agencies including USFS, BLM, US Fish and Wildlife Service, and Crater Lake National Park. The SCOFMP shares resources to manage fire in the region, which primarily comprises Klamath and Lake counties. Dispatch responsibilities for the SCOFMP are with the Lakeview Interagency Fire Center (LIFC). Jackson County, Oregon, the southern portion of which is

part of the Klamath River Basin near the Project, is part of the ODF SWO. The northern portion of Siskiyou County, California, including the Iron Gate Reservoir and Copco Lake Project sites, is included in the fire protection area of ODF SWO that overlaps into California.

The city-operated fire stations in the ASE area include the Yreka and Mount Shasta Fire Departments in California. Many county fire stations are present throughout the analysis area and are associated with Klamath and Jackson counties in Oregon and Siskiyou County in California (Table 3-1).




Figure 5. Map of hospitals, fire stations, and major fire routes near the Klamath Dams. From BOR & CDFG (2012). Note, Klamath Falls Interagency Fire Center is now an air tanker base.

In the Oregon Proposed Action areas, primarily ODF KLD is responsible for organizing fire prevention and suppression, and stations and districts that service Oregon are in Table 3-2. ODF KLD operates within the SCOFMP and shares resources and responsibilities with the other agencies therein. Dispatch responsibilities for SCOFMP are handled by LIFC. Klamath County has 17 fire districts and 30 fire stations. Jackson County has several nearby fire districts also capable of providing fire suppression resources, including Greensprings Rural Fire District, Jackson County Fire Districts, and Ashland fire stations. For J.C. Boyle Dam, the closest station is the Keno Rural Fire Protection District Station 1, which is located approximately 6 miles to the east and hosts 2 fire engines, an ambulance, and a water tender among other equipment.

In the California Proposed Action areas, CFSU provides fire suppression resources and coordinates with additional local fires suppression entities (Table 3-2). CFSU has a CalFire- and USFS-staffed Emergency Command Center located at the CFSU Headquarters in Yreka that handles dispatching services for CalFire, USFS, 30 local government departments, and 5 ambulance companies (CalFire, 2016). CFSU is divided into 4 battalions, and the California Proposed Action area is in Battalion 2 (Shasta Valley), which has CalFire stations in Yreka and Hornbook. For the Copco and Iron Gate dams, the closest fire stations in the area is Yreka Fire Department and Copco Lake Fire Department Station 210, which services the area surrounding Copco Lake. Jackson County, Oregon, has several nearby fire districts, including Ashland and Jackson County Fire Districts and Colestin Rural Fire District, that can provide additional fire suppression resources.

Table 3-2. Fire services in the analysis area.

County	Fire Protection Services
Siskiyou County, CA	Fire protection is provided by 9 incorporated cities fire protection districts: Yreka, Fort Jones, Etna, Weed, Mt. Shasta, Dorris, Dunsmuir, Montague, and Tulelake. Other nearby fire protection districts and stations in Siskiyou County include Copco Lake Fire Protection District, Hornbrook Fire Protection District, Butte Valley Fire Protection District, Mayten Fire Protection District, and Grenada Fire Protection District. (CalFire, 2016)
City of Yreka, CA	Fire services are provided by the Yreka Fire Volunteer Department.
Klamath County, OR	Klamath County is served by 17 fire districts including Klamath County Numbers 1 through 5, Keno, Chiloquin, Central Cascades, Crescent, Oregon Outback, Chemult, Bonanza, Bly, Malin, and Merrill.
Jackson County, OR	Fire protection services provided by Jackson County include Ashland and Medford Fire and Rescue Stations and Jackson County Fire District Stations. Nearby services are provided by Colestin Rural Fire Protection District and Greensprings Rural Fire District.

Several of the fire suppression agencies have fire management and suppression plans that identify resources at risk and resources for fire suppression within their respective jurisdictions and outline protocols that would be initiated in the event of a fire. These plans were consulted in the development of the FMP and provide a continued reference resource. SCOFMP has a plan and set of operation protocols for fire support in the area (SCOFMP, 2015). Klamath County has a Community Wildfire Protection Plan document and companion database to support wildfire prevention and suppression planning efforts in the county (WFT, 2016). CFSU has a Unit Strategic Fire Plan that describes fire prevention goals and resources and guides fire management and fire suppression tactics (CalFire, 2016). Siskiyou County has a Community Wildfire Protection Plan, which is a collaborative document between the Fire Safe Council of Siskiyou County (FSCSC), CFSU, and Siskiyou County, developed to inform Siskiyou County communities and residents with fuel reduction treatments and reducing the ignitability of structures in the county (Siskiyou County, 2019).

3.2 Existing Management Resources and Strategies

In this section, we document the existing fire management resources and strategies, explain how they function, and describe other background considerations the influence fire management in the Basin. The

locations of existing fire detection and water resources for the ASE portion of the Klamath River Basin are shown in Figure 6.

3.2.1 Fire Detection

Rapid detection and reporting of wildfire ignitions are critical for the effective deployment of initial attack resources and suppression of wildfires before they grow to a large scale. The top goal listed by the CFSU Prevention Bureau is to reduce the total number and severity of fires (CalFire, 2016), and CalFire has made it an agency-wide goal to contain 95% of all unwanted fires at 10 acres or less (CalFire, 2002). California has statewide objectives to maintain an aggressive initial attack policy and utilize emerging technologies to improve emergency response effectiveness (California State Board of Forestry and Fire Protection (CSBFFP) and CalFire, 2018). The severity of a given fire is influenced by environmental conditions, but also by the length of time between start and detection. The fuel types and semi-arid climate in the Basin are conducive to the rapid growth of wildfires. Wildfires in the Basin can spread at rates as fast as 1.25 miles per hour (mph) (Siskiyou County, 2019; Stephens et al., 2008). As a result, early detection is critical in the analysis area.

In the Basin, wildfires are typically either reported by 911 calls or spotted from aerial surveillance and fire lookouts (Figure 6). 911 calls are a non-systematic method for detecting and locating wildfires. They require a chance sighting of smoke by a civilian and the ability to place a phone call. The ASE and Proposed Action areas are sparsely populated, and cellular coverage is poor, particularly adjacent to the Klamath River (Figure 7). In some locations, more than 30 minutes may be needed to acquire a cell signal. 911 callers may not properly identify the specific locations of smoke in the steep and rugged terrain in the rural basin. As a result, the exact location of the fire must be determined in the field by vehicle or helicopter, if available, after the 911 call has been received. With few roads and bridges crossing the Klamath River in the Basin, detailed knowledge of a newly ignited fire's location, especially with respect to which side of the Klamath River the reported fire is on, is vital to effectively deploy the appropriate resources in a timely manner. Fire containment is achieved by the construction of fire lines, which typically require ground resources (J. Fried, pers. comm., 2019.08.27). With only a few access roads and bridges crossing the Klamath River, precise and accurate knowledge of fire location can save ground resources minutes to hours of time as they commence initial attack in the Basin.



Figure 6. Overview map of the existing fire management resources in the Klamath River Basin near the Project.

Fire lookouts provide an effective vantage for detecting smoke and its location. Historically, fire lookouts have been staffed during fire season, and this practice continues at the fire lookouts at Parker Mountain, Oregon, (staffed by ODF KLD) and Paradise Craggy, California, (staffed by CFSU) (Figure 6). With favorable conditions, the distance at which the human eye is able to detect smoke from a fire lookout is approximately 7 miles. A newer practice in the West is exchanging human presence in the lookouts for video cameras, the live web feed of which can be monitored remotely online (e.g., ALERTWildfire).




Figure 7. Cell coverage in the ASE area where white indicates “no coverage.” Coverage maps generated from their respective carrier websites on May 12, 2020.

The state-of-the-art technique for early detection of wildfires is the “Monitored Detection System” (MDS), whereby high definition imagery and video transmitted from cameras strategically placed at fire lookouts is monitored for smoke by humans at a detection center. The EnviroVision Solutions (EVS) ForestWatch® software integrates the camera feed with a GIS platform, and locations of fires can be triangulated if captured by cameras in more than one location. This, combined with an on-site dispatch center, enables rapid and efficient deployment of initial attack resources from fire stations and in the field. The MDS technology is an improvement over more passive live web feed cameras because it has dedicated staff monitoring it and is integrated with the GIS platform, among other benefits and capabilities. The MDS technology is an improvement over manned lookout towers because the cameras have a greater visible distance than the human eye (e.g., 12 miles vs. 7 miles, respectively depending on conditions; Appendix A) and a single staff member can monitor the feed from many cameras simultaneously.

ODF SWO has had a functional MDS since 2012, and ODF KLD installed one in 2019. Currently, two MDS cameras (one from ODF SWO located on Soda Mountain, OR, and one from ODF KLD on Chase Mountain, OR) are currently directed into the ASE area (Figure 6). The ODF SWO system has been in place since 2012 and has included a dedicated staff for monitoring since 2017. The Chase Mountain MDS camera was installed in 2019.

The viewshed (i.e., visibility coverage) with the existing fire lookouts and two MDS cameras in the ASE area was analyzed in the Reax report (Appendix A) and is shown in Figure 8. Currently, there is coverage by a single observer (camera or fire lookout) at 500 Ft above the ground surface for much of the northern portion of the ASE area, but a much smaller fraction of the south side of the ASE area is covered by the existing viewshed. With coverage by only a single observer, it is challenging to decipher, e.g., what side of the Klamath River a fire is located, so it is preferable to have two or more observers to effectively triangulate fire locations.




Figure 8. Viewshed analysis at 500 Ft above ground surface for existing detection resources with green and yellow indicating visibility by one and two observers, respectively. From Reax report (Appendix A).

3.2.2 Prevention and Preparedness

Community preparedness and pre-prevention is an important component of both ODF and CalFire missions. Both agencies direct resources to the education of the local community on fire season proclamation and regulated use restrictions, fire hazards, and defensible space. Defensible space around structures is a legal requirement for California and Oregon residents (CA - PRC 4921; OR - ORS 477.015 - 477.061; OAR 629-044-1000 - 629-044-1110) and critical for preventing structure fires. Increasing the number of defensible homes is on the CFSU Prevention Bureau's list of goals (CalFire, 2016) and educating landowners and residents about defensible space and increasing the number and effectiveness of inspections are statewide

objectives (CSBFFP and CalFire, 2018). The CalFire response report to EO N-05-19 (CalFire, 2019) explicitly encourages private landowners to engage in fuel reduction projects and proposes several projects to improve community defensible space (CalFire, 2019). To assist Siskiyou County residents with creating defensible space, the Yreka Area Fire Safe Council organized a grant-funded 2018 community event called “Chipper Days,” whereby a chipper was rented and driven around to chip fuels and debris from private property around the county. Improving defensible space is a top, county-wide priority for many groups in Siskiyou County, including the FSCSC (Siskiyou County, 2019).

3.2.3 Water Sources and Access

Water sources and access to them are vital for fire suppression for both ground-based and aerial crews and for both structure fires and wildfires.

Ground-based resources (e.g., fire engines, dozers, and hand crews; Lee et al., 2012) are typically used for structure fires, initial attack, and line support for wildfires. Ground-based efforts to procure water resources in the ASE area are currently supported with boat launches around the reservoirs and along the river, with a gravity fed hydrant system at Copco Lake, and a two-hydrant system that services the gated area near the Copco No. 2 powerhouse. Boat launches and river access points provide dependable access for ground-based resources to draft water from the river and reservoirs. There are currently 12 total boat launches in the ASE area: three boat launches around Iron Gate Reservoir, two around Copco Lake, two around J.C. Boyle Reservoir, and others along the free-flowing Klamath River and Keno Reservoir (Figure 6). Several of these boat launches (e.g., Iron Gate Hatchery, Fall Creek, Copco Cove) have a gravel surface with narrow access roads and are not suitable for use by water tenders and fire engines. The hydrant system at Copco Lake consists of six hydrants that are the primary water sources for the Copco Lake Fire Department to protect the community and structures at the upstream portion of Copco Lake (Figure 6). These hydrants are gravity-fed from a water storage tank, which is filled from a spring and supplemented by a well, and operated by agreement between Copco Lake Mutual Water Company and Copco Lake Fire Department.


Aerial efforts with helicopters, which are used for both initial and extended attack, are a critical component of wildfire suppression and are capable of applying large volumes of water (*cf.* Table 3-3) to remote areas. Firefighting helicopters vary in size and water-carrying capacity and are classified into three types (1 to 3 from largest to smallest). The two mechanisms for aerial drafting of water are snorkels and buckets. Snorkels (e.g., Table 3-3) are only used by Type 1 and Type 2 helicopters and involve lowering a hose directly into a water source and pumping water into an on-board tank. The hoses are on the order of 10 Ft in length, so snorkel helicopters must get correspondingly close to the water surface. The water tank capacity can vary from 100 gallons to 3000 gallons depending on the size of the helicopter (CalFire, n.d.-a). Buckets are suspended from longlines attached the helicopters and lowered into the water source to be filled. The volume and line length vary, with smaller Type 3 helicopters operating shorter lines with buckets on the order of 100 to 200 gallons (CalFire, n.d.-a) and Type 1 helicopters supporting 100 Ft to 200 Ft lines with bucket capacity of over 2000 gallons (CalFire, n.d.-a).

Desired conditions for aerial suppression include well-distributed water sources suitable for drafting by a range of aircraft and drafting mechanisms simultaneously; potentially minimizing the turn-around time between water drops. The suitability of a water source for drafting depends on water depth and the dimensions of the water surface, which relate to the physical space available for a helicopter to safely hover

and for the drafting mechanism to draw water. Deeper and wider water sources are easier, faster, and safer choices for drafting. Buckets and snorkels typically need about 3 Ft of water depth, but deeper sources are preferred, especially for large buckets. Buckets can be safely used in narrower water bodies than snorkels can because the helicopters do not need to be as close to the water surface.

Specific guidelines for snorkel drafting rotor safety clearance (i.e., the lateral distance between the tips of the helicopter rotors and vegetation, infrastructure, or other obstructions) are not formally established, so it is up to pilot discretion which water sources they feel comfortable drafting from (CalFire, n.d.-b; Section 8344.5.2). Experienced pilots often utilize pools narrower than the recommended drafting safety clearance of 150 Ft (Table 3-3; L. Winslow ODF SWO, *pers. comm.*, 2019.05.16). Drafting is dangerous, and the hazard is greater for narrow water sources in confined, steep terrain. Proximity of a water source is a key consideration as each mile of travel distance will add several minutes to the draft and drop turn-around time. As such, pilots usually seek the closest suitable drafting source, rather than travel longer distance to access the best water source.

Table 3-3. Comparison of common firefighting helicopters.

Helicopter	Bell Super Huey (UH-1H)	Sikorsky Skycrane (S-64)	Sikorsky Firehawk (UH-70)
Type	2	1	1
No. rotors	1	1	1
Rotor diameter (Ft)	48	72	54
Aircraft Length (Ft)	57	89	65
Landing zone minimum diameter ¹ (Ft)	86	135	100
Pool drafting diameter ² (Ft)	348	372	354
Water capacity (gal)	360	2650	1000
Photos ³			

¹ Minimum diameter for landing is 1.5X the aircraft length (USFS & OAS, 2015).

² Recommended safe lateral clearance from tip of rotor during drafting is approximately 150 Ft (L. Winslow, ODF-SWO, *pers. comm.*, 2019.04.02). Minimum drafting diameter is rotor diameter plus 300 Ft.

³ Photo sources (from left to right): Prestige Worldwide; S. Wright, 2012; www.helis.com

Aerial fire suppression in the ASE area is currently supported by the Klamath River and reservoirs, including Keno Reservoir, Lake Ewauna, and Upper Klamath Lake, as primary water sources. The reservoirs are wide, deep, and lower hazard drafting sources that are capable of supplying water to multiple aircraft of any size

simultaneously. The mainstem Klamath River offers suitable drafting locations as well. The Renewal Corporation identified 96 aerial river access points (ARAPs; i.e., locations with hydraulic conditions appropriate for helicopter drafting) currently in the free-flowing Klamath River from Keno Dam to I-5, and the inventory was reviewed and approved by ODF SWO (ODF SWO, *pers. comm.*, 2019.05.46). Portions of the mainstem Klamath River in the ASE area are around 200 Ft wide between tall woody riparian vegetation. This distance is too narrow to meet drafting safety clearance recommendations for Type 1 helicopters with snorkels but does meet the Type 1 minimum landing area requirements (Table 3-3). Type 2 and Type 3 helicopters with buckets currently draft from many parts of the Klamath River, including the reach near Hornbrook (Appendix A) and the narrow confines of the Klamath Canyon between J.C. Boyle Dam and Copco Lake (ODF KLD, *pers. comm.*, 2019.05.16). The ability and willingness to use the Klamath River is dependent on pilot experience and comfort and on environmental variables (e.g., wind speed and direction). Smaller sources (e.g., ponds on private property) will be used opportunistically when they are the closest source to a drop location. For example, on the 2018 Klamathon Fire, two runoff ponds and the free-flowing Klamath River were used as dip sites in addition to Iron Gate Reservoir because they were closer to the drop location (Appendix A).

4. REGULATIONS AND REQUIREMENTS

The FMP is developed to meet or exceed the regulations and requirements set forth by the controlling fire suppression agencies in the Proposed Action area (Figure 4). The Renewal Corporation will comply with all applicable requirements. Most of the dam deconstruction and reservoir management will take place on private land. Private lands are under the protection of ODF and CalFire, agencies that handle state regulations for fire management regarding various construction related activities. Measures for fire preparedness, prevention, and suppression in addition to those prescribed by state and Federal law are described in Section 5 Short-Term Fire Management Plan.

4.1 Federal

Federal agencies (BLM and USFS) manage their respective lands, and regulations only need to be met for construction taking place on federal land. In Oregon, there are several BLM parcels along the Klamath River in the J.C. Boyle Proposed Action area. These parcels are managed as part of the SCOFMP. Fire-related restrictions on these parcels follow the industrial operations requirements and restrictions that correspond to four adjective classes of the Industrial Fire Precautionary Levels (IFPL) (T. Wilkie, Assistant Fire Management Officer, BLM Lakeview District, *pers. comm.*, 2020.06.10). In California, a few BLM parcels are located near the Copco Proposed Action footprint. In the California locations, BLM generally defers to restrictions corresponding to the Predicted (or Designated) Activity Levels (PALs) set by the USFS Klamath National Forest and relies on CalFire for direct protection responsibilities (L. Brodhead, BLM Redding, *pers. comm.*, 2017.08.29). For logging operations on BLM land in California, contractual fire prevention and suppression measures vary between projects but must typically conform to general CalFire and USFS regulations and the input from a BLM Authorized Agent assigned to the contract (L. Brodhead, BLM Redding, *pers. comm.*, 2017.08.29). The USFS owns land that is near Copco Lake but outside of the Proposed Action footprint. Therefore, the FMP does not address specific USFS fire prevention and suppression requirements outlined in the Code of Federal Regulations (CFR) or the United States Code (USC) (e.g., 16 USC 551, 36 CFR

261.50, and 36 CFR 261.52). The Proposed Action will comply with the applicable state regulations described in Sections 4.2 and 4.3, which are comparable with regards to fire related restrictions.

4.2 Oregon Department of Forestry Klamath-Lake District

Oregon law prescribes regulations and minimum requirements for fire prevention and suppression that are applicable in each ODF Fire Protection District during fire season. Oregon fire season is declared by each ODF district and is typically between early June and mid-to-late October. The laws and requirements for all ODF districts are provided in Table 4-1.

ODF districts west of the Cascades crest, which includes ODF SWO, have industrial operations requirements and restrictions that correspond to IFPLs. A different system is in place for ODF districts east of the Cascades crest, such as ODF KLD. Construction operations must follow the regulations in Table 4-1 for all levels of fire danger during fire season. Additional restrictions are enforced when fire hazard is classified as “extreme.” ODF does not have general restrictions or requirements when work is performed outside of the fire season.

A permit must be obtained from the ODF state forester for construction activities that involve heavy machinery. The permit is the “Permit for Power-Driven Machinery (PDM),” which is described by Oregon law ORS 477.625. There are fire prevention requirements that accompany the permit that are dependent on the Fire Danger Level (FDL). The PDM permit relates requirements for fire prevention and suppression preparedness to type of machinery and fire hazard. The requirements are more restrictive during “Extreme” adjective class FDL and include the suspension of the operation of tracked machinery between the hours of 1 pm and 8 pm as prescribed by the PDM (ORS 477.625(1a), OAR 629-043-0026(5)). The use of tracked equipment is expected at the Proposed Action sites and, if a PDM was required, would be subject to these restrictions during extreme fire danger. ODF typically informs PDM permit holders of changes in fire hazard and operation requirements. PDM permits expire at each new calendar year and must be renewed. The ODF forester can grant waivers from the fire prevention and suppression requirements, including the PDM, in some instances. Waivers may be granted in certain project areas for favorable weather conditions, topographic setting, and/or if alternate methods and equipment proposed by the operator provide equal or better fire prevention and suppression.

Table 4-1. 2019 ODF fire season minimum requirements (ODF, 2019).

Topic	Law	Description
No Smoking	ORS 477.510	No smoking while working or traveling in an operation area
Hand Tools	ORS 477.655, OAR 629-043-0025	Supply hand tools for each operation site - 1 tool per person with a mix of pulaskis, axes, shovels, hazel hoes. Store all hand tools for fire in a sturdy box clearly identified as containing firefighting tools. Supply at least one box for each operation area. Crews of 4 or less are not required to have a fire tools box as long as each person has a shovel, suitable for firefighting and available for immediate use while working on the operation.

Topic	Law	Description
Fire Extinguishers	ORS 477.655, OAR 629-43-0025	Each internal combustion engine used in an operation, except power saws, shall be equipped with a chemiCalFire extinguisher rated as not less than 2A:10BC (5 pound).
Power Saws	ORS 477.640, OAR 629-043-0036	<p>Power saws must meet Spark Arrester Guide specifications - a stock exhaust system and screen with < 0.023 inch holes.</p> <p>The following shall be immediately available for prevention and suppression of fire:</p> <ul style="list-style-type: none"> - One gallon of water or pressurized container of fire suppressant of at least eight-ounce capacity - 1 round pointed shovel at least 8 inches wide with a handle at least 26 inches long - The power saw must be moved at least 20' from the place of fueling before it is started.
Fire Tools, Extinguishers for Trucks	ORS 477.655, OAR 629-043-0025	<p>Equip each truck driven in forest areas for industrial purposes with:</p> <ul style="list-style-type: none"> - 1 round pointed shovel at least 8 inches wide, with a handle at least 26 inches long - 1 axe or Pulaski with 26 inch handle or longer - 1 fire extinguisher rated not less than 2A:10BC (5 pound).
Spark Arresters and Mufflers	ORS 477.645, OAR 629-043-0015	<p>All non-turbo charged engines must meet Spark Arrester Guide specifications except:</p> <ul style="list-style-type: none"> - Fully turbo charged engines. - Engines in motor vehicles operating on improved roads equipped with an adequate muffler and exhaust system. - Engines in light trucks (26,000 GVW or less) that are equipped with an adequate muffler and an exhaust system. - Engines in heavy trucks (greater than 26,000 GVW) that are equipped with an adequate muffler and exhaust system. - If a truck engine is not fully turbo-charged, then the exhaust must extend above the cab and discharge upward or to the rear, or to the end of the truck frame. - Water pumping equipment used exclusively for fighting fire. - Engines of 50 cubic inch displacement or less, except ATV's and motorcycles, shall be equipped with an adequate muffler and an exhaust system. - Engines in ATV's and motorcycles must be equipped with an adequate muffler and exhaust system or an approved screen, which completely encloses exhaust system. - Power saws. (See power saw requirements)

Topic	Law	Description
Pump, Hose, and Water Supply	ORS 477.650, 477.625, OAR 629-043-0026, 629-43-0020	<p>Supply a pump, hose and water supply for equipment used on an operation.</p> <ul style="list-style-type: none"> - Pump must be maintained ready to operate and capable to provide a discharge of not less than 20 gallons per minute at 115 psi at pump level. Note: Volume pumps will not produce the necessary pressure to effectively attack a fire start. Pressure pumps are recommended. - Water supply shall be a minimum of 300 gallons if a self-propelled engine. Water supply shall be a minimum of 500 gallons if not self-propelled (pond, stream, tank, sump, etc.) - One water supply is adequate as long as the operator can deliver water to the fire within 10 minutes - Provide enough hose (500 feet minimum) not less than 3/4" inside diameter to reach areas where power driven machinery has worked. Note: Should a fire occur, the operator must be able to position the water supply in a location where enough hose is available to reach the area worked by power driven machinery. This includes mobile equipment as well as motorized carriages and their moving lines. Moving lines are defined as main lines and haul back lines. This can be achieved in many ways, including the practice of having a water tank and hose attached to a piece of equipment, like a skidgen or skidder, that can get the water to the fire. - Water supply, pump, and at least 250' of hose with nozzle must be maintained as a connected, operating unit ready for immediate use.
Fire Watch Service	ORS 477.665, OAR 629-043-0030	<p>Each operation area is to have a fire watch. Fire watch shall be on duty during any breaks (up to 3 hours) and for three hours after all power-driven machinery used by the operator has been shut down for the day.</p> <p>The ODF KLD has specific fire watch duration prescriptions based on FDL adjective class.</p> <ul style="list-style-type: none"> - Low = 1 hr fire watch - Moderate = 2 hrs - High to Extreme = 3 hrs <p>Fire watch shall:</p> <ul style="list-style-type: none"> - Be physically capable and experienced to operate firefighting equipment. - Have facilities for transportation and communications to summon assistance. - Observe all portions of the operation on which activity occurred during the day. <p>Upon discovery of a fire, Fire watch personnel must: First report the fire, summon any necessary firefighting assistance, describe intended fire suppression activities and agree on a checking system; then, after determining a safety zone and an escape route that will not be cut off if the fire increases or changes direction, immediately proceed to control and extinguish the fire, consistent with firefighting training and safety.</p>

Topic	Law	Description
Operation Area Fire Prevention	ORS 477.625, OAR 629-043- 0026	<ul style="list-style-type: none"> - Keep all power driven machinery free of excess flammable material which may create a risk of fire. - Avoid line-rub on rock or woody material, which may result in sparks or sufficient heat to cause ignition of a fire. - Disconnect main batteries from powered components (other than what may be necessary to retain computer memory) through a shut-off switch or other means or leave equipment on ground cleared of flammable material.

4.3 CalFire Siskiyou Unit

California law prescribes regulations and minimum requirements for fire prevention and suppression that are applicable during fire season in all lands within the CalFire jurisdiction. The California Public Resources Code (PRC) requires preventative fire measures (Table 4-2) that are imposed during the time where a Burn Permit is required under PRC-4423. For Zone B, which includes the Northern California counties, this period usually begins May 1 and persists until proclamation of the termination of fire season by a CalFire Director. CalFire does not require a permit for the use of equipment and heavy machinery on a construction site. State forest and fire laws may be enforced by USFS, BLM, NPS, and certain county fire departments in addition to CalFire personnel. The California Code of Regulations (CCR) has specific and generally applicable regulations that pertain to fire prevention and suppression, e.g., requirements for smoking during fire season, but there are no associated permits required. The CCR, PRC, and CFR regulations pertaining to construction sites and logging operations in California and the associated best management practices are described in detail in the *CalFire Industrial Operations Fire Prevention Guide* (1999).

Table 4-2. Fire precautionary measures required by California Public Resources Code (PRC) and applicable during any times of the year when burning permits are required unless otherwise stated.

Topic	Law	Description
Fire Causing Equipment	PRC- 4427	<p>No person shall use or operate any motor, engine, boiler, stationary equipment, welding equipment, cutting torches, tarpots, or grinding devices from which a spark, fire, or flame may originate, which is located on or near any forest-covered land, brush-covered land, or grass-covered land, without doing both of the following:</p> <ul style="list-style-type: none"> - First clearing away all flammable material, including snags, from the area around such operation for a distance of 10 feet. - Maintain one serviceable round point shovel with an overall length of not less than 46 inches and one backpack pump water-type fire extinguisher fully equipped and ready for use at the immediate area during the operation. <p>This section does not apply to portable powersaws and other portable tools powered by a gasoline-fueled internal combustion engine.</p>

Topic	Law	Description
Use of Internal Combustion Engines	PRC-4428	<p>No person shall use or operate any vehicle, machine, tool or equipment powered by an internal combustion engine operated on hydrocarbon fuels, in any industrial operation located on or near any forest, brush, or grass-covered land between April 1 and December 1 of any year, or at any other time when ground litter and vegetation will sustain combustion permitting the spread of fire, without providing and maintaining, for firefighting purposes only, suitable and serviceable tools.</p> <ul style="list-style-type: none"> - A sealed box of tools shall be located, within the operating area, at a point accessible in the event of fire. This fire toolbox shall contain: one backpack pump-type fire extinguisher filled with water, two axes, two McLeod fire tools, and a sufficient number of shovels so that each employee at the operation can be equipped to fight fire. - One or more serviceable chainsaws of three and one-half or more horsepower with a cutting bar 20 inches in length or longer shall be immediately available within the operating area, or, in the alternative, a full set of timber-felling tools shall be located in the fire toolbox, including one crosscut falling saw six feet in length, one double-bit ax with a 36-inch handle, one sledge hammer or maul with a head weight of six, or more, pounds and handle length of 32 inches, or more, and not less than two falling wedges. - Each rail speeder and passenger vehicle shall be equipped with one shovel and one ax, and any other vehicle used on the operation shall be equipped with one shovel. Each tractor used in such operation shall be equipped with one shovel.
Fire Fighting Tools	PRC-4429	<p>In an area of any industrial or other operations on or near any forest-covered land or brush-covered land, there shall be provided and maintained at all times, in a specific location, for firefighting purposes only, a sufficient supply of serviceable tools to equip 50% of the able-bodied personnel for fighting fires.</p> <ul style="list-style-type: none"> - Tools shall be included shovels, axes, saws, backpack pumps, and scraping tools. - One serviceable headlight adaptable for attachment to at least one-half of the tractor-bulldozers used on the operation. - A sufficient number of canteens and flashlights to equip a third of the able-bodied personnel.

Topic	Law	Description
Water Pumps	PRC-4430	<p>The use or operation of any steam-operated engine or machine equipment, located on or near forest-covered land or brush-covered land, requires</p> <ul style="list-style-type: none"> - One adequate force pump or water under pressure equivalent to a pump, and not less than 200 feet of hose not less than one inch in diameter for each steam-operated engine or equipment. - The pump or water pressure shall be capable of applying a minimum of 40 pounds pressure at the nozzle on 200 feet of hose, such nozzle to be 0.25 inch or larger in diameter. - If two steam-operated engines or steam equipment are customarily operated within 100 feet of each other, only one engine or piece of equipment need be equipped with pump and hose.
Gas Powered Saws	PRC-4431	<p>No person shall use or operate or cause to be operated any portable saw, auger, drill, tamper, or other portable tool powered by a gasoline-fueled internal combustion engine on or near any forest-covered land, brush-covered land, or grass-covered land, within 25 feet of any flammable material, without providing and maintaining at the immediate locations of use or operation of the saw or tool, for firefighting purposes one serviceable round point shovel, with an overall length of not less than 46 inches, or one serviceable fire extinguisher.</p> <p>The Director of Forestry and Fire Protection shall by administrative regulation specify the type and size of fire extinguisher necessary to provide at least minimum assurance of controlling fire caused by use of portable power tools under various climatic and fuel conditions.</p> <p>The required fire tools shall at no time be farther from the point of operation of the power saw or tool than 25 feet with unrestricted access for the operator from the point of operation.</p>

Topic	Law	Description
Spark Arresters	PRC-4442	<ul style="list-style-type: none"> - No person shall use, operate, or allow to be used or operated, any internal combustion engine which uses hydrocarbon fuels on any forest-covered land, brush-covered land, or grass-covered land unless the engine is equipped with a spark arrester maintained in effective working order or the engine is constructed, equipped, and maintained for the prevention of fire. - Spark arresters affixed to the exhaust system of engines or vehicles shall not be placed or mounted in such a manner as to allow flames or heat from the exhaust system to ignite any flammable material. - A spark arrester is a device constructed of nonflammable materials specifically for the purpose of removing and retaining carbon and other flammable particles over 0.0232 of an inch in size from the exhaust flow of an internal combustion engine that uses hydrocarbon fuels or which is qualified and rated by the United States Forest Service. - Engines used to provide motive power for trucks, truck tractors, buses, and passenger vehicles, except motorcycles, are not subject to this section if the exhaust system is equipped with a muffler. - Turbocharged engines are not subject to this section if all exhausted gases pass through the rotating turbine wheel, there is no exhaust bypass to the atmosphere, and the turbocharger is in effective mechanical condition.
Exclusion of Outdated, Handheld Internal Combustion Equipment	PRC-4443	No person shall use, operate, or cause to be operated on any forest-covered land, brush-covered land, or grass-covered land any handheld portable, multi-position, internal-combustion engine manufactured after June 30, 1978, which is operated on hydrocarbon fuels, unless it is constructed and equipped and maintained for the prevention of fire.

5. NEAR-TERM MEASURES: CONSTRUCTION-RELATED ACTIVITIES

This section describes near-term fire management associated with construction-related activities for the Proposed Action. The purpose of the near-term fire management plan is to eliminate and/or mitigate fire sources and to prevent loss of life and property by adhering to and implementing all agency regulations and requirements, all applicable standards from the National Fire Protection Association (NFPA), and industry-accepted best workplace practices.

Near-term fire management is divided into two Proposed Action time periods: 1) during Dam Decommissioning and Removal (i.e., Phase 1, 2, and 3A in the DDP [Renewal Corporation, 2020]); and 2) during Restoration and Monitoring (i.e., Phase 3B in the DDP [Renewal Corporation, 2020]). Dam Decommissioning and Removal corresponds to the period from the commencement of construction activities to the complete removal of the four dams and all associated facilities. Restoration and Monitoring corresponds to the time period from the onset of restoration and monitoring activities, as described in Reservoir Area Management Plan of the Definite Decommissioning Plan (Renewal Corporation, 2020), in the de-watered reservoirs to the conclusion of monitoring and restoration activities in the former reservoirs.

The Renewal Corporation design-build contractor responsible for fire management during dam decommissioning and removal is Kiewit Corporation. The Renewal Corporation contractor responsible for fire management during restoration and monitoring is Resource Environmental Solutions, LLC (RES). The fire prevention and suppression measures and responsibilities described in the near-term measures apply to both Kiewit and RES (the Contractors), but Kiewit and RES will operate and apply this Fire Management Plan independently of one-another.

5.1 Roles and Responsibilities

5.1.1 During Dam Decommissioning and Removal - Kiewit

The Renewal Corporation's design-build contractor, Kiewit, will comply with all applicable requirements and implement best management practices to prevent, contain, or control any fire associated with construction. Kiewit is responsible for providing FERC a real-time report for any fires caused as a result of the Proposed Action during dam decommissioning and removal. Kiewit has never caused a wildfire as a result of one of their construction projects and has a long track record of avoiding and mitigating against wildfires on large construction projects in the fire-prone regions similar to the analysis area. No wildfires were caused by their recent California and western North America construction projects, which include the reconstruction of the Oroville and Folsom dam spillways in the high-fire risk California Sierra foothills. Kiewit successfully mitigated against on-going wildfires and fire risks in remote and rugged terrain on Kwalsa and Upper Stave hydropower construction project in British Columbia.

Kiewit is an industry leader in safety statistics and always employs best practices for their projects. They have Crisis Management and Fire Prevention Plans for each their projects. They refine and adapt site- and conditions-specific fire prevention methods as needed. They routinely have safety meetings and equipment

checks. Kiewit practices a fire watch on construction sites, and, for the Kwalsa and Upper Stave project, even conducted a 24/7 watch patrol to monitor conditions associated with the on-going wildfires.

The Kiewit personnel roles and responsibilities pertaining to near-term fire management for the Proposed Action are shown in Table 5-1. Kiewit has a trained Safety Manager already assigned to the Proposed Action, and he will serve as the fire-specific Safety Officer (see Section 5.1.3), who will be the primary Kiewit contact and fire manager on-site during construction. Kiewit will also have a construction manager to assist the Safety Officer with ensuring the execution of the FMP. The Kiewit Project Manager, in coordination with the Safety Officer, is in charge of overall fire management.

Table 5-1. Kiewit primary leads for fire protection and control.

Title	Plan Responsibilities
Kiewit Project Manager	<ul style="list-style-type: none"> - Overall fire prevention and control management - Implementation and review of the Fire Management Plan (FMP) - Maintain communication with local firefighting agencies
Kiewit Safety Manager/Officer	<ul style="list-style-type: none"> - Update on fire conditions and communicate conditions to site personnel - Training of site personnel in the use of fire protection equipment - Check all fire protection systems and equipment are installed and maintained - Enforce all standards, regulations, and best practices described in the FMP
Kiewit Construction Manager	<ul style="list-style-type: none"> - Check that the necessary resources and processes are in place for the implementation of the FMP - Check that all personnel comply with fire prevention and flammable storage requirements - Check that the necessary resources and processes are in place for the implementation of the FMP - Enforce all standards, regulations, and best practices described in the FMP
Kiewit Superintendents and Field Engineers	<ul style="list-style-type: none"> - Verify that all personnel are aware of the site fire prevention methods and potential fire hazards. - Responsible for supervising the permit system for hot work operations
Kiewit employees and subcontractors	<ul style="list-style-type: none"> - Complete all required training as assigned by the FMP - Conduct work operations safely to limit or eliminate the risk of a fire related incident. - Report potential fire hazards to their supervisors as soon as possible - Operate in accordance with FMP

5.1.2 During Restoration and Monitoring - RES

The Renewal Corporation's monitoring and restoration contactor, RES, will comply with all applicable requirements and will implement best management practices to prevent, contain, or control any fire

associated with construction. RES is responsible for providing FERC a real-time report for any fires caused as a result of the Proposed Action during restoration and monitoring. RES prioritizes safety as its top core value. Whether the focus of their work be geared toward active construction, field work, or monitoring activities, the approach to safety is specific, methodical, deliberate and collaborative. RES has a fully-staffed Environmental Health, Safety and Security (EHS&S) department, led by a Certified Safety Professional (CSP)-credentialed Director and supported by dedicated Specialists embedded within each region to verify that work is completed compliantly, responsibly, and, most importantly, safely.

For each their projects, RES completes team-focused and comprehensive risk assessments, designed to account for hazards specific to project activities. After developing a risk mitigation plan for the identified hazards and applying the hierarchy of controls, RES develops an emergency action plan and a robust communication strategy between personnel and emergency response government organizations. RES checks that requisite training is obtained by all applicable employees (Table 5-2) and includes: California Fire Prevention, OSHA 10/30 Hour Construction, CPR, First Aid, AED, and fire management. Orientations are required for all new RES employees, as well as site contractors. RES will have routine and continuous worksite inspections to create a culture of safety and security excellence, and that RES is focused on being compliant with necessary regulations and requirements. RES will have a Safety Officer (see Section 5.1.3) on site. RES will maintain an open line of communication between all project stakeholders and see that all identified risks or hazards that develop are met with immediate response. The RES Project Manager, in coordination with the Safety Officer, is in charge of overall fire management.

Table 5-2. RES leads for fire protection and control.

Title	Plan Responsibilities
RES Project Manager	<ul style="list-style-type: none"> - Overall fire prevention and control management - Implementation and review of this Fire Management Plan (FMP) - Maintain communication with local firefighting agencies
RES Environmental Health, Safety, and Security Department (EHS&S)	<ul style="list-style-type: none"> - Work with and support Safety Officer (see Section 5.1.3) to develop, administer, and maintain the FMP - Check that all fire protection systems and equipment are installed and maintained - Conduct a Fire Risk Survey in applicable facilities - Train employees in recognition, reporting, and controlling fire hazards - Train employees in the use and operations of fire protection/suppression systems and equipment
RES EHS&S Safety Officer	<ul style="list-style-type: none"> - Be on-site responsible party for EHS&S department - Update on fire conditions and communicate conditions to site personnel - Check that all fire protection systems and equipment are installed and maintained - Train employees in the use and operations of fire protection/suppression systems and equipment - Train employees in recognition, reporting, and controlling fire hazards - Monitor and check that fuel source hazards are properly stored and handled

Title	Plan Responsibilities
RES Supervisors	<ul style="list-style-type: none"> - Verify that employees receive the required training and notifying their EHS&S Safety Officer when there is a change in operations that creates or increases the potential for a fire related incident - Enforce all standards, regulations, and best practices described in the FMP - Check that the necessary resources and processes are in place for the implementation of the FMP - See that all personnel comply with fire prevention and flammable storage requirements
RES employees and subcontractors	<ul style="list-style-type: none"> - Complete all required training as assigned by the EHS&S Department and the FMP - Conduct work operations safely to limit or eliminate the risk of a fire related incident. - Report potential fire hazards to their supervisors as soon as possible - Operate in accordance with FMP

5.1.3 Safety Officer

Each contractor will designate a Safety Officer, and each Safety Officer will be responsible for overseeing fire responsibilities for their respective operations. The Safety Officer will be available and on-call 24 hours a day, 7 days a week in the event of a fire. They will be specifically identifiable on-site (NFPA, 2018). The Safety Officer will be the primary on-site communication linkage to ODF and CalFire personnel and will communicate with state and local fire suppression agencies regularly when Proposed Action conditions and locations change and at least weekly during fire season. The Safety Officer for each Contractor will get agency sign-off on the FMP with a target date before construction. Agency communication topics include:

- Reviewing and getting agency approval on the FMP with a target date before construction
- Developing site- and Proposed Action-timeline specific Fire Prevention Plan with a target date before construction and modifying as needed over course of the Proposed Action
- Discussing fire hazards, prevention, suppression, and contingency plans prior to and during construction (NFPA, 2018)
- Identifying water sources (e.g., fire hydrants, reservoirs, rivers, pond) and access points proximal to the operation areas. The Safety Officer will supplement scarce water resources with water storage tanks as needed.
- Identifying fire protection features and firefighting resources (NFPA, 2018)
- Identifying existing resources and infrastructure in the Proposed Action areas that are at risk in the event of a fire
- Informing agency contacts of any modifications to existing water resources due to dam removal activities, e.g., the drawdown of the reservoirs
- Evaluating the location, condition, and importance of existing fuel breaks, and determining if fuel breaks need to be modified to envelop the work area

The Safety Officer will be responsible for all on-site fire management for the Proposed Action, verifying that the measures included in the FMP are enacted, and communicating with all Proposed Action personnel. The Safety Officer's on-site duties include:

- Conducting fire hazard assessment of the Proposed Action sites with a target date before construction in an area. The assessment will include an evaluation of fuels and vegetation, landscape characteristics, fire history, fire danger rating, potential fire behavior, firefighting capabilities and limitations, and ingress and egress (NFPA, 2018)
- Monitoring and identifying conditions, activities, and operations that create fire hazards and ignition risks within the site (NFPA, 2018)
- Managing all on-site fire prevention and suppression documentation, including information on local emergency services (e.g., local fire stations, hospitals, access roads, evacuation routes, and water sources; Figure 5), and checking that the information for each agency is posted clearly at the Proposed Action site and available to fire watch personnel and on-site workers
- Developing an emergency call-list before construction starts and verifying that tables of emergency contact agencies, their jurisdictions, and phone numbers are clearly posted at each Proposed Action site in case of fire
- Instructing other workers in the required fire prevention and suppression measures, including the use of fire suppression equipment and the protocols in the event of a fire
- Communicating current fire hazards and any changes in prevention and suppression methods on a daily basis
- Checking that all fire suppression equipment (e.g., fire extinguishers, dozers) is well-maintained and located in proper position within the construction site
- Checking that water tanks intended for fire suppression are full during operation hours and during fire watch periods
- Identifying the location of and access to the closest water sources each day to provide direction if fire suppression tanks need to be refilled during fire suppression (NFPA, 2017b)
- Exercising emergency authority to stop and prevent unsafe acts on the Proposed Action site (NFPA, 2018)
- Investigating accidents that have occurred within the incident area and recording the details in a log book (NFPA, 2018)

In the event of a fire, the Safety Officer will immediately contact LIFC dispatch and ODF KLD in Oregon or CFSU in California and subsequently any other pertinent fire suppression agencies. The Safety Officer will then initiate and command fire control activities on the site until relieved by fire suppression professionals. The expected agency or local fire personnel response time is 15 to 60 minutes depending on location of the incident relative to fire suppression departments and resources. All fire suppression activities by Proposed Action personnel will cease with the transfer of command to fire suppression professionals. The goal is to immediately and aggressively extinguish any fire that occurs during construction of the Proposed Action without sacrificing the safety of the workers. If the Safety Officer judges the equipment on-site incapable of suppressing the fire, the Safety Officer will initiate an evacuation of the Proposed Action site.

Local and regional weather patterns and antecedent moisture conditions can significantly impact fire hazards and fire behavior. Lightning is a leading cause of wildfire in Siskiyou County, and most of the larger fires are categorized as wind-driven fires (CalFire, 2016). Current and antecedent temperature and precipitation conditions directly influence the amount and condition of fuels. The Safety Officer will consult with ODF and CalFire foresters about anticipated weather conditions that may increase fire hazards and frequently update operations and fire response plans to changing environmental conditions. It is possible for favorable weather conditions to result in ODF foresters granting waivers of certain fire prevention and suppression requirements.

5.2 Agency Contacts

Before the LSO, the Renewal Corporation will supplement the FMP to include a phone tree with relevant agency contacts. Each Contractor will confer regularly with ODF and CalFire foresters to discuss Proposed Action progress and updates as they pertain to fire prevention and suppression and fire season designations.

In Oregon, the primary contact agencies are ODF KLD and ODF SWO. The ODF KLD Unit Forester and Stewardship Forester are the preferred contacts for discussion and modification of detailed, site-specific fire management plans, the identification of resources in the Proposed Action area, project management, and fire suppression. KLD will be the first contact agency in the event of a fire at the Oregon Proposed Action site. For Proposed Action activities taking place on BLM land, the primary BLM contact for coordination is the Field Manager of the BLM Lakeview District Klamath Falls field office.

In California, the primary contact agency is CFSU. The CFSU Prevention Specialist is the preferred contact for developing detailed, site-specific fire management plans, the identification of resources in the Proposed Action area, project management, and fire suppression. CFSU will be the first contact agency in the event of a fire at the California Proposed Action sites.

5.3 Fire Prevention and Suppression Measures and Equipment

The description of fire prevention and suppression measures and equipment is divided into those required by Oregon and California (and BLM where applicable) and those that are best practices and part of the NFPA standards.

5.3.1 Regulations and Requirements

The FMP includes fire prevention and response methods that are consistent with the regulations and requirements of the various local, county, state, and federal jurisdictions. Precautionary, pre-suppression, and suppression measures will be taken to increase public safety in the Proposed Action vicinity and comply with the fire season regulations and requirements set forth by ODF (Table 4-1) and CalFire (Table 4-2). Each Contractor will work closely with ODF KLD Unit Forester and Stewardship Forester and the CFSU Unit Forester and Prevention Specialist to develop effective communication links, evolve plans for fire prevention, suppression, and suppression actions in the event of a fire. ODF KLD will likely assign a Stewardship Forester to the Proposed Action for the duration of the Proposed Action (S. Cantrell, ODF KLD, *pers comm.*, 2017.08.16). Any Proposed Action activities occurring on BLM land will comply with the current IFPL

restrictions. The Field Manager of the Lakeview District Klamath Falls field office will coordinate with each Contractor for any Proposed Action activities on BLM land during IFPL restrictions.

Each Contractor will obtain the ODF PDM permit under Oregon statute ORS 477.625 to use heavy machinery during construction. Operation hours of tracked machinery are limited by the PDM permit during extreme fire danger, and these machines will accordingly suspend operations between the hours of 1 pm to 8 pm when required. Additional measures will be taken to keep machinery and the work area clear of excess flammable material. The PDM permit will be renewed annually, if needed, until Proposed Action completion. California does not have restrictions on the hours of operation of equipment and machinery.

Each Contractor will comply with all applicable laws pertaining to fire watch. ODF KLD prescribes fire watch duration based on FDL. Low fire danger requires a 1-hour fire watch, medium requires 2 hours, and high and extreme require 3 hours. ODF alerts all PDM permit holders of upcoming changes in FDL. A 1-hour fire watch is required on BLM lands when IFPL 1 or greater is in effect. California does not have fire watch requirements. Each Contractor will comply with all conditions of hot work permits.

Each Contractor will designate and train several members of their team to be able to serve as the Fire Watch. Fire Watch training, responsibilities, and actions will follow the regulations set forth in ORS 477.665 and OAR 629-043-0030 and the NFPA standards (NFPA, 2019a). The Fire Watch will be trained to recognize the inherent hazards of the work site and hot work operations, how to appropriately respond in the event of a fire, correctly use a fire extinguisher, be familiar with the Fire Watch decision tree (e.g., NFPA, 2019a), and contact fire suppression authorities. They will maintain safe conditions during any hot work operation and will have fire-extinguishing equipment readily available. They will be familiar with the construction site and facilities and the procedures for sounding an alarm in the event of a fire. The Fire Watch will watch for fires in all susceptible areas and try to extinguish them only when the fires are obviously within the capacity of the equipment available. If the Fire Watch determines that the fire is not within the capacity of the equipment, they will sound the alarm.

A primary feature of the FMP is preparedness for fire prevention and response in compliance with Oregon and California state regulations (Table 4-1 and Table 4-2, respectively). Construction vehicles and crews will be outfitted with the appropriate type and number of fire suppression tools, including but not limited to shovels, axes, and fire extinguishers. Required vehicles and machinery will be equipped with functional spark arresters and/or mufflers, where applicable, and spark arrester ports will be routinely cleaned. Gas powered saws, if operated at the Proposed Action site, will maintain the required fire suppression equipment as prescribed by Oregon and California. Water pumping systems conforming to the Oregon and California requirements for water volume, hose dimensions, and pumping rates will be provided at required locations on-site to suppress fires.

5.3.2 Standards and Best Practices

Each Contractor will conduct work using best management practices in addition to compliance with all federal, state, and local laws. Best practices follow the NFPA standards where available and employ industry-leading best practices. Each Contractor will oversee any sub-contractors, so they strictly adhere to both regulations and best practices.

Best practices that will be employed during the Proposed Action include the following:

- **Employee training.** Each Contractor will require the training of personnel with how to comply with the agency requirements and regulations and with best practices. The training will be required not only for Kiewit and RES employees, but also additional hired contractors and their crews. The Safety Officer will oversee training activities. Basic fire prevention training and education will be conducted during the initial employee safety brief. Additional training will be during bi-weekly safety training. An accurate and updated record of employee training will be in accordance with OSHA standards and requirements. The Safety Officer will be responsible for assigning and training persons to be responsible for 1) maintaining fire protection equipment and systems installed to prevent and/or control ignition of fires, 2) the control and accumulation of flammable or combustible materials and/or substances, and 3) advising personnel about site-specific flammable materials, hazardous processes or conditions, or other potential fire hazards (NFPA, 2019a).
- **Communication.** Each Contractor will establish effective communication lines to the various fire suppression agencies, particularly ODF KLD and CFSU. The Safety Officers will communicate these near-term measures to staff and subcontractors through new-hire orientation, various trainings, toolbox talks, and project meetings so that employees are familiar with fire prevention and control procedures. A communication system will be used for the duration of deconstruction and restoration activities to establish reliable communication lines between Proposed Action personnel and to agency and emergency contacts.
- **Equipment compatibility.** The Safety Officer and construction supervisors/superintendents will check that fire suppression equipment (e.g., hose connections and fittings) is fully compatible on both the Oregon and California portions of the Proposed Action and with local fire departments (NFPA, 2017b).
- **Good housekeeping.** Good housekeeping will be maintained in work areas to minimize the amount of Class A Materials (e.g., combustible vegetation, debris, rubbish, cloth, trash, and waste material). Class A materials must be kept away from accidental ignition sources, such as hot plates, heaters, welding operations, and be disposed of in appropriate receptacles. No burn fires will be allowed at the work site to dispose of Class A Materials. Materials susceptible to spontaneous ignition (such as oily rags) will be stored in a labeled disposal container. Access and egress routes will be kept clear and free of clutter, slip/trip/fall hazards, and other obstructions.
- **Flammable and combustible material.** Minimize the storage of Class B Materials (e.g., flammable and combustible liquids (oil, grease, paint), flammable gas and aerosols) and use alternative products that are less reactive or combustible, if available. Class B Materials storage areas will be well-ventilated and maintained clear of combustible vegetation and waste materials. Such storage areas will not be used for the storage of other combustible materials. Keep materials that are not non-compatible (chemically reactive) in separate flammable cabinets or different locations. Bulk fuel storage will be located at an approved area at the maintenance yard. Properly dispose of combustible waste in the appropriate receptacles, preferably metal containers with an airtight lid. Approved appliances and pumps will be used to dispense liquids from tanks, drums, or similar containers. Class B Materials will not be used, handled, or stored near or in emergency exits, stairs, or egress paths, nor will they be near welding, cutting, grinding, or spark-producing appliances or equipment. Safety Data Sheets will be reviewed and readily available for chemicals.

- **Spills, leaks, and clean-up.** Report, contain and isolate, and clean-up observed and suspected fluid and gas spills/leaks quickly and in accordance to the Safety Data Sheet of that material.
- **Emergency contacts.** An emergency call-list will be developed before construction. Emergency contacts will be posted by the Safety Officer and readily available in the event of a fire at the construction site. A temporary communication system will be setup to reliably contact emergency personnel.
- **Motorized vehicles and equipment.** Operation of internal combustion engines shall comply with PRC-4428 (Table 4-2). Equipment will be maintained to the working standards of the manufacturer, be kept clean of flammable material and debris, and inspected early in the shift prior to use. Persons operating equipment will be responsible for conducting the daily visual inspection of said equipment. The equipment group will perform routine maintenance on equipment to check that fire prevention measures (spark arrestor, shielding, smoke stacks, etc.) are clean and in proper working order. Inspection and maintenance tasks include ensuring that batteries, hydraulic lines, and fuel lines are in good condition. Equipment will be stored overnight in locations cleared of flammable material. Motorized construction equipment will be located such that the exhausts do not discharge against combustible materials. Vehicles will be restricted to the work site and will not be parked or operated in areas that contain vegetation. Vehicles will be shut down and allowed to cool before refueling. Gasoline powered construction equipment with catalytic converters will be equipped with shielding or other acceptable fire prevention features.
- **Electrical equipment and appliances.** Wiring and cords on electrical equipment and appliances will be inspected for damage (i.e. broken insulation, missing ground pin, signs of being crushed/bent, etc.). Appropriately rated fuses will be used for electrical equipment. Electrical equipment and appliances that have been approved by a Nationally Rated Testing Laboratory will be used. Extension cords will not be used as permanent wiring, nor will multiple extension cords together be connected together. Extension cords will not be pinched, shut, or crushed in doors, cabinets, or other items. Approval of portable heaters by the Safety Officer is required. Portable heaters will be turned off and unplugged before leaving for the day and when the unit is left unattended. Heaters will not be run near trash cans, curtains, or similar materials. Jackets, towels, or similar items will not be placed on heaters. Heaters will have tip-over protection and automatically shut off in the event it is tipped over. Space heaters, fans, coffee makers, and other similar appliances will be turned off when left unattended.
- **Hot work.** Permits will be obtained for hot-works and a fire watch will be completed under the permits.
- **Smoking.** During ODF fire season, smoking is not allowed while working or travelling in an “operation area” (ORS 477-001; Table 4-1). When not in fire season, smoking in active work areas of the Proposed Action area should be in designated areas that contain cigarette butt collection receptacles. Smoking will be prohibited in all other areas especially flammable and combustible liquid storage areas. Warning signs will be posted. No smoking will be permitted within 25 feet of flammable vegetation and 50 feet of flammable and combustible liquids. Smoking will be prohibited in all vehicles and equipment. E-cigarettes must be recycled and not mixed with regular trash as the lithium ion battery is a potential fire hazard and ignition source.
- **Firefighting equipment.** The NFPA recommends (NFPA, 2017b) wildfire plans conform to the local and regional regulations for firefighting equipment requirements (i.e., Table 4-1 and Table 4-2). In addition to complying with Oregon and California regulations, each Contractor will comply with these

additional best practices. Equipment capable of halting the spread of a fire will be kept on-site during construction-related activities while heavy machinery is being used and flammable materials are present. Any temporary water storage tanks will be inspected, tested, and maintained in accordance with NFPA 25 (NFPA, 2017a). If roads are needed to access water supplies, they will be designated as water access routes. Fire extinguishers, shovels and other firefighting equipment will be available at work sites and on construction equipment. 20-pound (or two 10-pound) fire extinguisher(s) and 5 gallons of water in firefighting apparatus (e.g., bladder bags), will be made available in areas of high risk for fire. Keep a fire extinguisher within 10 feet of fuel tanks and running gas powered equipment, especially in wooded areas and areas with tall/dry grass. (NFPA, 2017b). Only properly trained individuals shall perform maintenance and inspections on fire protection equipment and systems.

- **After hours.** To the extent workers remain on-site after work hours, aforementioned best practices will be followed while on the Proposed Action site regardless of whether work is ongoing. In the event of an ignition after hours, on-site personnel will immediately alert fire emergency contacts.

Supplementary information to the near-term measures to assist with fire prevention will be added as needed and maintained during construction activities as the Proposed Action develops.

5.3.3 Fire Management Preparation Checklist

Table 5-3. Fire management preparation checklist for the Contractors.

Action	Responsible Party	Completion Date / Frequency
Coordinate with state and federal fire resources (e.g. CalFire, ODF, USFS, BLM, local FDs) on fire management activities, fire risks and hazards, Proposed Action updates	Project Manager, Safety Officer	<ul style="list-style-type: none"> - Target before construction - Routinely during construction not in fire season - Minimum weekly during fire season
Work with ODF KLD and CFSU foresters to develop broad scale contingency plans for fire containment within their respective jurisdictions in the Proposed Action areas.	Project Manager, Safety Officer	<ul style="list-style-type: none"> - Target before construction - As needed during construction
Inform state foresters of any modifications to existing water resources due to dam removal activities, e.g., the drawdown of the reservoirs	Project Manager, Safety Officer	<ul style="list-style-type: none"> - Regularly as needed
Secure Permit for Power Driven Machinery from ODF	Safety Officer	<ul style="list-style-type: none"> - Target before construction - Renewed annually

Action	Responsible Party	Completion Date / Frequency
Communicate on wildland fire season updates and forecasts with ODF and CalFire contacts	Safety Officer	<ul style="list-style-type: none"> - Minimum weekly during fire season - Routinely during non-fire season construction
Verify that emergency contact information is up-to-date and visibly posted at active Proposed Action sites	Safety Officer	<ul style="list-style-type: none"> - Target before construction - Regularly as needed
Verify locations, check conditions, and maintenance of fire management equipment	Safety Officer, Supervisors/Superintendents	<ul style="list-style-type: none"> - Daily
Provide personnel with wildland fire training related to equipment, tools, and conditions	Safety Officer	<ul style="list-style-type: none"> - Target before construction - Bi-weekly refresher and as needed during construction
Communicate current and forecasted wildland fire season updates to personnel	Safety Officer, Supervisors/Superintendents	<ul style="list-style-type: none"> - Weekly as needed - Daily during fire season
Complete fire watch of required duration following applicable activities and during fire season	Fire Watch	<ul style="list-style-type: none"> - Daily
Check that vehicles working in and around fire potential areas are equipped with required fire management tools	Supervisors/Superintendents	<ul style="list-style-type: none"> - Daily
See that Proposed Action sites and personnel comply with best practices described herein, including good housekeeping, treatment of flammable material, and equipment requirements	Safety Officer, Supervisors/Superintendents	<ul style="list-style-type: none"> - Daily

6. LONG-TERM FIRE MANAGEMENT MEASURES

6.1 Term

The long-term fire management measures that are the Renewal Corporation's obligations will begin on LSO and end when the License Surrender is effective. These long-term measures, specifically the fire suppression and detection equipment, will provide fire management benefits long after License Surrender is

effective through the cooperative agreements with fire agency successors. The Renewal Corporation will undertake to reach such cooperative agreements in the first quarter of 2022, and it will purchase and install the various long-term measures as specified in such agreements.

6.2 Objectives and Overview

The objective of the long-term fire management measures and supporting analysis is to assure that the Proposed Action, post-dam removal, will not cause a net diminution in firefighting resources in the Basin or increase the fire ignition risks that exist prior to the Proposed Action.

The long-term measures were developed using analytical results from the Reax report (Appendix A) and in consultation with CalFire and ODF, among others, in order to better understand the existing needs and opportunities to improve fire prevention and suppression capabilities of the respective agencies. The contacts consulted are described in Section 8. Several common themes emerged from discussions with fire agency personnel as summarized below and were used to guide development of the long-term measures:

- Early detection of fires is critical
- Water sources and access are important
- Local community fire preparedness is vital for protecting residents and infrastructure
- Each fire is unique, so tactics and resources used for suppression are correspondingly unique
- Environmental conditions (e.g., topography, weather, fuel availability, antecedent moisture, ignition type) vary widely between fires
- Resources available for initial attack or a sustained fire suppression effort vary widely depending on locality, time of year, and the distribution of resources to other fires; hence, a diversity of measures are required to address many components and stages of fire management including fire prevention and preparedness, monitoring and detection, and initial attack and suppression.

In the sections below, we first describe the anticipated conditions following dam removal. Then, we propose new and enhanced fire management measures and strategies and discuss the motivation and logistics for each. Finally, we compare existing fire risk with long-term fire risk as a result of the Proposed Action and the proposed management resources in the FMP and explain how the FMP meets its objectives.

6.3 Conditions after Dam Removal

Some environmental conditions and fire management resources will change in the ASE area as a result of the Proposed Action. When the fire management measures described in detail in Section 6.4 are implemented, the conditions related to wildfire risk will not worsen, and the amount of fire suppression resources will increase. The Renewal Corporation will implement the installation of early detection cameras in the ASE area that will significantly reduce wildfire detection and initial attack arrival times. New water access points (i.e., dry hydrants and boat launches) for ground crews will be developed and dip tanks for aerial crews will be provided to supply a diverse and flexible suite of water access fire suppression options. The two-hydrant system that services the Copco No. 2 powerhouse area will no longer be used. Iron Gate Reservoir, Copco Lake, and J.C. Boyle Reservoir will no longer be available as water sources for aerial fire suppression crews. In place of the reservoirs will be a free-flowing Klamath River. The reservoirs serve as a broad fuel break that can prevent the spread of wildfires. Post-removal, the reservoir footprints will be revegetated, so what was once covered with water will be replaced with potential fuel sources. Potential

post-removal vegetation succession is described in Appendix A and was estimated from existing vegetation types and historical imagery.

The restored free-flowing Klamath River will be a water source and a fuel break, albeit a narrower one. The Renewal Corporation identified 41 potential post-removal ARAPs in the reservoir footprints using high resolution bathymetry and historical topography, photos, and imagery. The majority of the reservoir sediment is silt- and clay-sized sediment (BOR, 2011), which will be easy for the Klamath River to erode and transport. As such, existing deep pools in the mainstem river will not experience infilling from mobilized reservoir sediments and will continue to serve as a water source for aerial firefighting crews. There will be ample year-round flow in the Klamath River post-removal. The minimum prescribed post-removal Klamath stream flows from the 2019 National Marine Fisheries Service Biological Opinion (NMFS, 2019) for July and August are 900 cfs and will be even greater the rest of the year. In addition, the dry hydrants will provide water sources, supplied by tributary flow, along major roads. The portable dip tanks will provide mobile water sources that can be deployed in remote locations where water access is currently unavailable.

Power generating facilities, transformers, circuit breakers, and lengths of transmission and distribution lines will be removed at each dam site as part of the Proposed Action as outlined in the DDP (Renewal Corporation, 2020). More than 15 miles of transmission and distribution lines and 231 power poles will be removed as part of the Proposed Action (Table 6-1). Most of the Copco line that will be removed is located in a CPUC Tier 2 Elevated Fire Threat area (Figure 3). The area may be reclassified as no fire threat as a result of the Proposed Action.

Table 6-1. Miles of transmission and distribution lines removed by the Proposed Action (Renewal Corporation Technical Representatives, 2018, updated 2021).

Project site	Miles of 69-kV line removed	Number of power poles removed
J.C. Boyle	3.5	68
Copco No. 1 & 2	11.2	131
Iron Gate	0.5	14
Total	15.2	231

6.4 Post-Removal Management Measures

This section describes the post-removal management measures (Figure 9) that the Renewal Corporation will make available to aid with fire prevention and suppression efforts in the Basin following the removal of the dams and demonstrates that post-dam removal firefighting resources are similar to current conditions. The measures include technologies, facilities, and equipment that are both new to the Basin and improvements and upgrades to existing resources in the Basin. The Renewal Corporation will provide the proposed management measures described in the following subsections.




Figure 9. Proposed post-removal long-term fire management measures.

6.4.1 Monitored Detection System (MDS)

As supported by the agencies, the Renewal Corporation will implement the installation of new early detection MDS camera technology to improve early fire detection in the Basin, as described below. With high definition cameras, GIS integration, and the ability to triangulate fires, the MDS is a powerful tool for rapidly detecting and locating wildfires (see Section 3.2.1 for description). The MDS can potentially save minutes to hours of time from ignition to the arrival of initial attack resources relative to detections from 911 calls. ODF SWO has had a functional MDS since 2012, and ODF KLD installed one in 2019. Since installation of the ODF SWO system, their number of first fire detections has increased from two in 2012 (when there were not dedicated staff observers) to 24, 69, and 27 first detections when staffed in 2017, 2018, and 2019, respectively. For context, an average number of 14 initial detections from ODF SWO staffed fire lookouts were recorded from 2003 to 2011 with a maximum value of 24 initial detections in 2003. The system also allows for remote monitoring of dozens of fires simultaneously. The MDS technology is scalable, such that additional cameras can be added to a network with all data routed to a single detection center. In San Diego County, firefighters using a network of fire detection cameras were able to pinpoint and confirm the location of the Lilac Fire within 31 seconds. This rapid detection allowed the blaze to be contained before it could grow into a larger

devastating fire, for which the conditions were favorable. This result prompted Neal Driscoll, Professor at UC San Diego that has been deploying fire detection cameras in Southern California, to say “early detection is the whole game.”




Figure 10. Viewshed analysis at 500 Ft above ground surface for contemplated MDS camera locations with green, yellow, and orange indicating visibility by one, two, and three observers, respectively. From Reax report (Appendix A).

As supported by the agencies, the Renewal Corporation will implement the installation of MDS cameras, power sources, and data transmitters at the contemplated locations shown in Figure 9 and Figure 10. The contemplated locations include several existing fire lookouts (Parker Mountain, OR, and Paradise Craggy, CA) and the development of two new sites (Mt. Ashland, OR, and Eagle Rock, CA). The contemplated Mt. Ashland and Eagle Rock sites are both located in the Klamath National Forest, and the Parker Mountain and Paradise Craggy locations are currently operated as fire lookouts by ODF and CalFire, respectively.

The viewshed analysis of the contemplated MDS camera locations (Figure 10) shows that nearly the entire ASE area, and much of the surrounding area, is covered by at least one observer. Importantly, there is a large amount of the ASE area, including locations near the Klamath River, that is covered by multiple cameras to enable triangulation of fires. Coverage of the full ASE area is not currently possible with just the Soda Mountain and Chase Mountain cameras, so these additions would be a major improvement to rapid detection and suppression in the area.

ODF SWO and KLD currently use MDS technology with great results, and the additional cameras improve their coverage and improve the existing coverage by adding an additional observer for triangulation and monitoring. As specified in cooperative agreements, the Parker Mountain and Eagle Rock locations will be integrated into the ODF KLD network of cameras with the existing Chase Mountain camera and monitored in their detection center. The Mt. Ashland and Paradise Craggy cameras will be integrated into the ODF SWO network of cameras with the existing Soda Mountain camera and monitored in their detection center.

The Renewal Corporation will address costs of the MDS technology in cooperative agreements. The Renewal Corporation will cover costs of any hardware (instruments, microwave communication system, computer monitoring station) and any associated setup for the contemplated camera locations at Paradise Craggy and Eagle Rock; will cover the cost of the instruments for the contemplated ODF KLD Parker Mountain and the ODF SWO Mt. Ashland sites; and will cover the costs of camera and tower updates at the ODF SWO Soda Mountain site. The Renewal Corporation will cover the costs of the EVS ForestWatch® software one-time site license for cameras on Parker Mountain, Mt. Ashland, Paradise Craggy, and Eagle Rock. The Renewal Corporation will cover costs for annual EVS software licenses and periodic camera replacement for the contemplated ODF KLD Parker Mountain and Eagle Rock sites and the ODF SWO Mt. Ashland and Paradise Craggy sites for a period to be agreed upon between ODF and the Renewal Corporation. The Renewal Corporation will collaborate with CalFire, ODF, and USFS (for Eagle Rock and Mt. Ashland contemplated locations) prior to the start of construction to implement this measure. The cooperative agreements may specify amortization funds. Development of MDS cameras at certain contemplated sites will involve approval by landowners.

6.4.2 Chipper

As specified in a cooperative agreement with FSCSC, the Renewal Corporation will pay for a 9-inch chipper and dump bed trailer combo and a base model truck to haul it that will be owned and maintained by FSCSC to provide frequent and consistent assistance with defensible space to the local community. Defensible space, which is a legal requirement in California and Oregon and a top priority for many groups in Siskiyou County (Siskiyou County, 2019), can significantly reduce the risk of structure fires. CalFire urges private landowners to reduce fuels around their structures (CalFire, 2019), and the chipper would aid in that effort. FSCSC would administer the use of the chipper and be responsible for maintenance and for scheduling and staffing chipping events.

6.4.3 Copco Lake Hydrant System

The water supply for the existing gravity fed hydrant system at Copco Lake (Figure 13) is maintained by storage tank fed by a spring on Snackenburg Creek and supplemented in the summer by a groundwater well operated by the Copco Lake Mutual Water Company. This system is not expected to be affected by the drawdown of the reservoirs or the removal of the dams because the well is believed to tap subsurface flow from Snackenburg Creek. The Renewal Corporation does not propose any improvement in this system. If directed by CalFire, the Renewal Corporation will ensure that the loss of the reservoirs does not affect the system's functionality through License Surrender.

6.4.4 Dry Hydrants

Pursuant to a cooperative agreement with CalFire and ODF, the Renewal Corporation will construct five permanent dry hydrants located at or near road crossings of large tributaries to provide additional water sources. The Renewal Corporation has designed these hydrants and includes the specifications in the DDP.

Dry hydrants provide a simple and reliable water supply for ground-based firefighting crews to fill fire engines and water tenders. Dry hydrants are passive, unpressurized water supply systems with a screened intake placed in the channel above the channel bed in a location of satisfactory water depth (during dry conditions), flow rate, and channel stability. Dry hydrants have an above-ground fire hose connection to which truck-mounted pumps can be connected. Dry hydrants are commonly used as water supply for fighting fires in rural areas. The Renewal Corporation will design and construct five permanent dry hydrants located at or near road crossings of large tributaries to provide additional water sources (Figure 9; Table 6-2). This measure will be implemented as part of the road and bridge improvements associated with construction and dam removal. Long-term maintenance of the hydrants will be the responsibility of CalFire and ODF.

The addition of dry hydrants will add water access to ground-crews that is currently not available around the reservoirs. The dry hydrant network (as an addition to the boat launches and existing hydrant system) will reduce fire suppression responses times and allow for more aggressive responses as tanker refill and rotation times are reduced. The dry hydrants will be placed at or near bridge crossings over larger tributaries with perennial flow with minimum flow rates of several cfs or greater. The Iron Gate dry hydrants will be along Iron Gate Lake / Copco Road at Jenny and Fall creeks (Figure 12). The Copco Lake hydrants will be along Copco Road at Beaver Creek and along Ager-Beswick Road at Deer Creek (Figure 13). The J.C. Boyle dry hydrant will be located at the Pioneer Park West boat launch to provide more rapid drafting at that location than the boat launch (Figure 14). For convenient, dependable, permanent, and rapid access, the hose connections will be placed, where feasible, on the bridges that are scheduled to be built across each tributary as part of Proposed Action construction measures. Bridges and crossings are desirable given the increased certainty of access to water post-removal and the ability to utilize the structure for mounting the dry hydrant pipe and hose connection.

As specified in a cooperative agreement with CalFire and ODF, the Renewal Corporation will complete the design, permitting, and construction of the dry hydrants in compliance with NFPA standards (NFPA, 2017b) and will continue to consult with agency fire personnel during the design phase. Unless advised otherwise by fire agencies, the location, design, and materials will follow the standards of NFPA 1142 (NFPA, 2017b). The dry hydrants will be designed to provide a minimum flow of 1000 gpm (2.2 cfs) (NFPA, 2017b), which is a fraction of the low flow discharges of the perennial tributaries selected for the hydrants. The screened intakes will be placed in portions of each tributary with the required 1 Ft of flow depth below and 2 Ft above (NFPA, 2017b). The intake locations will be placed upstream of the crossings to reduce the vertical height that water must be raised during drafting (lift) to less than 10 Ft, unless an alternate maximum lift value is specified by firefighting groups. The hose connection fitting provided at the dry hydrant must be compatible with the local and agency pump equipment and conform to the NFPA 1963 standards (NFPA, 2019b).

6.4.5 Boat Launches

The Renewal Corporation will construct or improve three boat launches to provide Klamath River water access following dam removal. Boat launches provide simple and reliable water access for ground-based firefighting crews to fill fire engines and water tenders. Most of the existing boat launches around the reservoirs (Figure 6) will no longer function once water levels are lowered during drawdown and dam removal, although Fall Creek will retain its current functionality.

The Renewal Corporation will construct boat launches near J.C. Boyle, Copco, and Iron Gate (Figure 9; Table 6-2). Above J.C. Boyle Dam, a new boat launch at Pioneer Park West will replace the existing gravel boat launch at Pioneer Park East (Figure 14). Below Copco 2 Dam, a new boat launch will be constructed at Fall Creek (Figure 12). This new launch will replace the existing boat launch at Fall Creek, which has an unimproved surface too steep and narrow to be suitable for water tenders or fire engines. And immediately below Iron Gate Dam, the existing boat launch on river-right will be improved for firefighting purposes (Figure 12).

States of Oregon and California will support these new boat launches as successor landowners. The new boat launches will have concrete ramps and access roads with dimensions designed to comply with the NFPA standards for width, grade, and turning radius (NFPA, 2017b) and using materials that can support the weight of water tenders and fire engines.

Table 6-2. Post-removal ground access points as shown in Figure 9.

Proposed Action site ¹	Type	Description
Keno Dam	Boat launch	Existing
J.C. Boyle – Pioneer Park West	Dry hydrant	Proposed
J.C. Boyle - Pioneer Park West	Boat launch	Proposed
Copco – Deer Creek	Dry hydrant	Proposed
Copco – Beaver Creek	Dry hydrant	Proposed
Iron Gate – Fall Creek	Boat launch	Improved
Iron Gate - Fall Creek	Dry hydrant	Proposed
Iron Gate - Jenny Creek	Dry hydrant	Proposed
Iron Gate Dam / Hatchery	Boat launch	Improved
KRCE Campground	Boat launch	Existing
Klamathon Bridge	Boat launch	Existing

¹ Listed from upstream to downstream.

6.4.6 Aerial River Access Points (ARAPs)

As specified in a cooperative agreement with CalFire and ODF, the Renewal Corporation will implement the identification and maintenance, through the surrender term, of aerial river access points (ARAPs) in the former reservoirs (two per reservoir) that meet specific suitability performance criteria to be used by Type 1 helicopters with snorkels. Strategic use of the post-dam removal Klamath River corridor as a water supply for aerial fire suppression is an important part of countering the loss of the reservoirs. Viable water sources

need to be perennial and have sufficient flow and accessibility (NFPA, 2017b). Minimum flows in the river will be sufficient to provide adequate water supply even under the heaviest drafting withdrawals. Some reaches of the free-flowing Klamath River are currently used for bucket and longline drafting in the ASE area, and additional locations suitable for drafting ARAPs are expected to form naturally in the reservoir footprints post-removal.

The Renewal Corporation has analyzed the expected changes in the Klamath River after dam removal and anticipate that there will be at least two ARAPs which will form naturally in each former reservoir and meet the specific suitability performance criteria to be used by Type 1 helicopters with snorkels (Figure 11). ARAPs are expected to have wetted widths and centerline depths greater than 150 Ft and 3 Ft, respectively, providing an adequate amount of water to target and draft using a snorkel device from the helicopter. A safety clearance diameter of 400 Ft is required to reduce the hazards of helicopter drafting due to rotor wash, obstacles, and vegetation that could interact with the rotors. An area satisfying the safety clearance diameter criteria will need to be devoid of woody vegetation taller than 18 inches and lack any other obstacles posing a potential hazard to helicopter rotors (*cf.* USFS & OAS, 2015).




Figure 11. Conceptual cross-section illustrating the performance criteria/minimum requirements for aerial river access points.

The locations of more than 40 potential post-removal ARAPs were estimated within the reservoirs from historical air photos, pre-dam topographic data, and high-resolution reservoir bathymetry (Figure 12, Figure 13, and Figure 14). Analysis of the currently free-flowing sections of the Klamath River in the ASE area yielded nearly 100 locations that met the width and depth criteria, and channel dimensions in the reservoir footprints are expected to be comparable. The prevalent exposed bedrock in the reservoirs will effectively maintain channel dimensions in ARAP locations, and significant filling of new or existing ARAPs with mobilized reservoir sediments is not anticipated in the Project reach given the fine-grained composition of the reservoir sediments (Renewal Corporation Technical Representatives, 2018; Appendix H).

Vegetation management of riparian areas may be needed for ARAPs to meet the safety clearance performance criterion. Wetland vegetation will generally be appropriate for meeting the safety clearance criterion because they generally lack woody species and do not grow as tall as typical riparian vegetation. There are areas designated for restoration and emergent wetlands creation, as described in the Reservoir Area Management Plan of the Definite Decommissioning Plan (Renewal Corporation, 2020) and in Figure 12, Figure 13, and Figure 14. Vegetation management will not interfere with the objectives of salmonid recovery because the areas are designed emergent wetlands. Any annual maintenance will be targeting

treatment of woody, non-wetland species that have grown up around the ARAP and will thereby improve wetland health and function.

The Renewal Corporation will identify two naturally-occurring ARAPs per reservoir to be maintained through the term of the FMP to meet Type 1 helicopter drafting requirements. The specific location of each ARAP will be selected with coordination from CalFire and ODF. The number of ARAPs per reservoir for maintenance was based on recommendations from ODF SWO. The ARAPs will be inspected annually to assess their ability to meet performance criteria for depth, width, and safety clearance. Following inspection, the vegetation surrounding the ARAPs will be managed, if necessary, to meet the safety clearance criterion and to remove all woody species exceeding 18 inches in height. The Renewal Corporation will work with CalFire and ODF to implement this measure.




Figure 12. Potential post-removal resources in footprint of Iron Gate Reservoir.




Figure 13. Potential post-removal resources in footprint of Copco Lake.




Figure 14. Potential post-removal resources in footprint of J.C. Boyle Reservoir.

6.4.7 Dip Tanks

As specified in a cooperative agreement with CalFire, the Renewal Corporation will cover the costs of seven portable dip tanks of varying sizes to provide CalFire diverse and flexible additional water sources for aerial drafting efforts. Dip tanks are a proven method for providing reliable alternative water sources for helicopter drafting. Even though there will be ample water supply for drafting in the free-flowing Klamath River, dip tanks can provide yet another method of drafting to complement the boat launches, hydrants, and ARAPs as water sources in the Basin. Portable dip tanks vary in design and widely in size (i.e., 72 gallons to 6000 gallons), so they provide the flexibility to customize to fit the needs (e.g., location, volume, dip bucket size) of local and state fire agencies. Portable, self-supporting (i.e., no frame required) tanks can be stored, easily transported and erected, and filled rapidly, so they can be deployed to varying locations as needed. Portable, self-supporting tanks can vary widely in size and ease of setup, with larger tanks requiring a thicker and a greater amount of fabric, which increases the weight and reduces the ease of transport and setup. Helicopter sling tanks are smaller, portable, soft-sided tanks that can be air-lifted by helicopters and placed

in remote locations needing additional water supply. Portable tanks must be paired with a pump system to be refilled, and therefore must be placed in locations with viable water supply.

As specified in a cooperative agreement with CalFire, the Renewal Corporation will provide dip tanks to CalFire to diversify their water supplies for fighting fires in the ASE area. All tanks, hoses, and pump systems will be NFPA 1142 compliant (NFPA, 2017b) and provide the water volume, refill rates, and hose compatibility needed by fire personnel. Tanks will be sized for compatibility and safety with the bucket sizes of CalFire and ODF helicopters. Ownership and maintenance of tanks will be with CalFire.

As specified in a cooperative agreement with CalFire, the Renewal Corporation will pay for seven dip tanks, including five portable, self-supporting tanks (5000 – 6000 gallons each) and two portable helicopter sling tanks (350 gallons each) with hoses and pumps for refilling. These portable tanks can be stored in fire department buildings (e.g., CFSU headquarters in Yreka, Hornbrook FD, or Copco Lake FD) or in pre-determined locations either along existing roads in the ASE area and can always be transported elsewhere if needed. There are several strategic locations these tanks could be staged in locked housing. Camp Creek and Jenny Creek both have 150+ Ft wide gravel lots near the locations where dry hydrants will be installed, so they provide good helicopter clearance and reliable access to water. These locations could provide a higher elevation drafting alternative to refilling in the Klamath River. They can be placed in open areas that meet the drafting criteria for helicopters. Water pumps and hoses will accompany the portable tanks for on-site pumping from ponds, streams, and hydrants. The cooperative agreement may address amortization of this equipment.

6.5 Evaluation of Post-Removal Fire Risk

The Reax analysis demonstrates (Appendix A), that the proposed long-term fire management measures meet the objectives that the Proposed Action, post-construction, will not increase the risk of fire ignitions that currently exist or cause a net diminution in firefighting resources in the Basin. The Renewal Corporation believes that the proposed long-term measures meet the objectives and improve firefighting resource availability and decrease ignition risk in the Basin relative to the *status quo*. The Renewal Corporation's conclusion is supported by the numerical modeling and quantitative analysis performed by Reax (Appendix A).

Reax analyzed the effects of the Proposed Action on wildfire in the Basin with numerical modeling, where stochastic ignition locations and weather conditions would initiate wildfires that burn on the landscape and fuels of the Basin (see Appendix A for a detailed description). This Monte Carlo wildfire modeling generates a burn probability for each location on the landscape. Burn probability is a quantitative measure of the likelihood that a point on the landscape will be impacted by a fire during a given period of time. The Reax wildfire modeling yields an analogous measure, whereby burn probability is the number of times a point on the landscape burned in model runs divided by the total number of model runs. Reax simulated both existing “pre-restoration” conditions with the reservoirs present and a “post-restoration” scenario where the reservoirs have been replaced with vegetation (see Section 6.5.1). In these first simulations, initial attack and fire suppression were disabled. In a second set of simulations, Reax enabled modeling of initial attack and fire suppression to investigate the effects of the early detection measures proposed as part of the Proposed Action, and their effect on reducing initial attack arrival time, on burn probability (see Section 6.5.2).

6.5.1 Burn Probability and Risk of Ignition

The Reax modeling demonstrates quantitatively that the Proposed Action and the replacement of the reservoirs with vegetation will have a negligible effect on burn probability in the ASE area (Table 6-3, Figure 15) and that mean burn probability should decrease as a result of the post-removal fire management measures (Section 6.5.2). In the simulations that do not consider the management measures, the mean burn probability in the ASE area for “pre-restoration” and an average “post-restoration” are 7.73E-06 and 7.75E-06, respectively, which amounts of an average percent change of 0.29% that varies from 0.00% to 0.90% depending on fuel type (Table 6-3). This percent change is negligible and within the range of variability from the stochastic/random nature of the analysis. The environmental conditions related to fire ignition (e.g. lightning, high temperatures, high wind speeds, and drought conditions) will be unaffected by the Proposed Action, so they do not change burn probability or ignition risk as a result of the Proposed Action. There is an increased risk of lightning striking fuel sources rather than water with the loss of the reservoirs, and this risk is captured in the Reax analysis (Appendix A). However, lightning tends to strike the highest objects in the landscape, so the risk of strikes occurring in the “post-restoration” Klamath River valley bottom are much lower (Appendix A). The variability in simulated burn probability as a result of stochasticity of wildfire ignition locations in the ASE area amounts to comparable magnitude of local changes in burn probability to those associated with the loss of the reservoirs (Figure 15). As a result, the Reax analysis demonstrates that burn probability in the ASE area is relatively unaffected by the replacement of the reservoirs with various fuel sources.

Table 6-3. Change in modeled burn probability within ASE area from pre-restoration to post-restoration fuels.

Fuel	Mean burn probability	Percent change ¹
Pre-restoration	7.73E-06	
Post-restoration (short grass)	7.80E-06	0.90%
Post-restoration (grass / shrub)	7.72E-06	0.00%
Post-restoration (timber)	7.73E-06	0.01%

¹ Percent change calculated relative to pre-restoration burn probability.

The risk of ignition for both wildfires and structure fires in the Basin could decrease as a result of the Proposed Action, even without the reductions in burn probability from the management measures. More than 15 miles of power transmission and distribution lines will be removed as part of the Proposed Action. Overhead utilities are an ignition source that has started large fires in California before, and they account for hundreds of ignitions per year in PacifiCorp’s Northern California service territory (PacifiCorp, 2019). The removal of these lines could cause the CPUC to declassify the current “Elevated Fire Threat” designation for the Copco Lake area (Figure 3) and replace it with a “No Threat” designation.




Figure 15. Difference between modeled pre- and post-restoration burn probabilities. Red/orange and blue/green indicate increases and decreases in burn probability, respectively. From Reax report (Appendix A).

The addition of the chipper and dump bed trailer provided to FSCSC should decrease the risk of ignitions unintentionally caused by burning debris piles and thereby decrease the risk of structure fires in the Basin. Some local residents currently comply with defensible space regulations by burning slash and debris from their property (debris burning), and these debris burning piles occasionally get out of control. Debris burning accounted for 5.05% of all large (grass fires > 100 ac, timber fires > 5 ac) fire ignitions in Northern California from 2007 to 2017 and 6.20% (15 of 240 total ignitions) of the ignitions in PacifiCorp's Northern California service territory over the same period (PacifiCorp, 2019). On CalFire-protected lands in Siskiyou County from 1919 to 2016, debris burning has accounted for an average of 800 to 1600 acres burned per year and 26 to 43 fires per year in Siskiyou County (Keeley and Syphard, 2018). The chips produced by the chipper will be hauled away in the dump trailer to safe and approved locations, and thereby remove the fuel source from each property. A chipper is not currently available to residents, so the chipper at FSCSC will allow more residences to meet the defensible space requirements.

6.5.2 Firefighting Capabilities

The Reax analysis quantitatively demonstrates that by providing new early detection and initial attack capabilities, which can help contain small fires before they grow into large fires, the Renewal Corporation has offset the loss of the reservoirs as a water source and fuel break. These new capabilities are not currently available in the Basin, so they represent an improvement over the existing resources. Early detection and rapid, efficient deployment of initial attack resources are critical for containing fires in the Basin before they become large, dangerous events. The fuel types, dry and hot conditions, and high winds in the ASE area are conducive to the rapid spread of wildfires, so lowering response time with improved early detection and more capable initial attack resources is critically important. In addition, the much-improved viewshed coverage provided by the new MDS cameras will dramatically improve the ability to monitor on-going fires and efficiently direct and deploy aerial and ground resources.

The viewshed analysis in the Reax report (Appendix A) demonstrates that the ability to detect and triangulate fires will improve dramatically to nearly full coverage of the 568.9 mi² ASE area with the additional proposed MDS cameras (Figure 16, Table 6-4). The new cameras increase coverage dramatically in the southern portion of the ASE area and the high fire danger area of the Klamath Mountains west of the ASE area (Figure 16). With the new cameras, 93% of the ASE area is visible at a height of 500 Ft above the ground surface (i.e., as an indication of detecting the smoke plume as it rises) as opposed to only 66% with the existing resources (Table 6-4). Importantly, the new cameras increase the percentage of the ASE area over which fire location can be triangulated by nearly 40% (Table 6-4) with much of the increase along the Klamath River (Figure 16). Given the importance for locating which side of the river a fire is burning for effective deployment of initial attack resources, the new triangulation capabilities are tremendously valuable. Nearly the entire basin will have fire detection coverage as a result of the new MDS cameras, and this improvement will translate into more rapid and efficient deployment of fire suppression resources and initial attack success.




Figure 16. Comparison of pre- (white) and post-Proposed Action viewsheds at 500 Ft above ground level with additional coverage (pink) by one observer (left) and multiple observers (right). From Reax report (Appendix A).

The MDS system has proven effective at improving the accuracy and frequency of rapid fire detection. With the proposed set of cameras, the agencies will be able to quickly locate fires anywhere in the ASE area and efficiently deploy initial attack resources. This technology is an invaluable addition to the Basin's fire suppression capabilities because it will shorten by minutes or even hours the initial attack response time from fire ignition to arrival of initial attack resources compared to the current strategies. Currently, fire suppression personnel in much of the ASE area rely on fielding 911 calls, which may be delayed getting into cellular range and may not have specific information on fire location, and then they must search for the fire location in the field. At fire growth and spread rates as fast as 1.25 mph in the area (Siskiyou County, 2019; Stephens et al., 2008), the time savings provided by Proposed Action measures are dramatic. Given that CFSU deals with hundreds of ignitions each year, improvement of initial attack effectiveness by any amount is very significant (*cf.* Fried et al., 2006). In addition, the MDS cameras will increase the speed at which 911-reported fires are accurately located.

Table 6-4. Percentage of ASE area (568.9 mi²) covered from Reax viewshed analysis

	Pre-restoration viewshed			Post-restoration viewshed		
Target height	0 feet	100 feet	500 feet	0 feet	100 feet	500 feet
1 observer	33.4%	45.3%	56.7%	45.9%	51.0%	45.6%
2 observer	1.90%	5.58%	9.63%	8.18%	21.2%	39.8%
3 observer	0%	0%	0%	0.58%	2.44%	7.31%
Total coverage:	35.3%	50.9%	66.3%	54.7%	74.6%	92.7%

To quantify the effect of the early detection and of the proposed fire suppression measures in this plan on reducing burn probability in the ASE area, Reax conducted additional modeling simulations where they enabled initial attack and fire suppression and analyzed varying initial attack arrival times, t_a (Appendix A). As expected, their results show that mean burn probability in the ASE area decreases with decreasing arrival time (Table 6-5, Figure 17). The mean incremental percent change in mean burn probability per 5 minute decrease in t_a is -20.1%, an absolute difference which is nearly two orders of magnitude greater than the average percent change increase (0.29%) in mean burn probability from “pre-restoration” to “post-restoration” conditions (Table 6-5). This result indicates that the even modest improvements in early detection and initial attack arrival time should more than offset the effect of the loss of the reservoirs on mean burn probability in the ASE area. Given that the MDS cameras and other measures should easily offer more than a 5-minute average improvement in initial attack response time, the improvements in burn probability far outweigh the consequences of replacing the reservoirs with vegetation.

The MDS cameras not only assist with more rapid detection of fires compared to, for example, 911 calls, but also in pinpointing fire locations from 911 calls for effective deployment of initial attack resources.

As a result, decreases in initial attack arrival time by more than 5 minutes are likely and should result in large decreases in mean burn probability in the ASE area compared to existing conditions more than offset the impacts of the loss of the reservoirs on mean burn probability.

Table 6-5. Results for mean burn probability from Reax's wildfire spread modeling

Scenario	Mean burn probability	Percent change in burn probability ¹	Incremental percent change in burn probability ²
Existing "pre-restoration" conditions	7.73E-06		
No reservoirs, average "post-restoration"	7.75E-06	0.29	
No reservoirs; t_a = 30 mins	1.16E-06		
No reservoirs; t_a = 25 mins	1.08E-06	-6.92%	-6.92%
No reservoirs; t_a = 20 mins	7.69E-07	-33.65%	-28.72%
No reservoirs; t_a = 15 mins	7.03E-07	-39.39%	-8.65%
No reservoirs; t_a = 10 mins	3.76E-07	-67.54%	-46.44%
No reservoirs; t_a = 5 mins	3.40E-07	-70.69%	-9.71%

¹ Percent change in mean burn probability is calculated relative to existing "pre-restoration" conditions. For the initial attack arrival time (t_a) scenarios, percent change is calculated relative to the "No reservoirs; t_a = 30 mins" scenario.

² The percent changes are calculated as the change in mean burn probability per 5 minute incremental improvement in arrival time.

The MDS system will add benefit beyond the ASE area to other areas under CFSU and ODF protection. CFSU and ODF protect the extensive mountainous region west of I-5, an area which has a "very high" fire hazard (Figure 2) and an Elevated CPUC fire threat tier (Figure 3). The Paradise Craggy and Mt. Ashland cameras will add important fire detection coverage in this mountainous and forested region, and the Mt. Ashland camera will improve detection around the city of Ashland, Oregon (Figure 16).




Figure 17. Modeled mean burn probability in ASE area vs. time of initial attack after fire ignition. From Reax report (Appendix A).

Initial attack is often spearheaded by ground crews building containment fire lines, and the ability of ground crews to fight fires in the Basin will improve as a result of the long-term measures. The dry hydrants are new resources that will provide new access to water sources along the major roads in the ASE area for ground-crews and reduce refilling travel times for tenders and fire engines by up to 30 to 60 minutes per turn, depending on fire location, compared to existing boat launches and access points. The Deer Creek dry hydrant (Figure 13) is located in the middle of a relatively dense collection of homes along Ager-Beswick Road to the east and Patricia Avenue to the west and will reduce round-trip travel time between refills by 20 to 30 minutes for fighting structure fires on this southern side of Copco Lake. There will be 11 combined boat launches and dry hydrants post-removal. The two new boat launches, which will be specifically designed to accommodate water tenders and fire engines, will be constructed to replace existing gravel-surfaced boat launches that are not suitable for this equipment. The dry hydrants and new boat launches will be an improvement over existing boat launches because they are specifically designed for firefighting ground crews. The gravity fed hydrant system at Copco Lake will continue to function (Section 6.4.3), so these capabilities will be maintained post-removal. The area currently serviced by Copco No. 2 powerhouse hydrant system will be serviced by the Iron Gate Fall Creek boat launch, which is located only 1500 ft away. In addition, initial attack by ground crews will be much more efficient given the improved ability to monitor fire locations in real-time provided by the new MDS cameras.

The free-flowing Klamath River following dam removal is an adequate replacement water source for the loss of the reservoirs with respect to water access, supply, and travel time for helicopter drafting. The loss of J.C. Boyle will have only a minor impact, given the proximity of Keno Reservoir, which is a better drafting water source than J.C. Boyle Reservoir. Also, two wide, deep pools will be re-exposed in the upstream portion of the

J.C. Boyle Reservoir following drawdown. Bucket and longline operations in the other reservoirs should be relatively unaffected by the Proposed Action as dozens of river locations in the reservoir footprints will have suitable width and depth for bucket drafting. Buckets are more commonly used by CFSU and ODF for initial attack than snorkels, so those efforts will be relatively unchanged as a result of the Proposed Action. The anticipated ARAPs should result in at least two locations per reservoir which meet the drafting safety criteria for snorkel helicopters. This should be a sufficient number of drafting locations to limit traffic delays on drafting activities.

Flows in the free-flowing Klamath River following dam removal will be more than sufficient to replenish water even under the most extreme drafting conditions. A large Type 1 snorkel helicopter can hold approximately 2000 gallons and takes about a minute to fill. If a Type 1 snorkel helicopter was drafting continuously, it would extract 2000 gal/min, which is approximately 4.5 cubic feet per second (cfs). For context, the minimum prescribed post-removal Klamath River stream flows from the 2019 National Marine Fisheries Service Biological Opinion (NMFS, 2019) for July and August are 900 cfs, which is equivalent to 400,000 gal/min and is enough flow to support 200 snorkel helicopters drafting continuously. This is an order of magnitude more helicopters than are drafting on even the largest fires, so there is ample water supply for all imaginable circumstances.

The dip tanks will provide additional flexibility and utility for aerial drafting in the ASE area, including capabilities that do not currently exist in the Basin. The portable tanks can be transported to areas of need and will allow CFSU to create helicopter drafting opportunities in many locations around the ASE area that do not currently support aerial efforts.

While the reservoirs currently offer more wetted area for snorkel drafting than the post-removal river will, it is impossible to say how this difference in wetted area will affect firefighting abilities in the Basin. Each fire has different characteristics and will require different fire suppression strategies and resources. The proximity of a water source to the fire is a primary driver of choice for helicopter drafting, and other sources (e.g., ponds and the free-flowing Klamath River) have been used in favor of the reservoirs on even large campaign fires. Furthermore, the number of drafting helicopters used for a given incident will depend on the scale of the fire but also on the allocation of helicopters to other incidents. Given the improvements in early detection, fewer fires should reach a significant scale.

Maximum potential increases in air attack turn-around time are expected to be smaller than the gains in early detection and initial attack response time. Given the many anticipated locations of ARAPs (e.g., Figure 12, Figure 13, and Figure 14), maximum increases in the distance a helicopter would need to travel to access a suitable drafting location are around 1 mile, and most increases will be much smaller compared to existing conditions. As a rule of thumb, each mile added to a helicopter drafting flight adds 2 to 3 minutes to each round-trip water draft and drop (L. Winslow, ODF-SWO, *pers. comm.*, 2019.04.02). Potential maximum increases in helicopter turn-around times during initial attack will be only a fraction of the potential time saved using the MDS system, so aerial initial attack efforts should be more effective post-removal than the *status quo*.

7. RENEWAL CORPORATION COMMITMENTS

Upon FERC approval of the Fire Management Plan, the Renewal Corporation will implement the measures stated in this Fire Management Plan, including any changes required in the FERC LSO. The measures, as described below, will be implemented in order to (a) prevent or control any fire caused by construction or habitat restoration activities under the Definite Decommissioning Plan, and (b) avoid a net diminution in firefighting resources, or an increase in fire ignition risk, as a result of the loss of the Project reservoirs. The Renewal Corporation will seek cooperative agreements with a completion target in the first quarter of 2022. The Renewal Corporation expects all the commitments stated herein to be complete in less than 5 years from License Surrender.

- 1) The Renewal Corporation will comply with all applicable agency regulations and requirements.
- 2) The Renewal Corporation will employ the best workplace practices, as described herein, to mitigate fire risk during construction activities.
- 3) The Renewal Corporation will enter into appropriate agreements with fire agencies to implement the following measures:
 - Installation of early detection camera technology for ODF to improve early fire detection capabilities in the Basin
 - Provision of a 9" chipper-dump bed trailer for FSCSC and base model pick-up truck to haul the trailer to assist with defensible space in Siskiyou County
 - Design and construction of five permanent dry hydrants located at or near road crossings of large tributaries to provide additional water sources
 - Verification of continued functionality of Copco Lake hydrant system through License Surrender
 - Construction or improvement of three boat launches to access the Klamath River following dam removal
 - Identification and maintenance, through the term of the FMP, of aerial river access points (ARAPs) in the former reservoirs (two per reservoir) that meet specific suitability performance criteria to be used by Type 1 helicopters with snorkels, and
 - Provision to CFSU of five portable, self-supporting (5000 - 6000 gallon) dip tanks and two helicopter sling (360 gallons) dip tanks; all with required pumps and hoses.
- 4) The Renewal Corporation will annually report to FERC on the implementation of these measures.
- 5) The Renewal Corporation will submit a real-time report to FERC for any fires caused as a result of the Proposed Action.

8. AGENCY CONSULTATION

The Fire Management Plan was developed in consultation with agency personnel. Letters of support for the Fire Management from CalFire and ODF are in Appendix C. A record of the agency personnel consulted during the development of the FMP and the topics consulted on is provided in Table 8-1.

Table 8-1. Agency personnel consulted during development of the Fire Management Plan.

Agency	Title of Agency Representative	Topics of Consultation	Dates consulted
CalFire	Director	Long-term fire management	2020.07.29 2020.08.05 2021.01.08
CalFire	Chief Deputy Director	Long-term fire management	2021.01.08
CalFire	Deputy Director, Fire Protection	Long-term fire management	2020.07.29 2020.08.05 2021.01.08
CalFire	Deputy Director, Legislation	Long-term fire management	2021.01.08
CalFire	Deputy Director, Resource Management	Long-term fire management	2020.07.29
CalFire	Deputy Director of Fiscal Services	Long-term fire management	2020.08.05
CalFire	Chief, Northern Region	Long-term fire management	2020.07.29 2020.08.05 2021.01.08
CalFire	Northern Assistant Region Chief	Long-term fire management	2019.02.15
CalFire	Deputy Chief	Long-term fire management, Tactical air ops	2020.08.03 2020.08.05
CalFire	Fire and Resource Assessment Program – Chief, Fire Science and Environmental Science Specialists	Long-term fire management, Reax analysis	2020.07.14 2020.07.29

Agency	Title of Agency Representative	Topics of Consultation	Dates consulted
CalFire Siskiyou Unit	Unit Chief	Long-term fire management	2019.02.15 2019.09.04
CalFire Siskiyou Unit	Shasta Valley Battalion Chief	Long-term fire management	2019.03.04 2019.05.14 2019.09.04
CalFire Siskiyou Unit	Assistant Chief of Operations	Long-term fire management	2019.03.04 2019.05.14 2019.09.04
CalFire Siskiyou Unit	Forester	Regulations, near-term fire management	2017.08.10 2017.08.14
CalFire Siskiyou Unit	Prevention Specialist	Regulations, near-term fire management	2017.08.14
Copco Fire Protection District	Fire Chief	Contact attempted 2019.04.01; 2019.04.10	
Hornbrook Volunteer Fire Department	Chief	Long-term fire management, existing resources	2019.04.01
Keno Fire Department	Chief	Existing resources	2017.08.09
Oregon Department of Forestry - Klamath Lake District	Protection Unit Forester	Regulations, near-term fire management, long-term fire management, existing resources, monitored detection system	2017.08.16 2019.05.16 2020.04.22 2020.12.01
Oregon Department of Forestry - Klamath Lake District	Stewardship Forester	Regulations, near-term fire management	2017.08.16
Oregon Department of Forestry - Klamath Lake District	Management Unit Forester	Regulations, near-term fire management	2017.08.16 2019.05.16

Agency	Title of Agency Representative	Topics of Consultation	Dates consulted
Oregon Department of Forestry – Southwest Oregon District	Forester	Near-term fire management, PDM	2017.08.11
Oregon Department of Forestry – Southwest Oregon District	Assistant District Forester/Medford Unit Forester	Aerial fire suppression	2019.04.02 2019.04.12 2019.04.29 2019.05.16 2019.09.04 2020.07.10 2020.10.30
Oregon Department of Forestry – Southwest Oregon District	Wildland Fire Supervisor – Dispatch	Monitored detection system	2019.05.16
Oregon Department of Forestry – Southwest Oregon District	Lead Detection Dispatcher	Monitored detection system	2019.05.29 2019.06.12
United States Bureau of Land Management – Lakeview District, Klamath Falls Field Office	Assistant Fire Manager	Regulations, jurisdictions	2020.06.10
United States Bureau of Land Management – Lakeview District	Manager	Regulations, jurisdictions	2017.08.11
United States Bureau of Land Management – Northern California District, Redding Field Office	Forest Ecologist	Regulations, jurisdictions	2017.08.29

9. REFERENCES

- CalFire, (n.d.-a). Firefighting Aircraft Recognition Guide.
http://www.fire.ca.gov/communications/downloads/AviationGuide_FINAL_web.pdf. Accessed 2019.
- CalFire. (n.d.-b) CalFire Operations Handbook. <http://calfireweb.fire.ca.gov/library/handbooks/>
- CalFire, 1999. Industrial Operations Fire Prevention Field Guide. July 29, 1999.
- CalFire, 2007. Fire and Resource Assessment Program. Fire Hazard Severity Zones [computer file].
Sacramento, CA.
- California State Board of Forestry and Fire Protection (CSBFFP) and CalFire, 2018. 2018 Strategic Fire Plan for California. August 22, 2018.
- CalFire, 2019. Community Wildfire Prevention and Mitigation Report in response to Executive Order N-05-19. February 22, 2019.
- CalFire Siskiyou Unit (CalFire), 2016. Unit Strategic Fire Plan: Siskiyou Unit. Yreka, CA.
- Estes, B.L., Knapp, E.E., Skinner, C.N., Miller, J.D. and Preisler, H.K., 2017. Factors influencing fire severity under moderate burning conditions in the Klamath Mountains, northern California, USA. *Ecosphere*, 8(5), p.e01794.
- Fried, J.S., Gillless, J.K. and Spero, J., 2006. Analysing initial attack on wildland fires using stochastic simulation. *International Journal of Wildland Fire*, 15(1), pp.137-146.
- Governor Newsom's Strike Force (Strike Force), 2019. Wildfires and Climate Change: California's Energy Future. A Report from Governor Newsom's Strike Force. April 12, 2019.
- Keeley, J.E. and Syphard, A.D., 2018. Historical patterns of wildfire ignition sources in California ecosystems. *International Journal of Wildland Fire*, 27(12), pp.781-799.
- Klamath River Renewal Corporation Technical Representatives (Renewal Corporation), 2020. Definite Decommissioning Plan for the Lower Klamath Project. Prepared for the Klamath River Renewal Corporation.
- Lee, Y., Fried, J.S., Albers, H.J. and Haight, R.G., 2012. Deploying initial attack resources for wildfire suppression: spatial coordination, budget constraints, and capacity constraints. *Canadian Journal of Forest Research*, 43(1), pp.56-65.
- Oregon Department of Forestry (ODF), 2019. Fire Season Requirements.
<https://www.oregon.gov/ODF/Fire/FirePreventionDocuments/2019%20Fire%20Season%20Requirements.pdf>

- National Fire Protection Association (NFPA), 2017a. NFPA 25 Standard for the Inspection, Testing, and Maintenance of Water-Based Fire Protection Systems. August 24, 2016.
- National Fire Protection Association (NFPA), 2017b. NFPA 1142 Standard on Water Supplies for Suburban and Rural Fire Fighting. June 2, 2016.
- National Fire Protection Association (NFPA), 2018. NFPA 1143 Standard on Wildland Fire Management. August 21, 2017.
- National Fire Protection Association (NFPA), 2019a. NFPA 51B Standard for Fire Prevention During Welding, Cutting, and Other Hot Work. July 15, 2018.
- National Fire Protection Association (NFPA), 2019b. NFPA 1963 Standard for Fire Hose Connections. November 25, 2018.
- National Marine Fisheries Service (NMFS), 2019. Endangered Species Act Section 7(a)(2) Biological Opinion, and Magnuson-Stevens Fishery Conservation and Management Act Essential Fish Habitat Response for Klamath Project Operations from April 1, 2019 through March 31, 2024. NMFS Consultation Number: WCR-2109-11512, WRCO-2019-00113. March 29, 2019.
- PacifiCorp, 2019. California Wildfire Mitigation Plan. Implementing Requirements of Senate Bill 901 and Rulemaking 18-10-007. February 6, 2019.
- PacifiCorp, 2020. California Wildfire Mitigation Plan. Implementing Requirements of Senate Bill 901 and Rulemaking 18-10-007. February 7, 2020.
- Siskiyou County, 2019. Community Wildfire Protection Plan – Siskiyou County. May 21, 2019.
- South Central Oregon Fire Management Partnership (SCOFMP), 2015. South Central Oregon Interagency Fire Danger Operating Plan.
- Stephens, S.L., Weise, D.R., Fry, D.L., Keiffer, R.J., Dawson, J., Koo, E., Potts, J. and Pagni, P.J., 2008. Measuring the rate of spread of chaparral prescribed fires in northern California. *Fire Ecology*, 4(1), pp.74-86.
- United States Bureau of Reclamation (BOR), 2011. Reservoir Area Management Plan for the Secretary's Determination on Klamath River Dam Removal and Basin Restoration. Klamath River, Oregon and California. Technical Report No. SRH-2011-19. Mid-Pacific Region. June 2011.
- United States Bureau of Reclamation (BOR) and California Department of Fish and Game (CDFG), 2012. Klamath Facilities Removal Final Environmental Impact Statement / Environmental Impact Report. Sacramento, CA.

United States Forest Service (USFS), Remote Sensing Applications Center, 2010. MODIS Active Fire Detections for the CONUS [computer file]. Salt Lake City, Utah.

United States Forest Service (USFS) and U.S. Office of Aviation Services (OAS), 2015. Interagency Aviation User Pocket Guide. NFES 001373. May 2015.

Wildland Fire Technologies, Inc. (WFT), 2016. Klamath County Community Wildfire Protection Plan 2016 update. Klamath Falls, OR. December 5, 2016.

APPENDIX A – REAX ENGINEERING, INC., QUALITATIVE WILDFIRE RISK ANALYSIS OF THE KLAMATH RIVER RENEWAL PROJECT



Reax Engineering Inc.
Job # 19-0739

Quantitative Wildfire Risk Analysis of the Klamath River Renewal Project

Prepared for Klamath River Renewal Corporation

Revision 1
June 5, 2020

Document Revision History



Job #	Job Name	Client
19-0739	Quantitative Wildfire Risk Analysis of the Klamath River Renewal Project	Klamath River Renewal Corporation

Revision #	Date	Description	
Rev 0	February 26, 2020	Interim draft provided for KRRC review and comment.	
		Prepared by: Chris Lautenberger Darrell Schulte Delaney Seeburger Maria Theodori	Approved by: Chris Lautenberger
Rev 1	June 5, 2020	First complete draft.	
		Prepared by: Chris Lautenberger Darrell Schulte Delaney Seeburger Maria Theodori	Approved by: Chris Lautenberger
		Prepared by:	Approved by:
		Prepared by:	Approved by:

TABLE OF CONTENTS

EXECUTIVE SUMMARY	1
1.0 INTRODUCTION.....	1
2.0 BACKGROUND	2
2.1 FIRE MANAGEMENT PLAN	2
2.2 ANALYSIS AREA AND AERIAL SUPPRESSION EXTENT	2
2.3 WILDFIRE RISK QUANTIFICATION WITH MONTE CARLO FIRE SPREAD MODELLING	4
3.0 FIRE HISTORY.....	5
3.1 FIRE OCCURRENCE	5
3.1.1 Human-caused fires	5
3.1.2 Lightning-caused fires	8
3.1.3 Fires from all causes	10
3.2 FIRE PERIMETERS	10
3.3 LARGE FIRES OCCURRING IN ANALYSIS AREA	14
3.3.1 2014 Oregon Gulch Fire	14
3.3.2 2018 Klamathon Fire	15
3.4 SUMMARY.....	15
4.0 ANALYSIS OF THE FIRE MANAGEMENT PLAN'S FIRE RISK MITIGATION MEASURES.....	16
4.1 POST-REMOVAL RESOURCES	16
4.2 CHANGE IN WATER AVAILABILITY	17
4.3 CHANGE IN FIRE OCCURRENCE FREQUENCY	18
4.4 CHANGE IN FIRE DETECTION EFFICIENCY	19
4.4.1 Existing fire detection scheme	19
4.4.2 Post-restoration fire detection scheme	20
4.4.3 Detection coverage viewshed analysis.....	22
4.4.4 Limitations of viewshed analysis.....	28
4.4.5 Satellite-based fire detection technology	28
4.5 CHANGE IN INITIAL ATTACK PROBABILITY OF CONTAINMENT	29
4.6 CHANGE IN EXTENDED ATTACK EFFICACY	31
5.0 EFFECT OF RESERVOIR DEWATERING AND EARLY DETECTION ON LANDSCAPE-SCALE BURN PROBABILITY	32
5.1 MONTE-CARLO FIRE SPREAD MODEL: ELMFIRE	32
5.2 FUELS	34
5.2.1 Pre-restoration.....	34
5.2.2 Post-restoration	35
5.3 FIRE WEATHER.....	38
5.3.1 Methodology	38
5.4 STOCHASTIC SELECTION OF IGNITION LOCATIONS AND WIND/WEATHER CONDITIONS	40
5.5 QUANTIFICATION OF DEWATERING IMPACT ON MODELED LANDSCAPE-SCALE BURN PROBABILITY	40
5.6 QUANTIFICATION OF EARLY DETECTION TIME IMPACT ON MODELED LANDSCAPE-SCALE BURN PROBABILITY	42
6.0 CONCLUSIONS	44
7.0 REFERENCES.....	45

LIST OF FIGURES

FIGURE 1. LOCATION OF DAMS IN RELATION TO ANALYSIS AREA	3
FIGURE 2. AERIAL SUPPRESSION EXTENT.....	3
FIGURE 3. HUMAN-CAUSED IGNITIONS IN ANALYSIS AREA.	6
FIGURE 4. HUMAN-CAUSED FIRES IGNITION DENSITY.	6
FIGURE 5. HUMAN-CAUSED FIRES IGNITION DENSITY AND ROAD NETWORK.	7
FIGURE 6. HUMAN-CAUSED FIRES IGNITION DENSITY AND BUILDING FOOTPRINTS.	7
FIGURE 7. LIGHTNING-CAUSED IGNITIONS IN ANALYSIS AREA.....	8
FIGURE 8. LIGHTNING-CAUSED FIRES IGNITION DENSITY.....	9
FIGURE 9. LIGHTNING CAUSED FIRES IGNITION DENSITY AND TERRAIN.....	9
FIGURE 10. IGNITION DENSITY – ALL CAUSES.....	10
FIGURE 11. CALIFORNIA FIRE PERIMETERS 1970-1979.....	11
FIGURE 12. CALIFORNIA FIRE PERIMETERS 1980-1989.....	11
FIGURE 13. CALIFORNIA FIRE PERIMETERS 1990-1999.....	12
FIGURE 14. CALIFORNIA FIRE PERIMETERS 2000-2009.....	12
FIGURE 15. CALIFORNIA FIRE PERIMETERS 2010-2019.....	13
FIGURE 16. OREGON FIRE PERIMETERS 2000-2019.....	13
FIGURE 17. FINAL PERIMETER OF THE 2014 OREGON GULCH FIRE.....	14
FIGURE 18. FINAL PERIMETER OF THE 2018 KLAMATHON FIRE.....	15
FIGURE 19. POST-REMOVAL MANAGEMENT RESOURCES PROVIDED AS PART OF THE LONG-TERM FMP [3].	16
FIGURE 20. RIGID TANK MODEL SHOWN WITH HELICOPTER SNORKEL.....	17
FIGURE 21. SOFT-SIDED TANK MODEL BEING AIRLIFTED.....	17
FIGURE 22. PRE- AND POST-RESTORATION DIP SITES.....	18
FIGURE 23. EXISTING LOOKOUTS FOR FIRE SURVEILLANCE IN THE KLAMATH BASIN.....	20
FIGURE 24. POST-RESTORATION MDS CAMERA LOCATIONS FOR FIRE SURVEILLANCE.....	21
FIGURE 25. EXAMPLE OF SMOKE PLUME DETECTION FROM A CAMERA IN THE ALERTWILDFIRE NETWORK [30].	23
FIGURE 26. POST-RESTORATION FIRE DETECTION CAMERA VIEWSHED, RESULTS AT TARGET HEIGHT OF (A) 0 FEET, (B) 100 FEET, AND (C) 500 FEET ABOVE GROUND SURFACE, OVERLAID WITH THE AERIAL SUPPRESSION EXTENT.	25
FIGURE 27. COMPARATIVE VIEWS OF THE EXISTING RESOURCES VIEWSHED (1A, 1B, 1C) AND POST-RESTORATION RESOURCES VIEWSHED (2A, 2B, 2C) AT TARGET HEIGHTS OF 0 FEET, 100 FEET, AND 500 FEET, RESPECTIVELY FROM LEFT TO RIGHT. THE PINK AREAS (3A, 3B, 3C) HIGHLIGHT THE INCREASED COVERAGE PROVIDED BY THE POST-RESTORATION RESOURCES, CONTRAST TO THE EXISTING RESOURCES COVERAGE INDICATED IN WHITE. THE PINK AREAS (4A, 4B, 4C) HIGHLIGHT THE INCREASE IN TRIANGULATED AREA COVERAGE PROVIDED BY THE POST-RESTORATION RESOURCES, CONTRAST TO THE EXISTING RESOURCES TRIANGULATION COVERAGE IN WHITE.	27
FIGURE 28. SAMPLE ELMFIRE FIRE SPREAD SIMULATION FOR INDIVIDUAL FIRE IGNITION. (A) FIRE TYPE (SURFACE FIRE, PASSIVE CROWN FIRE, OR ACTIVE CROWN FIRE). (B) FLAME LENGTH.....	33
FIGURE 29. IRON GATE AND COPCO SURFACE FUEL (PRE-RESTORATION).....	35
FIGURE 30. FCCS EXISTING VEGETATION TYPES.....	36
FIGURE 31. LANDFIRE 2.0.0 (REMAP) EXISTING VEGETATION TYPES.....	36
FIGURE 32. IRON GATE AND COPCO SURFACE FUELS POST-RESTORATION.....	37
FIGURE 33. DIFFERENCE BETWEEN MODELED PRE-RESTORATION AND POST-RESTORATION BURN PROBABILITY.....	41
FIGURE 34. CHANGE IN MODELED MEAN BURN PROBABILITY WITHIN AERIAL SUPPRESSION EXTENT AS A FUNCTION OF INITIAL ATTACK TIME RELATIVE TO FIRE IGNITION.....	43

LIST OF TABLES

TABLE 1. FACTORS AFFECTING POST-REMOVAL FIRE OCCURRENCE FREQUENCY ¹	18
TABLE 2. EXISTING LOOKOUTS FOR FIRE SURVEILLANCE IN THE KLAMATH BASIN.	20
TABLE 3. POST-RESTORATION MDS CAMERA LOCATIONS FOR FIRE SURVEILLANCE IN THE KLAMATH BASIN.	21
TABLE 4. VIEWSHED ANALYSIS INPUTS FOR THE PRE- AND POST-RESTORATION FIRE DETECTION SCHEMES.	22
TABLE 5. PERCENT COVERAGE OF ASE ¹	25
TABLE 6. PROBABILITY OF CONTAINMENT AS A FUNCTION OF FIRE SIZE AND HEAD FIRE FIRELINE INTENSITY AT COMMENCEMENT OF INITIAL ATTACK FROM EQUATION 1 [42].	31
TABLE 7. IGNITION PROBABILITY BY WOODY EMBERS/FIREBRANDS AS TABULATED BY SCHROEDER [59].	39
TABLE 8. CHANGED IN MODELED MEAN BURN PROBABILITY WITHIN AERIAL SUPPRESSION EXTENT FROM PRE- RESTORATION TO POST-RESTORATION FUELS.	41

LIST OF ABBREVIATIONS

AI	Artificial Intelligence
ASE	Aerial Suppression Extent
CAL FIRE	California Department of Forestry and Fire Protection
EVS	EnviroVision Solutions
FFWI	Fosberg Fire Weather Index
FMP	Fire Management Plan
FOD	Fire Occurrence Database
FRAP	Fire and Resource Program
GIS	Geographic Information System
IAP	Incident Action Plans
KRRC	Klamath River Renewal Corporation
MDS	Monitored Detection System
MEL	Most Efficient Level
MFFWI	Modified Fosberg Fire Weather Index
NARR	North American Regional Reanalysis
NIFC	National Interagency Fire Center
NWCG	National Wildfire Coordinating Group
ODF	Oregon Department of Forestry
WRF	Weather Research and Forecasting

EXECUTIVE SUMMARY

Reax Engineering Inc. (Reax) has been retained by Klamath River Renewal Corporation (KRRC) to analyze KRRC's Fire Management Plan (FMP) and quantify the change in fire risk associated with the implementation of the Klamath Hydroelectric Settlement Agreement (KHSa). The KRRC will remove four dams along the Klamath River and adjacent areas. The following factors, among others, are considered as part of this analysis:

- Fire history in the area,
- Vegetation growth in areas that were previously reservoir,
- Potential reduction in the amount of water available for firefighting purposes as a result of reservoir removal,
- Removal of potential ignition sources associated with electrical generation, and
- Fire risk reduction measures such as real-time fire detection monitoring, and introduction of additional water sources for ground crews.

Our findings indicate the amount and accessibility of water for suppression will not be reduced by the removal of the reservoirs created by the dams. The amount of water that is available for extended attack, *i.e.* fires lasting over 48 hours that require staffing and shift changes, likewise will remain unchanged. This water will be available from dip tanks, dry hydrants, and the identified river pools rather than from large, open reservoirs. The river pools do alter the amount of risk to helicopter pilots as the maneuver requires hovering to drop in and out of a canyon. The ability to use water from the Klamath River for fire suppression will not be impacted although the convenience and technical skill required to access that water will be. Furthermore, Upper Klamath Lake and Link Reservoir will still be available for suppression efforts in the northeastern region of the project area.

One of the post-removal resources proposed in the FMP is Monitored Detection System (MDS) consisting of a network of detection cameras. In California and Oregon, there has been an increase in detection camera installations at fire lookouts that were historically staffed. A viewshed analysis was conducted of the existing and planned detection camera locations to assess and compare fire detection coverage of the Klamath Basin both pre- and post-restoration. This was done to determine if the proposed post-restoration fire detection resources provide adequate coverage of the project area within the Klamath River Basin and to quantify the change in detection effectiveness between pre- and post-restoration resources. The post-restoration detection scheme provides a significant increase in detection coverage for the protected area with a corresponding increase in triangulated coverage area. This increase in coverage area will lead to reduced fire detection times and thereby more rapid initial attack responses.

To assess how improved detection times (from cameras) and increased burnable landmass (from dewatering) affect landscape-scale burn probabilities in the project area, a Monte Carlo fire spread analysis was used to analyze several different scenarios within the Aerial Suppression Extent (ASE) defined by CAL FIRE which delineates the land area where water drafted from the existing reservoirs could be used in aerial fire suppression. Based on this analysis and the related analyses of water availability, post-removal suppression resources provided, and the proposed MDS, the

probability of containment on initial attack within the ASE will remain unchanged or increase for the following reasons:

- Dewatering causes an insignificant ($< 1\%$) increase in modeled burn probability,
- There is no reduction in water availability for firefighting purposes,
- Fire detection and reporting times will, at worst, remain unchanged but are more likely to be reduced due to the coverage provided by the proposed MDS, and
- Travel time by responding units will remain unchanged.

The salient conclusions drawn from the analyses presented in this report are:

1. There will be no effective decrease in water availability for firefighting purposes following reservoir drawdown due to implementation of measures described in the Fire Management Plan. The ease with which the helicopters and fixed wing aircraft can access the reservoirs will change but the amount of water available will not be affected by dam removal. Furthermore, the dip tanks and dry hydrants provided will offer alternate water sources for suppression efforts independent of water accessibility from the Klamath River.
2. Cameras will provide an effective means of early fire detection in the project area with fire sizes at detection expected to be between 0.01 acres and 0.1 acres. Detection at relatively smaller fire sizes expedites suppression response and increases probability of containment in initial attack.
3. Dewatering of the project reservoirs and reclamation of approximately 1,000 acres of land will have a negligible effect on burn probability.
4. Probability of containment on initial attack shows that early detection associated with installation of fire detection cameras increases probability of containment, consequently reducing modeled mean burn probability. For example, a reduction in average arrival time from 30 minutes to 25 minutes results in a 7% decrease in modeled mean burn probability within the ASE, and a reduction in average arrival time from 30 minutes to 20 minutes results in a 34% decrease in modeled mean burn probability within the ASE.

1.0 INTRODUCTION

Reax Engineering Inc. (Reax) has been retained by the Klamath River Renewal Corporation (KRRRC) to quantify the change in fire risk associated with the removal of four dams along the Klamath River and adjacent areas where fire risk may change. The following factors, among others, are considered as part of this analysis:

- Fire history in the area,
- Vegetation growth in areas that were previously reservoir,
- Potential reduction in the amount of water available for firefighting purposes,
- Removal of potential ignition sources associated with electrical generation, and
- Risk reduction/mitigation countermeasures such as real-time fire detection monitoring, introduction of additional water sources for ground crews.

As described in detail later in this report, one of tools used in this work is a Monte Carlo fire spread analysis [1-2] that quantifies landscape-scale burn probability under different scenarios so that the effect of vegetation regrowth, advance warning, *etc.* can be quantified.

This report is organized as follows:

- Section 2 provides background information regarding the KRRRC project.
- Section 3 describes fire history in the analysis area.
- Section 4 analyzes pre- and post-restoration state of the analysis area and the proposed changes in suppression and detection effectiveness.
- Section 5 presents the Monte-Carlo fire spread modeling methodology used to quantify changes in landscape-scale burn probability.
- Section 6 summarizes our conclusions.

2.0 BACKGROUND

2.1 Fire management plan

KRRC developed a Fire Management Plan (FMP) [3] to address fire prevention and suppression associated with the physical removal of four hydroelectric dams along the Klamath River (Iron Gate, Copco No. 1, Copco No. 2, and J.C. Boyle). The goal of the FMP is to assure that the dam removals will not cause a net diminution in firefighting resources and that, both during and after demolition, the current fire ignition risk that exists will not increase as a result of the dam removal. Pursuant to this goal, the FMP contains:

- Background on the history of fire in the region,
- Local fire agency jurisdictions and regulatory requirements,
- Descriptions of the short- and long-term FMPs to be implemented by KRRC.

Review and analysis of the FMP is the starting point for the work described in the current report.

2.2 Analysis area and aerial suppression extent

Analyzing fire risk only in an area immediately adjacent to the river course discounts the impact that removing the dams could have on fire risk at greater distances. Conversely, analyzing fire risk in areas at scales approaching the size of California and Oregon is inefficient. For that reason, the analysis area used in this project (Figure 1) is a 50-mile buffer surrounding the four dams slated for removal. The distance of 50-miles was chosen to strike a balance between analyzing an unnecessarily large region and capturing the extent of the area that could be impacted by the dam removal. The analysis area shown in Figure 1 is used primarily for analyzing fire history (Section 3.0) and conducting Monte-Carlo fire spread analyses (Section 0).

A smaller area known as the Aerial Suppression Extent (ASE) as shown in Figure 2 was used as a boundary in the detection effectiveness analysis (Section 4.4). The ASE was also used in analyzing any potential changes in suppression effectiveness due to dewatering the reservoirs. The ASE was defined by CAL FIRE and delineates the land area where water drafted from the existing reservoirs could be used in aerial fire suppression.




Figure 1. Location of dams in relation to analysis area.




Figure 2. Aerial Suppression Extent.

2.3 Wildfire risk quantification with Monte Carlo fire spread modelling

There is no “one size fits all” approach to quantifying wildland fire hazard or risk. Different approaches may be appropriate under different circumstances. Wildland fire hazard/risk assessment using fire behavior modeling has recently seen increased usage due in part to more powerful computational resources, improved fire models, and readily available geospatial input data. For example, ArcFuels [4-5] provides a desktop-based interface between ArcGIS and widely-used fire behavior models such as FARSITE [6] and FLAMMAP [7].

Keane *et al.* [8] highlighted the potential for Monte Carlo analysis to be used for wildland fire risk quantification. One advantage of such approaches is that fire shadows, islands, and related effects can be captured. For example, with all other factors held constant, an area downwind from an obstacle to fire spread such as a large barren area or water body is less likely to burn than areas upwind from the obstacle to fire spread. Similarly, a patch of highly flammable fuels surrounded by less flammable fuels is less likely to burn [9]. These spatial effects cannot be captured by analyses that consider conditions only at a point, or burn every point as a head fire, but would be captured by analyses that include fire progression. For these reasons, Monte Carlo simulations where fire spread is modeled from tens of thousands of separate ignition locations under a range of weather conditions is one of the most promising tools for quantitative wildland fire risk/hazard assessment.

Monte Carlo fire spread modelling techniques are now being applied in regulatory proceedings. For example, the California Public Utilities Commission (CPUC) recently commissioned development of powerline fire risk maps. The resultant high fire threat district maps were adopted by the CPUC for promulgating fire prevention regulations in 2018. One of the bases for these maps was Monte Carlo fire spread modeling conducted by an Independent Expert Team (IET) led by CAL FIRE. A similar approach has already been applied in Victoria, Australia, to quantify fire risk associated with overhead electrical utility ignited fires [10-14]. The Monte Carlo fire spread modeling techniques applied in this report are similar to those described above and used to develop the CPUC high fire threat district maps and map powerline risk in Australia.

3.0 FIRE HISTORY

To understand how fire has historically impacted the analysis area, fire history records for Oregon and California were aggregated and analyzed. Such analysis of past fire history provides context for historical fire sizes, locations, causes, and frequency at which fires occur. It can also provide insight into local hazards or weather events that dramatically influence fire behavior.

3.1 Fire occurrence

The US Forest Service has published a Fire Occurrence Database (FOD) [15] which contains spatial information for wildfires in the United States between 1992 and 2015. Federal, state, and local fire organizations contributed records with minimum requirement that the records include discovery date, final fire size, and a point location accurate to 1-square mile. Where possible, data were transformed to meet the National Wildfire Coordinating Group's (NWCG) data standards. Error-checking was performed, and redundant records were removed where possible, resulting in a database with 1.88 million geo-referenced wildfire records. The FOD also records fire cause, allowing spatial and temporal distinctions to be made. The difference of greatest interest to the KRRC project is between human-caused fires (Section 3.1.1) and lightning-caused fires (Section 3.1.2).

3.1.1 Human-caused fires

Human-caused fires describe a range of possible ignition causes including debris burning, vehicle, utility, campfires, electrical, *etc.* The locations of these types of ignitions often follow linear features, such as roads, or tend to be clustered near centers of human activity such as residential neighborhoods, campgrounds, *etc.* Human-caused ignition locations in the analysis area are shown in Figure 3. These individual ignition locations were used to create the ignition density “heatmap”¹ shown in Figure 4. The heatmap shows clustering around Interstate 5, Highway 3, Mt. Shasta, Hilt, Colestin, Mt. Ashland, Keno, Yreka, Ashland, Medford, and Chiloquin, among others. Road networks and building footprints were overlaid on the heatmap to illustrate the concentration of ignitions near infrastructure (Figure 5, Figure 6).

Human-caused fires tend to be smaller and are more successfully suppressed in the initial attack phase than lightning-caused fires. However, these ignitions are of significant interest despite the higher probability of success in initial attack because large human-caused fires often occur under high winds [16]. This can be attributed to many factors, including expansion of human-caused ignitions into regions and during seasons where wind speeds are climatologically higher and the reduced tactical capacities of aerial suppression efforts during high winds [16].

¹ Created using inverse distance weighted kernel density




Figure 3. Human-caused ignitions in analysis area.




Figure 4. Human-caused fires ignition density.




Figure 5. Human-caused fires ignition density and road network.




Figure 6. Human-caused fires ignition density and building footprints.

3.1.2 Lightning-caused fires

Locations of lightning-caused ignitions tend to be both more random and more uniform than human-caused fires (Figure 7). Lightning-caused ignitions are indifferent to geographic location and as such display no dominating trends such as following linear features. To show the relative location of lightning-caused ignitions with respect to topography, a heatmap was generated (Figure 8). The distribution of lightning-caused ignitions does not achieve the intense localization that human-caused ignitions exhibited. The lightning-caused fire heatmap is overlaid with a hill shade raster in Figure 9, allowing the correspondence between topography and lightning-caused ignitions to be visualized as lightning-caused ignitions are more prevalent at higher elevations. Lightning-caused ignitions are also less common where certain fuel types are prevalent (*e.g.* wetlands or sparsely vegetated areas).




Figure 7. Lightning-caused ignitions in analysis area.




Figure 8. Lightning-caused fires ignition density.




Figure 9. Lightning caused fires ignition density and terrain.

3.1.3 Fires from all causes

Compiling human- and lightning-caused ignitions within the analysis area resulted in an additional heatmap (Figure 10). Trends from all ignitions are visible and can be traced back to the contributing cause. For example, the high-density along linear features reflects the human-caused ignitions while the increase in density across the entire analysis area can be ascribed primarily to lightning-caused ignitions.




Figure 10. Ignition density – all causes.

3.2 Fire perimeters

Historical fire perimeters in California and Oregon were used to understand historical fire occurrence, particularly large fires, in the analysis area. The CAL FIRE Fire and Resource Assessment Program (FRAP) database [17] was used for ultimate perimeters in California, the National Interagency Fire Center (NIFC) [18] database was used for ultimate perimeters in Oregon, and GeoMAC data [19] were used to map daily progression of large fires. Figure 11 - Figure 15 present fire perimeters from the FRAP database by decade from 1970 – 2018. Figure 16 presents perimeters in Oregon from 2000-2019 (the period of availability).

Of note is the occurrence of very large fires and their frequency. Prior to 2000, two historical fires became large: an unnamed fire in 1926 and the Bogus Escape fire in 1957. There is an almost 30-year fire return interval for the region based on those two fires alone. After 2000 the return frequency has decreased significantly, as can be seen by the four-year lapse between the 2014 Oregon Gulch and 2018 Klamathon fires.




Figure 11. California fire perimeters 1970-1979.




Figure 12. California fire perimeters 1980-1989.




Figure 13. California fire perimeters 1990-1999.




Figure 14. California fire perimeters 2000-2009.




Figure 15. California fire perimeters 2010-2019.




Figure 16. Oregon fire perimeters 2000-2019.

3.3 Large fires occurring in analysis area

Viewing fire perimeters in context with the surrounding landscape shows that most fires in the analysis area have been small, indicating rapid response and effective containment from fire agencies relative to perimeter growth. Several larger escaped fires were examined in greater detail to understand the conditions that led to such extensive growth. As part of assessing these large historical fires, documentation on suppression resources used by local fire agencies in containing the fires were reviewed. The two most significant fires occurring in the analysis area within the last ten years are the 2014 Oregon Gulch Fire (Section 3.3.1) and the 2018 Klamathon Fire (Section 3.3.2).

3.3.1 2014 Oregon Gulch Fire

A lightning strike ignited the Oregon Gulch Fire on Thursday, July 30, 2014. Several red flag warnings were issued for the period between July 28 and August 5 as high winds were expected in addition to warm, dry days. By Friday morning the fire had grown to 7,500 acres. Over the course of two weeks, the fire burned a total of 35,111 acres north and east of the Copco dams. Figure 17 shows approximately daily progression from infrared imaging and satellite fire detection. The southern edge of the fire advanced up to the Klamath River. Oregon Gulch was managed as part of the Beaver Creek Complex (Figure 17) and was declared 100% contained on August 13, 2014.




Figure 17. Final perimeter of the 2014 Oregon Gulch Fire.

3.3.2 2018 Klamathon Fire

The Klamathon Fire was reported on July 5, 2018, near Hornbrook, CA. By the following evening, the fire had grown to 9,600 acres. Red flag warnings issued for the area on July 3 and continued through July 6 indicate the presence of strong winds with hot, dry conditions. Aerial suppression efforts relied on five dip sites, two from the reservoir above Iron Gate dam, one from the Klamath river, and two from runoff ponds. The Incident Action Plans (IAPs) available from the NIFC database [18] did not contain ICS 209 forms so specific tactics or number of drops were not able to be determined from publicly-available data. The ICS 220 forms that were available provided the type of resource and time the resource began operating each day. The communities of Hornbrook, Hilt, and Colestin were evacuated in addition to the area around Iron Gate dam. By July 21, 2018, the Klamathon Fire was contained after having burned 38,008 acres (Figure 18). There was one civilian fatality and three non-fatal injuries resulting from the fire. At least 80 structures were damaged or destroyed.




Figure 18. Final Perimeter of the 2018 Klamathon Fire.

3.4 Summary

Historical fire perimeters show that most fires in the analysis area were small with some exceptions. The Oregon Gulch and Klamathon fires were examined in greater detail to understand the conditions surrounding their rapid expansion. Fuel conditions and weather during these two fires makes it unlikely that either fire could have been contained in the initial attack phase, regardless of the number of resources dedicated to the effort. The results of a cost-benefit analysis between number of resources deployed versus rapid containment performed by the federal government are discussed in greater detail in Section 4.5.

4.0 ANALYSIS OF THE FIRE MANAGEMENT PLAN'S FIRE RISK MITIGATION MEASURES

The FMP [3] addresses long-term fire management in the Klamath River Basin, incorporating strategies to offset the loss of the three Klamath River reservoirs that have supported fire suppression resources in the past. The FMP also elaborates on the long-term new local and regional fire suppression resources to be implemented in the Basin. KRRC has committed to implement (and oversee through license surrender) effective and feasible strategies and concepts to enhance both short- and long-term fire prevention, detection, and suppression in the Basin. In this report, the effects of the proposed FMP strategies are analyzed, including change in water availability (Section 4.2), fire occurrence frequency (Section 4.3), detection effectiveness (Section 4.4), probability of containment on initial attack (4.5), and extended attack efficacy (Section 4.6).

4.1 Post-removal resources

A map of post removal resources, excerpted from the FMP [3], is shown in Figure 19. Key drafting points for engines and tenders include 2 new boat launches, six planned permanent dry hydrants to complement the six existing pressurized hydrants and provide viable water access points for ground-based equipment and to support aerial water delivery. In addition, the FMP proposes one large permanent rigid dip tank, three medium-sized, portable self-supporting dip tanks (Figure 20), and two small portable helicopter sling tanks (Figure 21) to complement other aerial drafting resources.




Figure 19. Post-removal management resources provided as part of the long-term FMP [3].



Figure 20. Rigid tank model shown with helicopter snorkel.



Figure 21. Soft-sided tank model being airlifted.

Where available, documentation and data regarding aerial suppression from previous fires were reviewed and analyzed in conjunction with the FMP post-removal resources to address the concerns of local fire agencies with respect to the proposed dam removal and its impact on available water sources.

4.2 Change in water availability

There are currently 96 inventoried river pools of varying risk classes for helicopter bucket work and another predicted 41 helicopter bucket sites of varying risk categories in the current reservoir pool areas (Figure 22) [3]. With around 137 pools for helicopter bucket use and a minimum of 18 other river access sites available for drafting, the ability to use water for fire suppression will not be impacted. The difficulty of using some sites, such as reservoirs, may be impacted but the overall amount of water available should not be affected by dam removal. The minimum post-removal river discharge of 900 ft³/s will be sufficient to maintain a good water supply for suppression forces. In addition to the various sizes of dip tanks will provide a helpful complement to the mainstem Klamath River for aerial drafting, and the portable tanks provide the ability to create dip sites in locations where they do not currently exist. The six planned permanent dry hydrants will also increase water availability for ground-based equipment relative to the pre-removal condition and can be used in conjunction with the portable dip tanks around the former reservoirs.




Figure 22. Pre- and Post-restoration dip sites.

4.3 Change in fire occurrence frequency

As part of reservoir dewatering and dam removal, three primary factors may affect future fire occurrence frequency in and around the project location. These factors are summarized and discussed qualitatively in Table 1.

Table 1. Factors affecting post-removal fire occurrence frequency¹.

Factor	Effect	Impact
Decommissioning 15 miles of overhead electrical utilities	Reduce fire occurrence frequency by removal of potential ignition sources	Minor
Dewatering of approximately 1,000 acres of reservoir	Increase fire occurrence frequency by increasing burnable landmass	Minor
Donation of 9" chipper-dump bed trailer and base model pick-up truck	Reduce fire occurrence frequency through reduction in debris burning; high impact on local residential vegetation management	Minor

¹ Impact is on fire occurrence frequency at the landscape scale.

All factors identified here are considered to have a minor impact on future fire occurrence frequency at the landscape scale. The removal of overhead electrical utilities and use of a chipper for improving defensible space should impact fire occurrence frequency locally, particularly as it relates to structure fires. On this basis, reservoir dewatering and dam removal is anticipated to have

a negligible change on fire occurrence frequency at the landscape scale. Fire occurrence will continue to meet historical averages; however, the cause of these future fires will change as a result of the removal of existing electrical utilities with a potentially corresponding increase in some other human-caused ignitions, *e.g.* campfires. After de-watering, average fire size and fire occurrence frequency will follow historic averages for the area.

4.4 Change in fire detection efficiency

One of the primary goals of KRRC's FMP is to minimize the likelihood of large-scale fire development such that a fire can be suppressed or contained. A critical component of the overall strategy is reliable, rapid fire detection following an ignition, including accurately placing the ignition location and prompt notification of responding authorities. The shorter the length of time between fire start and fire detection, the higher the probability of a successful initial attack. In the past, fires were commonly spotted and reported by personnel at staffed fire lookout towers. Today there are various methods of detection and new technologies available such as the use of sensors, cameras, and satellites.

In California and Oregon, there has been an increase in detection camera installations at fire lookouts that were historically staffed. Fire size at the time of detection by cameras generally scales with distance from the camera. With cameras, fires can be detected at much smaller sizes than are possible with the human eye alone. The Oregon Department of Forestry (ODF) reports that it is possible for a camera to detect fires on the order of 1/100th of an acre within 10 miles. Beyond 10 miles, cameras can typically detect fires at 1/10th of an acre.

Existing fire detection resources and the proposed post-restoration resources provided in the Klamath River Basin are discussed in detail in the FMP and are summarized here. A viewshed analysis identifies areas on Earth's surface that are visible from a specific location [20, 21] and is used in this work to:

1. Determine if the proposed post-restoration fire detection resources provide adequate coverage of the project area within the Klamath River Basin, and
2. Quantify the change in detection effectiveness between pre- and post-restoration schemes.

4.4.1 Existing fire detection scheme

As described in the FMP, there are four existing lookout towers that are used as surveillance vantage points for fire detection in the project area of the Klamath Basin and one that has been decommissioned. Three of these towers are in the ODF South West Oregon or Klamath Lake jurisdiction and one tower is in the CAL FIRE Siskiyou Unit jurisdiction. Two of the ODF lookouts are equipped with fire detection video camera systems, while the remaining two lookouts are staffed with fire service personnel during fire season. See Table 2 and Figure 23 for the locations and specifications of each of the four existing lookouts.

Table 2. Existing lookouts for fire surveillance in the Klamath Basin.

Tower Name/Location	Elevation (ft)	Tower Height¹ (ft)	Longitude	Latitude	Camera System
Paradise Craggy, CA	4,890	6	-122.54669	41.81476	No
Parker Mountain, OR	5,165	50	-122.27865	42.10527	No
Chase Mountain, OR	6,349	20	-121.99415	42.09461	Yes
Soda Mountain, OR	6,049	10	-122.47882	42.06447	Yes

¹ Tower heights were determined from online resources [22-25]




Figure 23. Existing lookouts for fire surveillance in the Klamath Basin.

4.4.2 Post-restoration fire detection scheme

The post-restoration fire detection scheme uses a Monitored Detection System (MDS) consisting of five lookout towers equipped with video surveillance cameras for around-the-clock, remote fire monitoring. The MDS technology transmits high definition video and images from cameras to an integrated Geographic Information System (GIS) platform that is monitored by dedicated staff. The software that enables this integration is EnviroVision Solutions (EVS) ForestWatch [26]. This software also enables triangulation of the fire location if more than one camera captures the fire.

The cameras that are recommended by EVS for use with the ForestWatch system are industrial Pelco cameras that can automatically rotate 360°, have an auto-detection surveillance distance of up to 12.4 miles (20 kilometers), and can be manually and remotely controlled. The infrared and near-infrared capabilities allow the cameras to see through haze and nighttime conditions.

The MDS cameras will be provided at Parker Mountain and Paradise Craggy so that each of the four existing lookouts in the Klamath Basin has a camera. Additionally, one new tower will be sited on Eagle Rock Mountain, CA. A sensitivity study of the viewshed at varying tower heights and location coordinates was conducted to determine optimal siting for the Eagle Rock camera. A camera will also be placed on an existing tower on Mt. Ashland. The post-restoration fire detection scheme is shown in Figure 24 and presented in Table 3 with changes from the existing scheme highlighted in gray.

Table 3. Post-restoration MDS camera locations for fire surveillance in the Klamath Basin.

Tower Name/Location	Elevation (ft)	Tower Height¹ (ft)	Longitude	Latitude	Camera System
Paradise Craggy, CA	4,890	6	-122.54669	41.81476	Yes
Parker Mountain, OR	5,165	50	-122.27865	42.10527	Yes
Chase Mountain, OR	6,349	20	-121.99415	42.09461	Yes
Soda Mountain, OR	6,049	10	-122.47882	42.06447	Yes
Eagle Rock ² , CA	6,970	10	-122.24138	41.87664	Yes
Mount Ashland, OR	7,533	10	-122.71688	42.08073	Yes

¹ Tower heights were determined from online resources [22-25]

² This tower is not yet constructed. The elevation and location coordinates were approximated.




Figure 24. Post-restoration MDS camera locations for fire surveillance.

4.4.3 Detection coverage viewshed analysis

A viewshed analysis was conducted of the existing and planned detection schemes to assess and compare fire detection coverage of the Klamath Basin both pre- and post-restoration. The inputs for the analysis are given in Table 4 and explained below. The results and limitations of the analysis are discussed in the following subsections.

Table 4. Viewshed analysis inputs for the pre- and post-restoration fire detection schemes.

Detection Scheme	Monitoring Location	Camera System	Radius of Visibility (mi)	Observer Height ¹ (ft)	Target Height (ft)
Pre-restoration	Paradise Craggy Tower	No	7	6	0, 100, 500
	Parker Mountain Tower	No	7	50	0, 100, 500
	Chase Mountain Tower	Yes	12	20	0, 100, 500
	Soda Mountain Tower	Yes	12	10	0, 100, 500
Post-restoration	Paradise Craggy Tower	Yes	12	6	0, 100, 500
	Parker Mountain Tower	Yes	12	50	0, 100, 500
	Chase Mountain Tower	Yes	12	20	0, 100, 500
	Soda Mountain Tower	Yes	12	10	0, 100, 500
	Eagle Rock Tower	Yes	12	10	0, 100, 500
	Mount Ashland Tower	Yes	12	10	0, 100, 500

¹ Observer height is relative to the ground and assumed to be the same height as the tower.


In the pre-restoration scheme, a horizontal 7-mile radius of visibility for human eye detection is applied for the two tower locations that are not equipped with a camera system at present [27]. Based on the EVS camera specification, which states a 12.4-mile maximum surveillance distance [26], a rounded value of 12 miles was applied for the cameras' radius of visibility in both pre- and post-restoration schemes. This analysis includes the effect of earth curvature on visibility but does not include visibility obscuration due to haze or smoke in the lower atmosphere. The human eye and camera "observer" heights are relative to the ground elevation and assumed to be at the same height of the towers listed in Table 3.

Three iterations of the analysis were conducted to determine the visibility to specified target heights of 0 feet (ground level), 100 feet above the ground (at or above canopy height), and 500 feet (clear of the canopy and low hills). These values were chosen based on a literature review of similar analyses [28-29]. The non-zero target heights represent a smoke layer above ground that follows the contour of the terrain. This is factored in the analysis because both the human eye and the ForestWatch system will detect smoke signatures before flaming fire at the ground level. As the smoke rises, it typically needs to clear interference from terrain and vegetation to be detected [28], as shown in Figure 25. The ability for detection of smoke plumes at lower or near-surface heights enables faster alerting and initiation of suppressing action. It is further beneficial for the detection systems to achieve visibility coverage extending beyond the lateral boundary of the desired detection coverage area because external fires may encroach into the Klamath Basin. For this reason it is also important to monitor and provide coverage of regions adjacent to the Klamath Basin that fall outside the ASE [28].




Figure 25. Example of smoke plume detection from a camera in the ALERTwildfire network [30].


The post-restoration detection viewshed results are first presented to illustrate coverage provided by the cameras as well as “blind spots” where no camera has visibility to the specified target height (Figure 26). The green areas indicate the target height is visible to one camera; the yellow areas indicate two of the six cameras can view the location; and orange indicates three cameras. There are no locations that are simultaneously visible to more than four cameras, at least up to a target height of 500 feet as analyzed here. The results are displayed with an overlay of the ASE as this is understood to comprise the area of operation for CAL FIRE’s aerial suppression equipment. With the planned removal of the four dams, this area was identified as a concern by CAL FIRE as they perceived the potential for the fire risk to increase following restoration of the Klamath River to its natural watercourse.



(a)



(b)



(c)

Figure 26. Post-restoration fire detection camera viewshed, results at target height of (a) 0 feet, (b) 100 feet, and (c) 500 feet above ground surface, overlaid with the aerial suppression extent.

The total land area included in the ASE boundary is approximately 570 square miles. By performing geospatial analytics on the viewshed raster (image) results files, the proposed post-restoration fire detection scheme was determined to provide 92% coverage of the protected area in the ASE boundary at a target height of 500 feet, 74% coverage at a target height of 100 feet, and 54% coverage at the ground surface. Coverage extends into surrounding areas of interest up to 12 miles in each cardinal direction and beyond the perimeter of the ASE. Additionally, roughly 20% of the detection coverage area is visible to multiple cameras at a target height of 100 feet, allowing for triangulation in the early stages of fire growth.

Table 5. Percent coverage of ASE¹.

Pre-restoration viewshed				Post-restoration viewshed		
Target height	0 feet	100 feet	500 feet	0 feet	100 feet	500 feet
1 camera	33.4%	45.3%	56.7%	45.9%	51.0%	45.6%
2 cameras	1.90%	5.58%	9.63%	8.18%	21.2%	39.8%
3 cameras	0	0	0	0.58%	2.44%	7.31%
Total coverage:	35.3%	50.9%	66.3%	54.7%	74.6%	92.7%

¹ASE total area 568.9 sq. mi

Figure 27 shows comparative views of the coverage between the existing and post-restoration detection resources. The first column is at a target height of 0 feet, the second column is at a target height of 100 feet, and the third column is at a target height of 500 feet. The pink areas in images 3a, 3b, and 3c highlight the increase in detection coverage provided by the post-restoration resources. The pink areas in images 4a, 4b, and 4c highlight the increase in triangulated detection coverage provided by the post-restoration resources.

The post-restoration detection scheme provides a 39% increase in detection coverage at 500 feet target height, a 45% increase at 100 feet target height, and a 54% increase at ground surface for the ASE. Triangulation coverage of the protected area is increased significantly under the post-restoration detection scheme at each target height.




Figure 27. Comparative views of the existing resources viewshed (1a, 1b, 1c) and post-restoration resources viewshed (2a, 2b, 2c) at target heights of 0 feet, 100 feet, and 500 feet, respectively from left to right. The pink areas (3a, 3b, 3c) highlight the increased coverage provided by the post-restoration resources, contrast to the existing resources coverage indicated in white. The pink areas (4a, 4b, 4c) highlight the increase in triangulated area coverage provided by the post-restoration resources, contrast to the existing resources triangulation coverage in white.

4.4.4 Limitations of viewshed analysis

The limitations of a viewshed analysis, especially in the context of understanding detection effectiveness, are enumerated below:

1. The analysis was reliant on the assumptions of the camera locations, heights, and radius of visibility. These assumptions were investigated by manual adjustment of camera locations based on satellite imagery of tower locations and by validation of the Eagle Rock camera height through a manual sensitivity study.
2. The viewshed analysis does not account for visibility obscuration due to possible haze or smoke. Note, however, that the EVS-recommended cameras specifications include the ability to see through haze and smoke.
3. The viewshed analysis is based on tower locations that already have a fire lookout and would therefore present minimal implementation expenses while providing a significant increase in MDS coverage. These locations are not fixed and may be changed after conferring with ODF and CAL FIRE about optimal siting.
4. Using a viewshed analysis with a smoke plume as the target is more representative of wildland fire detection than using the ground level as the target. It is much more common for fires to be reported because someone saw smoke than because someone saw physical flames. In this analysis, a smoke plume viewshed was approximated by using a target height of 500 ft. This height would allow the smoke to clear intervening terrain and vegetation and be “seen” by the detection network and is similar to elevations used in the literature. However, smoke plume detection has inherent uncertainties due to atmospheric stability and wind, both of which influence how the fire and subsequent smoke plume grow. Because of these uncertainties, deduction of fire size from smoke plume alone becomes intractable.

4.4.5 Satellite-based fire detection technology

Several commercial and non-commercial satellite-based fire detection technologies were evaluated for feasibility of implementation as an option for supplementary coverage of the Klamath Basin. The available technologies typically involve an algorithmic system that uses artificial intelligence (AI) and machine learning techniques to mine and manipulate publicly available, remote-sensed data. The systems can produce fire detection alerts or maps in near real-time to support end-user decision-making. Detections may be verified by various means to reduce omissions and commissions, for example, such as with “ground truth” validation from high-resolution (3-5 meters) imagery acquired at least once per day. Satellite-based technology provides several benefits over other detection methods, including fewer false positives, higher reliability, better precision, and earlier detection.

One of the available, non-commercial satellite-based options is the fire detection and characterization (FDC) data product from NOAA and UW-Madison [31, 32]. The algorithm ingests data from the latest GOES-R Series satellites which are equipped with an Advance Baseline Imager that has significantly improved resolution and fidelity of fire detections from previous GOES sensors. Lag time for the data between collection and post-processing is 4.4 minutes at a spatial resolution of 2 kilometers [32]. Because of this, the product generally still relies on data from additional satellites (with greater latency) for accurate fire characterization. The GOES-EFD

(Early Fire Detection) product [33] is another non-commercial option that is an improvement to the existing FDC product and is anticipated to be available in the next few years. Development of the product is a collaborative effort led by UC Davis. Initial validation stages of the EFD prototype are complete and have shown promising results for earlier detections with fewer false alarms, and at least 4× more precise geographic location of ignitions, as compared to similar existing products [34].

Initial testing of the commercial technologies has shown that satellite-based fire detection may detect fire events on average approximately 10 minutes after it was first reported by civilians via phone in populated areas during the day. However, for night-time detections, particularly in areas with low population density, fires may be detected by satellites more than an hour before detected manually. The two commercial offerings that were evaluated come at high cost on the order of \$100,000+ per year for solutions-based systems, or \$5,000 per month for subscription-based services. Since they offer minimal improvement in daytime detection effectiveness relative to camera technology, commercial satellite-based options are currently not recommended for implementation at this time.

The marked improvement in recent development of both commercial and non-commercial options for satellite-based fire detection is made possible by technological advancement in the newly released GOES-R satellites and sensor equipment. In the coming years, it is expected that the GOES-EFD product will be publicly available. Our recommendation is to monitor the release of this fire detection technology and implement the product at that time for enhanced coverage of the Klamath Basin.

4.5 Change in initial attack probability of containment

Approximately 90% of wildland fires in the U.S. are suppressed in the first 48 hours. The other 10% are not successfully suppressed initially usually because of an extreme but rare combination of fuel conditions and fire weather and can become campaign fires such as the Klamathon Fire.

The “10 AM policy”, *i.e.* fires were to be under control by 10:00 am the following day, which guided Forest Service wildfire suppression until the mid-1970s made sense in the short term as wildfires are much easier and cheaper to suppress when they are small [35]. The federal government has studied the atmospheric conditions conducive to fires escaping initial attack in depth and determined that it is unrealistic to keep increasing the suppression capacity nationally beyond a certain budgetary level. On average, 98.9% of wildfires on public land in the U.S. are suppressed before they exceed 120 hectares but larger fires account for 97.5% of all suppression costs [36]. Put differently, no matter how many resources are mobilized on a fire, fires occurring when fire weather indices are above their 90th percentile values may not be successfully suppressed in the first 48 hours.

Traditionally the federal fire budget was based on the most efficient level (MEL) of funding for suppression forces. Analysis showed that funding up to 90% of the MEL was cost-effective, but additional funding to try to catch that last 10% of fires was not cost-effective because the highest 10% of fires are usually the longest and most severe project fires. The federal government determined that it could not afford to staff forces at any level higher than the identified 90% MEL and therefore the federal budget is typically at or near this 90th percentile level.

The few fires that escape initial attack, such as the Klamathon Fire, are the ones that burn the most area. Success in initial attack is dependent on several factors including weather conditions, fire detection time, fire service arrival time, fire spread rates, fire line production rate, resource drawdown, and budget constraints. Recognizing the importance and effectiveness of the initial attack phase, CAL FIRE has a stated suppression acreage goal for all fires is 10 acres. ODF has a similar qualitative suppression goal of keeping fires as small as possible.

Due to the significant impact initial attack success or failure has on fire growth and intensity, numerous studies have been conducted assessing initial attack effectiveness. As proposed Keating *et al.* [37], for the purposes of assessing initial attack effectiveness, new ignitions can be classified into three categories:

- Category A: Fires likely to remain small regardless of initial attack due to low spread rate or marginal burning conditions
- Category B: Fires that can be prevented from becoming large through initial attack
- Category C: Fires that will become large independent of initial attack due to rapid spread rate or spotting

Note that these categories are different from federal fire size class codes [38] wherein fires are categorized Class A through L based on final size. Since initial attack success rate is close to 100% for Category A fires and close to 0% for Category C fires, of greatest interest here is Category B fires and understanding how early detection may affect initial attack effectiveness.

Several approaches have been applied to model initial attack effectiveness. Fried and Fried [39] developed a technique for simulating fire containment based on the balance between containment line production rate and fire perimeter growth. This has become the basis for the CONTAIN module in the BehavePlus fire modeling system [40]. Rodrigues *et al.* [29] showed the probability of initial attack success can be calculated as a combination of time to detection, travel time, fire spread potential, and available resources. Reimer *et al.* [41] investigated suppression effectiveness by pairing burn probability and containment probability calculations.

The approach used here to quantify initial attack probability of containment is based on the analysis of Hirsch *et al.* [42] who leveraged expert judgment to quantify initial attack effectiveness as a function of fire size and head fire fireline intensity, *i.e.* intensity at the main advancing fire front, at the time of initial attack commencement. Hirsch *et al.* [42] developed an expression for probability of containment (*POC*) as a function of fire size (*A*) and fireline intensity (*I*) which is given as Equation 1:

$$POC = \frac{E}{1+E} \quad (1a)$$

$$\ln E = 4.6835 - 0.7043 \times A - 0.00041 \times I - 0.000052 \times A \times I \quad (1b)$$

In Equation 1, *A* has units of hectares and *I* has units of kW/m. Since trends in probability of containment are not immediately apparent upon inspection of Equation 1, probability of containment calculated from Equation 1 is tabulated in Table 6 as a function of fire size and head fire fireline intensity at the time of initial attack. Although the qualitative trends in Table 6 are

logical, *i.e.* containment probability increases with smaller fires, lower intensity, or both, the Hirsch *et al.* [42] study was based on expert opinion from Canadian firefighters so differences in suppression tactics between Canadian and U.S. agencies are not reflected in Table 6.

Table 6. Probability of containment as a function of fire size and head fire fireline intensity at commencement of initial attack from Equation 1 [42].

Fire size (hectares)	10	77%	64%	49%	34%	22%	13%	8%	4%	2%	1%
	9	82%	71%	58%	43%	29%	19%	11%	6%	4%	2%
	8	86%	78%	66%	52%	38%	26%	16%	10%	6%	3%
	7	89%	83%	73%	61%	48%	34%	23%	15%	9%	5%
	6	92%	87%	80%	70%	57%	44%	31%	21%	14%	8%
	5	94%	90%	85%	77%	66%	54%	41%	30%	20%	13%
	4	95%	93%	89%	83%	74%	64%	52%	40%	29%	20%
	3	97%	95%	92%	87%	81%	73%	63%	51%	39%	29%
	2	97%	96%	94%	91%	86%	80%	72%	62%	51%	40%
	1	98%	97%	96%	94%	90%	86%	80%	72%	63%	52%
		1000	2000	3000	4000	5000	6000	7000	8000	9000	10000
Fireline Intensity (kW/m)											

In order to use Equation 1 (or Table 6), for each ignition location the time of initial attack commencement relative to the time of fire ignition (t_{ign}) must be established. This can be viewed as the sum of fire detection time (t_d), report time (t_r), and travel time (t_t):

$$t_{initial\ attack} - t_{ign} = t_d + t_r + t_t \quad (2)$$

Of the terms on the right hand side of Equation 2, fire detection time and report time are potentially reduced by deployment of fire detection cameras as described in Section 4.4.

In conclusion, probability of containment on initial attack will remain unchanged or increase because:

1. There is no reduction in water availability for firefighting purposes (Section 4.2),
2. Fire detection and reporting times in areas covered by the proposed MDS will likely decrease and will remain unchanged in areas not covered by the proposed MDS, and
3. Travel time by responding units will remain unchanged or decrease.

4.6 Change in extended attack efficacy

The amount of water that is available for initial and extended attack, *i.e.* fires lasting over 48 hours that require staffing and shift changes, will remain unchanged. However, the ease with which water can be retrieved will change slightly. Rather than having access to large, open reservoirs constituting minimal concern for both fixed wing and rotary pilots, the identified river pools will require slightly more time and skill for rotary winged aircraft to retrieve water. Fixed wing aircraft, like the CL415 Bombardier, require at least three-quarters of a mile of quasi-straight water with a minimum depth of six feet to scoop. The pools do alter the amount of risk to helicopter pilots as the maneuver requires hovering to drop in and out of the canyon. The narrowness and variable winds induced in the river canyon increases the difficulty for the pilot. Additionally, hovering to fill buckets as well as a slight increase in haul time when returning to fires will cause an overall increase in haul time.


5.0 EFFECT OF RESERVOIR DEWATERING AND EARLY DETECTION ON LANDSCAPE-SCALE BURN PROBABILITY

As described in Section 2.3, wildland fire hazard/risk assessment using fire behavior modeling has recently seen increased usage due in part to more powerful computational resources, improved fire models, and readily available geospatial input data. In this work, we apply ELMFIRE [1] (Eulerian Level Set Model for Fire Spread) to quantify landscape-scale burn probability.


5.1 Monte-Carlo fire spread model: ELMFIRE

ELMFIRE's computational engine is similar to other two-dimensional fire simulators such as FARSITE [6] or PHOENIX RapidFire [10-14] in that it calculates surface fire spread rate using the Rothermel surface spread model [43, 44], assumes that each point along the fire front behaves as an independent elliptical wavelet [45] with length to breadth ratio determined semi-empirically [6, 46], and simulates transition from surface to crown fire using the Van Wagner criterion [47] (with passive/active crown fire spread rates calculated from Cruz *et al.* [48]). ELMFIRE tracks the fire front using a narrow band level set method [49], a numerical technique for tracking curved surfaces on a regular grid.

To demonstrate how ELMFIRE simulates fire spread, Figure 28 shows 24-hours of fire progression from an individual ignition site. The black contour lines in Figure 28a represent fire front position at 2-hour intervals. Figure 28a also shows which parts of the burned area experienced surface fire (blue), passive crown fire (green), or active crown fire (red). Figure 28b similarly shows fire perimeter contours and flame length variation within the fire perimeter. Flame length (the distance measured from the average flame tip to the middle of the flaming zone at the base of the fire; measured on a slant when the flames are tilted due to effects of wind and slope [50]) is highest in areas that burn as heading fires or that experience crown fire, and lowest in areas that burn as a flanking or backing fire or as a surface fire. In this example, fire area after 24 hours of spread is approximately 560 acres.



(a)



(b)

Figure 28. Sample ELMFIRE fire spread simulation for individual fire ignition. (a) Fire type (surface fire, passive crown fire, or active crown fire). (b) Flame length.

5.2 Fuels

Fuel and topography layers in the analysis area were obtained from the LANDFIRE Remap (LANDFIRE 2.0.0) database [51-52] at a resolution of 30 m. Topography layers include elevation, slope, and aspect. Fuel layers include surface fuel model (in the Scott and Burgan 40 system [53]), canopy height, canopy cover, canopy base height, and canopy bulk density.

5.2.1 *Pre-restoration*

Existing vegetation rasters from LANDFIRE Remap were assessed for the types of vegetation expected in the areas surrounding the reservoirs (Figure 29). The numerical values of the fuel types do not provide insight into fire behavior, but the descriptions provided by Scott and Burgan [53] do. The major fuel types found around the Iron Gate and Copco reservoirs are described as follows:

- 91 (Urban/Developed) – consists of urban and suburban development that does not support wildland fire spread.
- 98 (Open Water) – land covered by open bodies of water such as lakes and rivers.
- 99 (Bare Ground) – land devoid of sufficient fuel to support wildland fire spread such as deserts, rock outcroppings, and beaches.
- 102 (Low Load, Dry Climate Grass) – primary carrier of fire is semi-continuous grass.
- 121 (Low Load, Dry Climate Grass-Shrub) – primary carrier of fire is grasses and small (1 ft.) shrubs together with moderate fire spread rate.
- 122 (Moderate Load, Dry Climate Grass-Shrub) – primary carrier of fire is grass and medium (1-3 ft.) shrubs together with high fire spread rate.
- 165 (Very High Load, Dry Climate Timber-Shrub) – primary carrier is heavy forest litter with a small tree or shrub understory with moderate fire spread rate.
- 186 (Moderate Load Broadleaf Litter) – primary carrier is moderate load broadleaf litter with moderate fire spread rate.




Figure 29. Iron Gate and Copco surface fuel (pre-restoration).

5.2.2 Post-restoration

Vegetation re-growth after dam removal was estimated using historical imagery and existing vegetation types surrounding the areas to be reclaimed. Existing vegetation typically is a good surrogate for expected re-growth in an area of similar soils, *etc.* The Fuels Classification and Characterization System (FCCS) [54] was utilized as well as LANDFIRE data [51-52] for the analysis area (Figure 30, Figure 31). The 30 m resolution LANDFIRE vegetation type data was compared to the FCCS existing vegetation to verify the potential vegetation for the site.




Figure 30. FCCS existing vegetation types.




Figure 31. LANDFIRE 2.0.0 (Remap) existing vegetation types.

Initial re-growth is assumed to be in the grass-forb stage for up to the first ten years after the dams are removed. An example of post-restoration fuels is shown in Figure 32 with reclaimed land as fuel model 101 (short grass). Simulations of fire growth and spread assumed this regrowth condition.

The second decade in grass dominated areas will remain grass. In shrub-chaparral areas the second ten-year increment (10-20 years) will move into a shrub-grass and in the third ten-year increment the vegetation will return to a shrub-chaparral vegetation type, such as the Chamise chaparral shrubland adjacent to the Iron Gate Dam area. Grass-forb and chaparral-shrub vegetation types have a relatively short developmental cycle and are considered mature within 30 years of re-establishment.

After the first ten-year increment forested areas will move into a shrub-grass type for the next ten years, followed by a timber-grass type as reforestation grows above the initial grass-shrub stages. These stages will be followed by a timber type that will mimic the existing timber type in the immediate area, such as the Jeffery pine, Ponderosa pine, and Douglas-fir forests around the Copco I and II site.

Once the revegetated timber areas reach the fifth ten-year increment it is assumed that they will be similar in type to the surrounding areas of vegetation but will not be in a similar age class or stage of development.




Figure 32. Iron Gate and Copco surface fuels post-restoration.

5.3 Fire weather

The general approach to developing requisite wind and weather inputs involves using the North American Regional Reanalysis (NARR) dataset [55] in conjunction with a fire weather filter to identify days of historic weather significance. The Weather Research and Forecasting (WRF) model is then used to generate wind and weather fields only for those days identified as being significant from a fire weather perspective.

The NARR dataset is maintained by the National Centers for Environmental Prediction, the National Weather Service, and the National Oceanic and Atmospheric Administration. It is a gridded meteorological dataset that provides a “snapshot” of the atmosphere every 3 hours at approximately 32 km resolution. Being a reanalysis, NARR is a hybrid of weather modeling and meteorological observations (surface observations of temperature, relative humidity, wind speed/direction, and precipitation, weather balloon observations of wind speed/direction and atmospheric, sea surface temperatures from buoys, satellite imagery for cloud cover and precipitable water, *etc.*). Ingested data include not only surface (meaning near ground level) quantities but also upper atmosphere quantities as well. The NARR dataset is available from 1979 when modern satellites first became available to current day, with a lag of a few weeks.

Although NARR’s 32 km resolution is too coarse to be useful for fire spread modeling purposes, it can be used to identify historical fire weather days to be recreated at higher resolution using WRF. The basic idea is to determine dates for each 32 km by 32 km NARR pixel in the analysis area where the most severe fire weather conditions have occurred between 1979 and 2018. The primary advantage of identifying historical fire weather events using reanalysis data, instead of surface (weather station) observations, is that the NARR dataset is both spatially and temporally uniform whereas point observations are not.

5.3.1 Methodology

The first step to identify historical fire weather days is selection of a single criterion that can be used to identify the most severe fire weather conditions in the NARR dataset. While there are many possibilities, a modification to the Fosberg Fire Weather Index (FFWI) [56] was selected. FFWI combines temperature, relative humidity, and wind speed into a single index ranging from 0 to 100, with 100 corresponding to a wind speed of 30 mph and fine fuel moisture content of 0%. The FFWI formula is presented as Equation 3:

$$FFWI = \eta \sqrt{1 + U^2} \quad (3)$$

where U is the 20-ft wind speed in miles per hour and η is a function of equilibrium moisture content, M_{eq} :

$$\eta = 1 - 2\left(\frac{M_{eq}}{30}\right) + 1.5\left(\frac{M_{eq}}{30}\right)^2 - 0.5\left(\frac{M_{eq}}{30}\right)^3 \quad (4)$$

In Equation 4, M_{eq} is calculated as [57, 58]:

$$M_{eq} = \begin{cases} 0.03 + 0.28 \times RH - 0.00058 \times RH \times T & \text{for } RH < 10\% \\ 2.23 + 0.16 \times RH - 0.0148 \times T & \text{for } 10 \leq RH < 50\% \\ 21.1 - 0.4944 \times RH + 0.00557 \times RH^2 - 0.00035 \times RH \times T & \text{for } RH \geq 50\% \end{cases} \quad (5)$$

where RH is relative humidity in percent and T is temperature in °F.

FFWI is very sensitive to wind speed, and less sensitive to relative humidity and temperature. For example, FFWI is 80 for a wind speed of 50 mph and an equilibrium moisture content of 10%, but only 73 for a wind speed of 25 mph and an equilibrium moisture content of 2%. Ignition of a wildland fire and growth to threatening scales may be more likely under the latter conditions but spread rates for an already established wildland fire could be higher under the former conditions.

It has been found that using a Fosberg Fire Weather Index (FFWI) could result in “off season” (generally, during the winter, *i.e.* after significant rains) days being falsely identified as fire weather days. To avoid these problems, a Modified Fosberg Fire Weather Index (MFFWI) is used in this work to identify wind events that occur simultaneously with low relative humidities and high temperatures. MFFWI is defined as follows:

$$MFFWI = FFWI \times \frac{P_{ign}}{100} \quad (6)$$

where P_{ign} is Schroeder’s ember ignition probability [59] as given in Table 7 as a function of fuel temperature and fine fuel moisture content. The data were originally published [59] with temperatures in degrees Fahrenheit and this convention is retained here. It is seen that the ember ignition probability is strongly sensitive to moisture content, and less sensitive to temperature.

Table 7. Ignition probability by woody embers/firebrands as tabulated by Schroeder [59].

Fuel Temp (F)	Fine Fuel Moisture Content (%)														
	1.5	2.0	2.5	3.0	4.0	5.0	6.0	7-8	9-10	11-12	13-16	17-20	21-25	26-30	>30
30-39	87	80	74	69	59	51	43	34	25	17	10	4	1	0	0
40-49	89	83	77	71	61	53	45	36	26	18	11	5	1	0	0
50-59	92	85	79	73	63	54	47	37	27	20	11	5	2	0	0
60-69	94	88	81	76	65	56	49	39	29	21	12	6	2	0	0
70-79	97	90	84	78	68	59	51	41	30	22	13	6	2	0	0
80-89	100	93	87	81	70	61	53	42	31	23	14	7	2	1	0
90-99	100	96	90	84	73	63	55	44	33	24	15	7	3	1	0
100-109	100	99	93	86	75	66	57	46	35	26	16	8	3	1	0
110-119	100	100	96	89	78	68	59	48	36	27	17	9	3	1	0
120-129	100	100	99	93	81	71	62	51	38	29	18	9	4	1	0
130-139	100	100	100	96	84	74	65	53	40	30	20	10	4	1	0
140-149	100	100	100	99	87	77	67	55	42	32	21	11	5	2	0
150-159	100	100	100	100	90	80	70	58	45	34	22	12	5	2	0

First, 10 m wind components, 2 m temperature, and 2 m relative humidity are extracted from the NARR dataset and converted to GeoTiff files at 3-hour intervals from 1979 to 2019 (41 years). 10 m wind components were used to calculate 20 ft wind speed, in mph, and wind azimuth, in degrees. FFWI and MFFWI were then calculated at 3-hour intervals using the formulas presented above. Because rapidly spreading fires often cause significant damage in the first ~6 hours of a burn period, MFFWI values were averaged over a 6-hour period.

Next, the 6-hr average files were processed to determine the maximum 6-hr average MFFWI that occurred on a particular calendar day. Finally, for each 32 km by 32 km pixel in the NARR dataset, the ~15,000 (41 yr × 365 days/yr) daily maximum MFFWI values were sorted from high to low, with the date carried along and sorted analogously. These were then written to two (MFFWI and date) stacked GeoTiff rasters such that the first band contains the highest MFFWI value over 40 years and the date corresponding to the highest MFFWI. The second band contains the second highest MFFWI and date corresponding to that MFFWI, and so on.

With historical weather dates now identified, a 41-year (1979-2019) fire weather climatology was developed using the WRF model to recreate historical days of fire weather significance across the analysis area. Approximately 200 days were included in this climatology, but for fire modeling purposes this data set was distilled to the most severe 50 days for a given location within the analysis area. High-resolution (1.2 km) hourly gridded fields of relative humidity, temperature, dead fuel moisture, and wind speed/direction were extracted from this analysis and provided as input to a Monte-Carlo-based fire modeling analysis.

5.4 Stochastic selection of ignition locations and wind/weather conditions

In order to capture a range of potential ignition locations, ignitions are distributed randomly (but not uniformly) within the analysis area shown previously as Figure 1. Modeled ignition density, meaning the number of ignitions per unit area, varies spatially across the analysis area in a pattern that mimics past fire occurrence. To accomplish this, the Figure 10 ignition density map from all fire causes is read into ELMFIRE so that ignitions can be distributed accordingly.

For each random ignition location, the weather stream is also selected randomly from the 50 most severe fire weather days (based on MFFWI) for that ignition location. Six hours of weather data, corresponding to approximately one burn period, are extracted from the fire weather stream, and provided as input to the fire spread simulations.

5.5 Quantification of dewatering impact on modeled landscape-scale burn probability

Burn probability is used here to quantify how dewatering and conversion of ~1,000 acres of water affects fire potential. Burn probability is the likelihood that a point on the landscape will be impacted by fire during a given period, usually one year (*i.e.*, annual burn probability). However, in this work burn probability is taken as the number of times a pixel on the landscape burned in a model run divided by the total number of model runs to facilitate comparison between different hypothetical scenarios.

Burn probability is determined by running ELMFIRE with stochastic ignition locations and weather data (Section 5.4). Separate runs were conducted with pre-restoration and post-restoration fuel layers. In both cases, initial attack and fire suppression were disabled, so the resultant burn probability figures do not reflect any effect that early detection and suppression may have on probability of containment.

Figure 33 shows the difference between modeled pre-restoration and post-restoration burn probability. The color-scale is such that areas in yellow indicate no change in burn probability, areas in blues and greens indicate a reduction in burn probability (attributed to the

stochastic/random nature of this analysis), and areas in orange and red indicate an increase in burn probability (due to reservoir dewatering and/or the stochastic/random nature of this analysis). The primary region of change occurs in the reservoir basins where land previously covered by water was converted to vegetation. Within the aerial suppression extent, modeled mean burn probability increases by less than 1% for a range of post-restoration fuels (short grass, grass/shrub, and timber understory) as shown in Table 8.

Table 8. Changed in modeled mean burn probability within aerial suppression extent from pre-restoration to post-restoration fuels.

Fuel	Mean burn probability	Relative change
Pre-restoration	7.73×10^{-6}	-
Post-restoration (short grass / FM101)	7.80×10^{-6}	0.90%
Post-restoration (grass / shrub FM 122)	7.73×10^{-6}	0.00%
Post-restoration (timber / FM 165)	7.73×10^{-6}	0.01%




Figure 33. Difference between modeled pre-restoration and post-restoration burn probability.

5.6 Quantification of early detection time impact on modeled landscape-scale burn probability

While the simulations discussed in Section 5.5 are intended to quantify how creation of additional burnable landmass affects modeled landscape-scale burn probability, simulations in the current section are intended to address how reduction in detection and travel times as discussed in Section 4.5 impact initial attack success rate and landscape-scale burn probability.

When initial attack modelling is enabled in ELMFIRE, for each combination of ignition location and time of ignition the following occurs at the time of initial attack commencement relative to time of ignition ($t_{initial\ attack} - t_{ign}$):

1. Fire size is calculated
2. Head fire fireline intensity is calculate as the maximum fireline intensity across all burning pixels
3. Equation 1 is used to calculate probability of containment from fire size and head fire fireline intensity
4. A random number between 0 and 1 is generated. If this random number is less than the probability of containment, then fire is considered contained and fire growth is halted. If this random number is greater than probability of containment, fire growth continues unchecked.

This allows ELMFIRE to quantify how changes in detection time, *e.g.* due to installation of fire detection cameras, affects landscape-scale burn probability. Since it has already been shown in Section 4.5 that initial attack effectiveness will increase or remain unchanged after dewatering and implementation of the FMP, a range of initial attack times from 5 minutes to 30 minutes was modeled. Figure 34 plots modeled mean burn probability within the aerial suppression extent (Figure 2) as a function of initial attack time. It is seen from the plot that small reductions in time of initial attack (*e.g.*, from 30 minutes to 25 minutes) reduce modeled mean burn probability by a an amount that is greater than any increase in burn probability associated with dewatering.




Figure 34. Change in modeled mean burn probability within aerial suppression extent as a function of initial attack time relative to fire ignition.

6.0 CONCLUSIONS

The salient conclusions drawn from the analyses presented in this report are:

1. There will be no effective decrease in water availability for firefighting purposes following reservoir drawdown due to implementation of measures described in the Fire Management Plan [3]. The ease with which helicopters and fixed wing aircraft can access the reservoirs will change. Helicopters will have to hover and drop/raise in and out of dip sites potentially increasing the overall haul time depending upon pool/river width and hazards in the area. However, the amount of water available will not be affected by dam removal.
2. Cameras will provide an effective means of early fire detection in the project area. Detection of most fires is expected at fire sizes between 0.01 acres and 0.1 acres. The post-restoration detection scheme provides a minimum 39% increase in detection coverage at the target heights used for the ASE. Triangulation coverage of the protected area is increased significantly under the post-restoration detection scheme at each target height.
3. Dewatering of the project reservoirs and reclamation of approximately 1,000 acres of land increases modeled mean burn probability by a negligible amount ($< 1\%$ in the aerial suppression extent).
4. Probability of containment on initial attack shows that early detection associated with installation of fire detection cameras increases probability of containment and reduces burn probability. Small reductions in initial attack time after fire ignition (*e.g.*, from 30 minutes to 25 minutes) more than compensate for the modeled increase in burn probability, especially considering the relative increase in burn probability was $< 1\%$. For example, a reduction in average arrival time from 30 minutes to 25 minutes results in a 7% decrease in modeled mean burn probability within the ASE, and a reduction in average arrival time from 30 minutes to 20 minutes results in a 34% decrease in modeled mean burn probability within the ASE.

7.0 REFERENCES

- [1] Lautenberger, C., “Wildland Fire Modeling with an Eulerian Level Set Method and Automated Calibration,” *Fire Safety Journal* **62**: 289-298 (2013).
- [2] Lautenberger, C., “Mapping areas at elevated risk of large-scale structure loss using Monte-Carlo simulation and wildland fire modeling,” *Fire Safety Journal* **91**: 768 – 775 (2017).
- [3] Klamath River Renewal Corporation, “Fire Management Plan Appendix 01,” June 2020.
- [4] Vaillant, N.M., Ager, A.A., Anderson, J., and Miller, L., “ArcFuels User Guide and Tutorial: for Use with ArcGIS 9®,” United States Department of Agriculture Forest Service, Pacific Northwest Research Station, General Technical Report PNW-GTR-877 June 2013.
- [5] Vaillant, N.M., Ager, A.A., and Anderson, J., “ArcFuels10 System Overview,” United States Department of Agriculture Forest Service, Pacific Northwest Research Station, General Technical Report PNW-GTR-875, March 2013.
- [6] Finney, M.A., “FARSITE: Fire Area Simulator – Model Development and Evaluation,” United States Department of Agriculture Fore Service Rocky Mountain Research Station Research Paper RMRS-RP-4 Revised February 2004.
- [7] Finney, M. A., “An overview of FlamMap fire modeling capabilities,” in *Fuels Management--How to Measure Success*, Ed. P.L. Andrews and B.W. Butler, Portland, OR, 2006.
- [8] Keane, R.E., Drury, S.A., Karau, E.C., Hessburg, P.F., and Reynolds, K.M., “A Method for Mapping Fire Hazard and Risk Across Multiple Scales and its application in fire management,” *Ecological Modeling* **221**: 2-18 (2010).
- [9] Parisien, M.-A., Walker, G.R., Little, J.M., Simpson, B.N., Wang, X., and Perrakis, D.D.B., “Considerations for Modeling Burn Probability Across Landscapes with Steep Environmental Gradients: an Example from the Columbia Mountains, Canada,” *Natural Hazards* **66**: 439-462 (2013).
- [10] Tolhurst, K.G., Shields, B., and Chong, D., “Phoenix: development and application of a bushfire risk management tool,” *The Australian Journal of Emergency Management* **23**: 47–54 (2008).
- [11] Chong, D., Tolhurst, K., and Duff, T., “Incorporating Vertical Winds into PHOENIX RapidFire’s Ember Dispersal Model,” Technical Report, Bushfire CRC/University of Melbourne, 14 December 2012.
- [12] Chong, D., Tolhurst, K., and Duff, T., “PHOENIX RapidFire 4.0’s Convective Plume Model,” Technical Report, Bushfire CRC/University of Melbourne, 16 December 2012.
- [13] Chong, D., Tolhurst, K., and Duff, T., “PHOENIX RapidFire 4.0 Convection and Ember Dispersal Model,” Technical Report, Bushfire CRC/University of Melbourne, 16 December 2012.
- [14] Chong, D., Tolhurst, K., Duff, T., and Cirulis, B., “Sensitivity Analysis of PHOENIX RapidFire,” Technical Report, Bushfire CRC/University of Melbourne, 7 May 2013.
- [15] Short, Karen C. 2017. Spatial wildfire occurrence data for the United States, 1992-2015 [FPA_FOD_20170508]. 4th Edition. Fort Collins, CO: Forest Service Research Data Archive. <https://doi.org/10.2737/RDS-2013-0009.4>
- [16] Abatzoglou, J. T., Balch, J. K., Bradley, B. A., Kolden, C. A., “Human-related ignitions concurrent with high winds promote large wildfires across the USA,” *International Journal of Wildland Fire* **27**: 377-386 (2018).
- [17] <https://frap.fire.ca.gov/frap-projects/fire-perimeters/>

- [18] https://ftp.nifc.gov/public/incident_specific_data/
- [19] https://rmgsc.cr.usgs.gov/outgoing/GeoMAC/historic_fire_data/
- [20] <https://github.com/zoran-cuckovic/QGIS-visibility-analysis>
- [21] Cuckovic, (2016). Advanced viewshed analysis: A Quantum GIS plug-in for the analysis of visual landscapes. *Journal of Open Source Software*, 1(4), 32, doi:10.21105/joss.00032
- [22] <http://nhlr.org/nhnr.org/lookouts/us/ca/paradise-craggy-lookout/>
- [23] <http://nhlr.org/nhnr.org/lookouts/us/or/parker-mountain-lookout/>
- [24] <http://www.firelookout.com/or/chasemtn.html>
- [25] <http://nhlr.org/nhnr.org/lookouts/us/or/soda-mountain-lookout/>
- [26] <https://evsolutions.biz/hardware/>
- [27] Kucuk, Omer, Topaloglu, Ozer, Altunel, Arif, Çetin, Mehmet. (2017). Visibility analysis of fire lookout towers in the Boyabat State Forest Enterprise in Turkey. *Environmental Monitoring and Assessment*. 189. 10.1007/s10661-017-6008-1.
- [28] Heyns, A., du Plessis, W., Kosch, M., Hough, G., “Optimisation of tower site locations for camera-based wildfire detection systems,” *International Journal of Wildland Fire*. Preprint (2019).
- [29] Rodrigues, M., Alcasena, F., Vega-Garcia, C., “Modeling initial attack success of wildfire suppression in Catalonia, Spain,” *Science of the Total Environment* **666**: 915-927 (2019).
- [30] <http://www.alertwildfire.org/>
- [31] https://www.goes-r.gov/education/docs/fs_fire.pdf
- [32] http://cimss.ssec.wisc.edu/goes_r/meetings/awg2010/Presentations/0608_145_Schmidt.pdf
- [33] <http://www.cstarsd3s.ucdavis.edu/systems/goes-efd>
- [34] Alexander Koltunov, Susan L. Ustin, Brad Quayle, Brian Schwind, Vincent G. Ambrosia, Wei Li, “The development and first validation of the GOES Early Fire Detection (GOES-EFD) algorithm,” *Remote Sensing of Environment*, Volume **184**, 2016, Pages 436-453.
- [35] Donovan, G.H., Brown, T.C., “Be careful what you wish for: the legacy of Smokey Bear,” *Front Ecological Environment* **5**(2): 73-79 (2007).
- [36] Christiansen, Victoria, “Opportunities to Improve the Wildland Fire System,” *Fire Continuum Conference*, May 21, 2018.
- [37] Keating, E.G., Morral, A.R., Price, C.C., Woods, D., Norton, D.M., Panis, C., Saltzman, E., and Sanchez, R., “Air Attack Against Wildfires: Understanding U.S. Forest Service Requirements for Large Aircraft,” RAND Corporation, 2012.
- [38] <https://www.nwcg.gov/sites/default/files/data-standards/pdf/values.pdf>
- [39] Fried, J.S. and Fried, B.D., “Simulating Wildfire Containment with Realistic Tactics,” *Forest Science* **42**: 267-281 (1996).
- [40] Heinsch, F.A. and Andrews, P.L., “BehavePlus Fire Modeling System, Version 5.0: Design and Features,” USDA Forest Service Rocky Mountain Research Station, General Technical Report RMRS-GTR-249, December 2010.
- [41] Reimer, J., Thompson, D. K., Povak, N., “Measuring Initial Attack Suppression Effectiveness through Burn Probability,” *Fire* **2**(4): 60 (2019).
- [42] Hirsch, K.G., Corey, P.N., and Martell D.L., “Using Expert Judgment to Model Initial Attack Fire Crew Effectiveness,” *Forest Science* **44**: 539-549 (1998).
- [43] Rothermel, R.C., “A Mathematical Model for Predicting Fire Spread in Wildland Fuels,” USDA Forest Service, Research Paper Int-115, January 1972.
- [44] Albini, F.A., “Estimating Wildfire Behavior and Effects,” USDA Forest Service General Technical Report Int-30, 1976.

- [45] Richards, G.D., "A General Mathematical Framework for Modelling Two-Dimensional Wildland Fire Spread, *International Journal of Wildland Fire* **5**: 63-72 (1995).
- [46] Anderson, H.E., "Predicting wind-driven wild land fire size and shape," United States Department of Agriculture Forest Service, Intermountain Forest and Range Experiment Station, Research Paper INT-RP-305, 1983.
- [47] Van Wagner, C.E., "Conditions for the Start and Spread of Crown Fire," *Canadian Journal of Forest Research* **7**: 23-34 (1977).
- [48] Cruz, M. G., Alexander, M. E., and Wakimoto, R.H., "Development and testing of models for predicting crown fire rate of spread in conifer forest stands," *Canadian Journal of Forest Research* **35**: 1626–1639 (2005).
- [49] Sethian, J.A., "A fast marching level set method for monotonically advancing fronts," *Proceedings of the National Academy of Sciences* **93**: 1591-1595 (1996).
- [50] nwcg.gov/course/ffm/vert-horiz-and-slope/41-flame-length
- [51] Rollins, M.G., "LANDFIRE: a nationally consistent vegetation, wildland fire, and fuel assessment," *International Journal of Wildland Fire* **18**: 235-249 (2009).
- [52] <http://landfire.cr.usgs.gov/viewer/>
- [53] Scott, J.H. and Burgan, R.E., "Standard Fire Behavior Fuel Models: A Comprehensive Set for Use with Rothermel's Surface Fire Spread Model," United States Department of Agriculture Forest Service, Rocky Mountain Research Station, General Technical Report RMRS-GTR-15 (2005).
- [54] <https://www.fs.fed.us/pnw/fera/fft/fccsmodule.shtml>
- [55] National Centers for Environmental Prediction/National Weather Service/NOAA/U.S. Department of Commerce: NCEP North American Regional Reanalysis (NARR). Research Data Archive at the National Center for Atmospheric Research, Computational and Information Systems Laboratory. Dataset. <http://rda.ucar.edu/datasets/ds608.0/>.
- [56] Fosberg, M.A., "Weather in Wildland Fire Management: The Fire Weather Index," *Conference on Sierra Nevada Meteorology*, American Meteorological Society, pp. 1-4 (1978).
- [57] Simard, A.J., "The Moisture Content of Forest Fuels – 1. A Review of the Basic Concepts," Canadian Department of Forest and Rural Development, Forest Fire Research Institute, Information Report FF-X-14, Ottawa, Ontario, 47 pp.
- [58] Goodrick, S.L., "Modification of the Fosberg fire weather index to include drought," *International Journal of Wildland Fire* **11**: 205-211 (2002).
- [59] Schroeder, M.J., "Ignition probability," USDA Forest Service. Fort Collins, CO. RMRS unpublished report, 1969.

APPENDIX B – SPATIAL INFORMATICS GROUP, REVIEW OF REAX ANALYSIS

June 24, 2020

Richard Roos-Collins
Water and Power Law Group
2140 Shattuck Avenue, Ste. 801
Berkeley, CA 94704

Dear Mr. Roos-Collins:

At your request, Spatial Informatics Group (SIG) has reviewed Appendix A to the *Lower Klamath Project FERC No. 14803 Fire Management Plan*. This Appendix was prepared for KRRC by Reax Engineering and is entitled "Quantitative Wildfire Risk Analysis of the Klamath River Renewal Project." Our review involved an iterative process of comments by SIG followed by revisions by Reax. You asked for a peer review and an opinion letter regarding the adequacy of the data, methods, and conclusions in the risk analysis. Review was conducted in May and June of 2020. This opinion letter refers to the final draft document, dated June 5, 2020.

The Appendix covers important information and analysis related to the assessment of change in fire risk resulting from the removal of four dams along the Klamath River and adjacent areas following the implementation of the Klamath Hydroelectric Settlement Agreement. It considers factors such as fire history, post-dam removal vegetative re-growth, changes to firefighting water availability, changes to ignition sources, and possible additional fire risk mitigation efforts. It finds that dam removals will not adversely affect water availability for suppression or burn probability. It also finds that cameras can be effectively used for early fire detection and will help decrease burn probability and increase the probability of containment in the event of a fire.

SIG has reviewed the document with respect to several factors: methods used in analysis and modeling, literature cited, assumptions made, data used, and effectiveness of visualizations and writing. We find that REAX's results and conclusions are based on appropriate data and methods and are consistent with industry standards and best practices. Reax appropriately and correctly applied methods and procedures to all tasks, including: inventorying and mapping fire history and perimeters, assessing ignition sources, running wildfire simulation models, calculating fire suppression water availability changes, simulating fire detection interventions through viewshed analysis, and estimating changes to burn and containment probabilities. Data on key factors, such as fire weather, fuels, and burn history, were appropriately sourced and used. Literature was appropriately cited and we felt that visualizations and writing were of good quality.

In sum, SIG affirms that Reax's Appendix Report meets all the standards expected for professional consulting in this field. We are available for questions or clarifications if needed.

Sincerely,

A handwritten signature in black ink, appearing to read "Austin Troy", is placed above the printed name.

Austin Troy, PhD
Principal, Spatial Informatics Group
802-734-6248
atroy@sig-gis.com

APPENDIX C – AGENCY APPROVAL LETTERS

**DEPARTMENT OF FORESTRY AND FIRE PROTECTION**

P.O. Box 944246
SACRAMENTO, CA 94244-2460
(916) 653-7772
Website: www.fire.ca.gov



January 12, 2021

Kimberly D. Bose, Secretary
Federal Energy Regulatory Commission
888 First Street, N.E.
Washington, D.C. 20426

Re: Fire Management Plan, Lower Klamath Project, FERC No. 14803

Dear Secretary Bose:

The California Department of Forestry and Fire Protection (CAL FIRE) has reviewed the Fire Management Plan (July 2020) prepared by the Klamath River Renewal Corporation (KRRC) to support the KRRC's and PacifiCorp's proposed removal of four dams in the Lower Klamath Project (FERC P-14803).

The Fire Management Plan thoroughly details the KRRC's overall plan to offset any loss of water available for firefighting purposes due to removal of four dams. Appendix A of the plan, which provides an independent quantitative analysis of wildfire risks associated with the project, was prepared by REAX, a fire analytics firm.

The KRRC's proposed investments include: providing a system of remote cameras that will allow better pinpointing of fire start locations as well as monitoring of fires; helicopter water drafting locations from the Klamath River suitable for helicopter access; continued operation of a gravity-fed hydrant system; a system of dry hydrants and revamped boat launches appropriate for fire engine access and drafting; and numerous portable dip tanks.

Firefighting agencies always need as many water sources as possible for firefighting purposes. Nevertheless, CAL FIRE believes the system of actions proposed in the Fire Plan are adequate to manage construction-related fire risks, comply with all applicable laws, and will not adversely affect CAL FIRE's ability to provide an adequate and effective firefighting capability in Siskiyou County and beyond. CAL FIRE concludes that Reax's analysis of the incremental risks associated with dam removal project is accurate.

Please contact Chief Mike Bradley at (530) 224-2460 if you have any additional questions.

Sincerely,

THOMAS W. PORTER
Director

cc: Wade Crowfoot, Secretary, California Natural Resources Agency
Katie Wheeler Mathews, Senior Advisor, Federal Affairs, Office of the California Governor
Mike Bradley, Northern Region Chief, CAL FIRE
Mark Bransom, CEO, Klamath River Renewal Corporation



Oregon

Kate Brown, Governor

Department of Forestry
Klamath - Lake District
3200 Delap Rd
Klamath Falls, OR 97601-5211
(541) 883-5681
Fax: (541) 883-5555



Kimberly D. Bose, Secretary
Federal Energy Regulatory Commission
888 First Street, N.E.
Washington, D.C. 20426

CC: Klamath River Renewal Corporation

Re: **Fire Management Plan, Lower Klamath Project, FERC No. 14803**

Dear Secretary Bose:

This agency has reviewed the Klamath River Renewal Corporation's Fire Management Plan (July 2020) for the proposed removal of four dams in the Lower Klamath Project (FERC P-14803).

In remaining sustained from the proposed project outcomes, we agree with the plan's analysis of wildfire risks and fire-suppression resources in the area. We conclude that its analysis of the incremental risks associated with dam removal project is accurate.

We have also reviewed the measures that the plan proposes as part of the dam removal project. These measures are adequate to manage construction-related fire risks, comply with all applicable laws, and cooperate with local and regional fire agencies to help manage long-term wildfire risk in the Klamath River Basin.

Sincerely,

Randall Baley, Klamath Protection Unit Forester

Oregon Department of Forestry

Lee Winslow, Medford Protection Unit Forester

Oregon Department of Forestry

www.klamathrenewal.org

Appendix E

Consultation Record

Consultation Record

Water Supply Management Plan			
Sub-Plan	Agency	Date of Agency Plan Submittal	Agency Comments Received Date
Fire Management Plan	California State Water Resources Control Board	January 18, 2021	No Comments Received
	California Department of Fish and Wildlife	January 18, 2021	No Comments Received
	Cal Fire Siskiyou County	July 7, 2020	July 12, 2020
	Oregon Department of Forestry	July 7, 2020	July 14, 2020
Oregon Groundwater Well Management Plan	Oregon Department of Environmental Quality	January 18, 2021 August 4, 2021	February 3, 2021 September 7, 2021
California Water Supply Management Plan	California State Water Resources Control Board	January 18, 2021 August 4, 2021	April 30, 2021 September 7, 2021
	California Department of Fish and Wildlife	January 18, 2021 August 4, 2021	No Comments Received No Comments Received
	California Department of Water Resources	August 4, 2021	No Comments Received
California Public Drinking Water Management Plan	California State Water Resources Control Board	January 18, 2021 August 3, 2021	No Comments Received September 7, 2021
	California Department of Fish and Wildlife	January 18, 2021 August 3, 2021	No Comments Received No Comments Received
	California Department of Water Resources	August 3, 2021	No Comments Received